

SIGN REPLACEMENT SCHEDULE

STATION	FACING	OFFSET	SIGN	SIGN DESIGNATION	SIGN SIZE (in.)	Sign Panel Ty 1 Spl (Sq. Ft.)	Sign Panel Ty 2 Spl (Sq. Ft.)	Rem Sign Panel Assembly Ty A Spl (Each)	Rem Sign Panel Assembly Ty B Spl (Each)	No. of Posts	Telescoping Stl Sign Support (Foot)
214+43	South	25LT	No Pass Zone (Rural)	W14-3	64 x 48		10.7				
214+43	South	25LT	County Reference Marker (Symbol) (Hancock)	STATE	18 x 18	2.3			1	2	28
214+43	North	25LT	County Reference Marker (Symbol) (Hancock)	STATE	18 x 18	2.3					
219+18	West	33RT	Stop	R1-1	36 x 36		9	1		1	14
219+71	East	33LT	Stop	R1-1	36 x 36		9	1		1	14
226+57	North	25LT	Crossroad (Symbol)	W2-1	36 x 36		9	1		1	14
231+32	North	25RT	No Pass Zone (Rural)	W14-3	64 x 48		10.7		1	2	28
269+87	South	25LT	Crossroad (Symbol)	W2-1	36 x 36		9				
269+87	South	25LT	Adrian Rd. (Bow Tie)	D3-1	18 x 30	3.8			1	2	28
269+87	South	25LT	County Reference Marker (Symbol) (Hancock)	STATE	18 x 18	2.3					
269+87	North	25LT	County Reference Marker (Symbol) (Hancock)	STATE	18 x 18	2.3					
271+45	South	25LT	Adrian 2->	D1-1	24 x 48	8		1		1	14
273+03	East	25LT	Double Arrow (symbol)	W1-7	24 x 48	8		1		2	28
273+03	East	25LT	Yellow Diamond	OM1-1	18 x 18	2.3		1		1	14
273+46	West	33RT	Stop	R1-1	36 x 36		9	1		1	14
273+56	East	33LT	Stop	R1-1	36 x 36		9	1		1	14
273+56	North	33LT	< - Adrian 2	D1-1	24 x 48	8		1		2	28
278+31	North	25LT	Crossroad (Symbol)	W2-1	36 x 36		9		1	2	28
278+31	North	25LT	Adrian Rd. (Bow Tie)	D3-1	18 x 30	3.8					
320+55	South	25RT	Crossroad (Symbol)	W2-1	36 x 36		9				
320+55	South	25RT	Burnside Rd (Bow Tie)	D3-1	18 x 30	3.8			1	2	28
320+55	South	25RT	County Reference Marker (Symbol) (Hancock)	STATE	18 x 18	2.3					
320+55	North	25RT	County Reference Marker (Symbol) (Hancock)	STATE	18 x 18	2.3					
SUB TOTAL =						51.5	93.4	9	5		294

TOTAL =	155	225	24	12		728
---------	-----	-----	----	----	--	-----

*NOTE: SIGNS TO BE SUPPLIED BY THE DISTRICT 6 SIGN SHOP