

WIDENING SCHEDULE

STATION TO STATION		SUBBASE GRANULAR MATERIAL, TYPE B	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING, 10"	PAVEMENT FABRIC	PAVED SHOULDER REMOVAL
		TON	SQ YD	SQ YD	SQ YD
EB					
RT	4054+05.00 TO 4056+60.00	19.4	170.0	170.0	170.0
LT	4054+05.00 TO 4056+60.00	19.4	170.0	170.0	170.0
RT	4057+65.00 TO 4059+45.00	13.7	120.0	120.0	120.0
LT	4057+65.00 TO 4059+45.00	13.7	120.0	120.0	120.0
TOTALS		66.0	580.0	580.0	580.0

PAVEMENT MARKING SCHEDULE

STATION TO STATION		URETHANE PAVEMENT MARKING - LINE 4"	URETHANE PAVEMENT MARKING - LINE 6"	PAVEMENT MARKING REMOVAL	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL
		FOOT	FOOT	SQ FT	FOOT	SQ FT
EB						
	4054+05.00 TO 4056+60.00	510.0	63.8	170.0	45.9	15.3
	4056+60.00 TO 4057+65.00	210.0	26.3	35.0	18.9	6.3
	4057+65.00 TO 4059+45.00	360.0	45.0	120.0	32.4	10.8
TOTALS		1080.0	135.0	325.0	97.0	32.0

TRAFFIC CONTROL DEVICES

STATION TO STATION		TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3
		FOOT	FOOT	SQ FT	FOOT
STAGE I					
	EB 1054+61.00 TO 1056+25.00	162.5	0.0	1.0	0.0
	EB 1056+25.00 TO 1057+75.00	150.0	0.0	0.0	0.0
STAGE II					
	EB 1054+61.00 TO 1056+25.00	0.0	162.5	0.0	1.0
	EB 1056+25.00 TO 1057+75.00	0.0	150.0	0.0	0.0
TOTALS		313.0	313.0	1.0	1.0