

SUMMARY OF QUANTITIES

URBAN

PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	100% STATE			
				I-64 ROADWAY	I-55 ROADWAY	I-55 RETAINING WALL 082-W310	
				0005	0005	0040	
42100615	PAVEMENT REINFORCEMENT	SQ YD	12,886	9,170	3,716		
44000100	PAVEMENT REMOVAL	SQ YD	25,814	13,558	12,256		
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	4,362	4,362	0		
44000165	HOT-MIX ASPHALT SURFACE REMOVAL, 4"	SQ YD	15,100	0	15,100		
44000400	GUTTER REMOVAL	FOOT	3,398	2,551	847		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,414	437	2,977		
44000600	SIDEWALK REMOVAL	SQ FT	1,229	0	1,229		
44001980	CONCRETE BARRIER REMOVAL	FOOT	6,015	3,438	2,577		
44004000	PAVED DITCH REMOVAL	FOOT	358	358	0		
44004250	PAVED SHOULDER REMOVAL	SQ YD	20,841	12,673	8,168		
44200620	CLASS A PATCHES, TYPE II, 14 INCH	SQ YD	10	0	10		
44200624	CLASS A PATCHES, TYPE III, 14 INCH	SQ YD	16	0	16		
44200628	CLASS A PATCHES, TYPE IV, 14 INCH	SQ YD	874	225	649		
44201015	CLASS B PATCHES, TYPE I, 14 INCH	SQ YD	10	0	10		
44201019	CLASS B PATCHES, TYPE II, 14 INCH	SQ YD	84	61	23		
44201023	CLASS B PATCHES, TYPE III, 14 INCH	SQ YD	132	132	0		
44213000	PATCHING REINFORCEMENT	SQ YD	900	225	675		
44213100	PAVEMENT FABRIC	SQ YD	226	193	33		
44213200	SAW CUTS	FOOT	5,153	2,616	3,137		
44213204	TIE BARS 3/4"	EACH	2,638	1,250	1,388		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2,890	2,178	712		
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SQ YD	4,622	0	4,622		
48300510	PORTLAND CEMENT CONCRETE SHOULDERS 10 1/2"	SQ YD	1,380	2,196	4,584		
48300710	PORTLAND CEMENT CONCRETE SHOULDERS 12 1/2"	SQ YD	11,946	11,290	656		
48300820	PORTLAND CEMENT CONCRETE SHOULDERS 14"	SQ YD	1,499	0	1,499		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1	0	1		
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1	0	1		
50100500	REMOVAL OF EXISTING STRUCTURES NO. 3	EACH	1	0	1		
50100600	REMOVAL OF EXISTING STRUCTURES NO. 4	EACH	1	0	1		

• DENOTES SPECIALTY ITEM

FILE NAME = DBTRI-76C52-sht-500-02.dgn	USER NAME = searab	DESIGNED SH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN BS	REVISED -			•	82-1-R(A), 82-1-R(B)	ST. CLAIR	629	6
	PLOT SCALE = 2.0000' / 1" =	CHECKED OP	REVISED -		SCALE: NONE					
	PLOT DATE = 2/6/2012	DATE 1-20-12	REVISED -		SHEET NO. 2 OF 10 SHEETS	STA.	TO STA.			CONTRACT NO. 76C52
						FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			