

SUMMARY OF QUANTITIES

URBAN

				100% STATE		
				I-64 ROADWAY	I-55 ROADWAY	I-55 RETAINING WALL 082-W310
PAY ITEM NO.	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0005	0005	0040
X6022830	MANHOLES, SANITARY, 6"-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	0	1	
X6026054	SANITARY MANHOLES TO BE REMOVED	EACH	1	0	1	
X6350120	DEL NEATOR REMOVAL	EACH	216	165	51	
X6370050	CONCRETE BARRIER WALL (SPECIAL)	FOOT	469	279	190	
X6370279	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT (SPECIAL)	FOOT	4,680	1,240	3,440	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.5	0.5	
* X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	153,564	114,733	38,831	
* X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 INCH	FOOT	20,801	9,005	11,796	
* X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 INCH	FOOT	2,323	745	1,578	
X7040650	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	2,975	1,786	1,189	
X7330076	BRIDGE MOUNTED SIGN SUPPORT	EACH	2	0	2	
X7340100	CONCRETE FOUNDATIONS, GROUND MOUNT	CU YD	6.3	6.3	0.0	
* X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	17,176	9,174	8,002	
* X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	7,408	3,873	3,535	
* X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	1,406	347	1,059	
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	11	0	11	
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	52			52
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	60			60
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5	
Z0019800	EARTH DITCH BERM	EACH	9	9	0	
Z0022800	FENCE REMOVAL	FOOT	1,896	439	1,457	
Z0024110	FILL DEEP WELL	EACH	2	0	2	
Z0024112	WELL CONTROL CENTER MODIFICATIONS	L SUM	1	1	0	
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	7	5	2	
* Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	6	1	5	
* Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	9	7	2	
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	940			940

* DENOTES SPECIALTY ITEM

FILE NAME = DBTRI-76C52-sht-500-09.dgn

USER NAME = sea-sb

PLOT SCALE = 2.0000' / in.

PLOT DATE = 2/6/2012

DESIGNED SH

DRAWN BS

CHECKED OP

DATE 1-20-12

REVISED -

REVISED -

REVISED -

REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: NONE SHEET NO. 9 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	82-1-R(A), 82-1-R(B)	ST. CLAIR	629	13
* 64/998/70		CONTRACT NO. 76C52		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		