

CURVES RAMP P-2, 3 & 4

	Station	Cross Slope %	RIGHT EOP ELEVATION	RAMP WIDTH (FEET)	LEFT EOP ELEVATION	COMMENTS
FULL SE	21+50.00	-2.20%	411.80	16.00	411.45	PROJECT LIMIT: MEET 76C76
	21+75.00	-2.20%	411.01	16.00	410.66	
	22+00.00	-2.20%	410.29	16.00	409.94	
	22+25.00	-2.20%	409.63	16.00	409.28	
	22+50.00	-2.20%	409.03	16.00	408.68	
	22+75.00	-2.20%	408.50	16.00	408.15	
	23+00.00	-2.20%	408.03	16.00	407.68	
	23+25.00	-2.20%	407.63	16.00	407.28	
	23+50.00	-2.20%	407.28	16.00	406.93	
	23+75.00	-2.20%	407.01	16.00	406.66	
	24+00.00	-2.20%	406.79	16.00	406.44	
	24+25.00	-2.20%	406.65	16.00	406.30	
	24+50.00	-2.20%	406.56	16.00	406.21	
	24+75.00	-2.20%	406.54	16.00	406.19	
	25+00.00	-2.20%	406.58	16.00	406.23	
REMOVAL	25+23.92	-2.20%	406.69	16.00	406.34	END FULL SUPERELEVATION / BEGIN TRANSITION
	25+25.00	-2.23%	406.69	16.00	406.33	
	25+50.00	-3.02%	406.86	16.00	406.38	
	25+61.92	-3.40%	406.97	16.00	406.43	PCC - END TRANSITION / BEGIN FULL SUPERELEVATION
FULL SE	25+75.00	-3.40%	407.10	16.00	406.56	
	26+00.00	-3.40%	407.40	16.00	406.86	
	26+25.00	-3.40%	407.76	16.00	407.22	
	26+50.00	-3.40%	408.15	16.00	407.61	
	26+75.00	-3.40%	408.63	16.00	408.09	
	27+00.00	-3.40%	409.17	16.00	408.63	
	27+25.00	-3.40%	409.77	16.00	409.23	
	27+50.00	-3.40%	410.46	16.00	409.92	
	27+75.00	-3.40%	411.24	17.97	410.63	
	28+00.00	-3.40%	412.02	17.54	411.42	
	28+25.00	-3.40%	412.85	17.10	412.27	
	28+50.00	-3.40%	413.68	16.66	413.11	
	28+75.00	-3.40%	414.52	16.22	413.97	
	29+00.00	-3.40%	415.35	15.78	414.81	
	29+25.00	-3.40%	416.19	15.34	415.67	
29+50.00	-3.40%	417.02	14.90	416.51		
29+75.00	-3.40%	417.86	14.45	417.37		
30+00.00	-3.40%	418.69	14.01	418.21		

RAMP P CONTINUED

	Station	Cross Slope %	RIGHT EOP ELEVATION	RAMP WIDTH (FEET)	LEFT EOP ELEVATION	COMMENTS
FULL SE	30+25.00	-3.40%	419.52	13.56	419.06	FULL SUPERELEVATION CONTINUED
	30+50.00	-3.40%	420.36	13.11	419.91	
	30+75.00	-3.40%	421.19	12.66	420.76	
	31+00.00	-3.40%	422.03	12.22	421.61	
	31+25.00	-3.40%	422.86	11.77	422.46	
	31+50.00	-3.40%	423.70	11.31	423.32	
	31+75.00	-3.40%	424.62	10.86	424.25	
	32+00.00	-3.40%	425.57	10.41	425.22	
	32+25.00	-3.40%	426.53	9.96	426.19	
	32+50.00	-3.40%	427.41	9.50	427.09	
	32+75.00	-3.40%	428.25	9.05	427.94	
	33+00.00	-3.40%	429.08	8.59	428.79	
	33+25.00	-3.40%	429.92	8.14	429.64	
	33+50.00	-3.40%	430.78	7.68	430.52	
	33+75.00	-3.40%	431.65	7.22	431.40	
34+00.00	-3.40%	432.52	6.77	432.29		
34+02.41	-3.40%	432.61	6.72	432.38	PCC	
REMOVAL	34+22.06	-3.40%	433.32	6.34	433.10	END FULL SUPERELEVATION / BEGIN TRANSITION
	34+25.00	-3.48%	433.43	6.28	433.21	
	34+50.00	-4.18%	433.43	5.71	433.19	
	34+50.94	-4.20%	434.42	5.68	434.18	END TRANSITION / BEGIN FULL SUPERELEVATION
FULL SE	34+75.00	-4.20%	435.23	5.09	435.02	
ATTAINMENT	34+85.81	-4.20%	435.53	4.83	435.33	END FULL SUPERELEVATION / BEGIN TRANSITION
	35+00.00	-3.81%	435.92	4.48	435.75	
	35+25.00	-3.11%	436.53	3.87	436.41	
	35+50.00	-2.42%	437.16	3.26	437.08	
	35+75.00	-1.72%	437.80	2.65	437.75	
	36+00.00	-1.03%	438.47	2.05	438.45	
	36+25.00	-0.33%	439.19	1.44	439.19	
	36+30.23	-0.19%	439.35	1.32	439.35	PT
	36+50.00	0.36%	439.97	0.93	439.97	
	36+75.00	1.06%	440.75	0.62	440.76	
	36+80.28	1.20%	440.93	0.55	440.94	PROJECT LIMIT: MEET EXISTING BRIDGE APPROACH SLAB