

CURVE 64W70W-1

	Station	Cross Slope %	RIGHT EOP	RAMP WIDTH	LEFT EOP	COMMENTS
ATTAINMENT	57+50.79	1.50%	395.91	16.00	396.15	END NORMAL CROWN / BEGIN TRANSITION
	57+75.00	2.26%	395.83	16.00	396.19	
	58+00.00	3.04%	395.86	16.00	396.35	
	58+25.00	3.82%	395.98	16.00	396.60	
	58+50.00	4.61%	396.21	16.00	396.95	
	58+65.79	5.10%	396.41	16.00	397.23	END TRANSITION / BEGIN FULL SUPERELEVATION
FULL SE	58+75.00	5.10%	396.56	16.00	397.37	
	59+00.00	5.10%	397.01	16.00	397.83	
	59+25.00	5.10%	397.57	16.00	398.39	
	59+50.00	5.10%	398.21	16.00	399.03	
	59+75.00	5.10%	398.84	16.00	399.65	
	60+00.00	5.10%	399.58	16.00	400.40	
	60+25.00	5.10%	400.43	16.00	401.25	
	60+50.00	5.10%	401.24	16.00	402.05	
	60+75.00	5.10%	402.06	16.00	402.87	
	61+00.00	5.10%	402.85	16.00	403.67	
REMOVAL	61+02.72	5.10%	402.94	16.00	403.76	END FULL SUPERELEVATION / BEGIN TRANSITION
	61+25.00	4.40%	403.65	16.00	404.36	
	61+50.00	3.62%	404.45	16.00	405.03	
	61+75.00	2.84%	405.25	16.00	405.71	
	62+00.00	2.05%	406.05	16.00	406.38	
	62+17.72	1.50%	406.62	16.00	406.86	END TRANSITION / BEGIN NORMAL CROWN

CURVE 64W70W-2

	Station	Cross Slope %	RIGHT EOP	RAMP WIDTH	LEFT EOP	COMMENTS
ATTAINMENT	64+40.18	1.50%	414.71	16.00	414.95	END NORMAL CROWN / BEGIN TRANSITION
	64+50.00	1.19%	415.17	16.00	415.36	
	64+75.00	0.41%	416.38	16.00	416.44	
	65+00.00	-0.37%	417.65	16.00	417.59	
	65+25.00	-1.15%	418.95	16.00	418.77	
	65+50.00	-1.93%	420.25	16.00	419.94	
	65+75.00	-2.71%	421.55	16.00	421.12	
	66+00.00	-3.49%	422.85	16.00	422.30	
	66+25.00	-4.27%	424.16	16.00	423.47	
	66+50.00	-5.05%	425.46	16.00	424.65	
	66+61.18	-5.40%	426.04	16.00	425.17	ROADWAY LIMIT / BEGIN BRIDGE APPROACH

FILE NAME = DBTRI-76C52-sh1-SE-Table\_06.dgn

USER NAME = searab

DESIGNED KM

REVISED -

DRAWN KM

REVISED -

PLOT SCALE = 20,000' / 1"

CHECKED DBM

REVISED -

PLOT DATE = 1/24/2012

DATE 1-20-12

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUPERELEVATION EDGE OF PAVEMENT ELEVATIONS

SCALE: NONE SHEET NO. 6 OF 6 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64/998/70	82-1-R(A), 82-1-R(B)	ST. CLAIR	629	39
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 76C52	