



NOTES:

1. PRIOR TO COMMENCEMENT OF ANY WORK, THE CONTRACTOR SHALL VERIFY THE CONDITIONS OF THE PLANS WITH THE ACTUAL CONDITIONS OF THE SITE. NO REMOVAL OR RELOCATION WORK SHALL BE COMPLETED WITHOUT THE APPROVAL OF THE ENGINEER. ALL ASSOCIATED APPURTENANCES OF THE REMOVED ITEMS SHALL BECOME THE PROPERTY OF THE CONTRACTOR AND SHALL BE REMOVED OFF-SITE AND DISPOSED OF BY THE CONTRACTOR IN A LEGAL DISPOSAL SITE. IF A DISCREPANCY OCCURS FROM WHAT IS SHOWN ON THE PLANS AND/OR SPECIAL PROVISIONS, THE CONTRACTOR SHALL NOTIFY THE ENGINEER AND SECURE WRITTEN INSTRUCTION FROM THE ENGINEER PRIOR TO PROCEEDING WITH ANY PART OF THE AFFECTED WORK, FAILING TO DO SO WILL BE CONSIDERED AS THE CONTRACTOR HAVING PROCEEDED AT HIS OWN RISK AND EXPENSE.
2. THE CONTRACTOR SHALL CONFINE HIS WORK OPERATIONS TO THE AREA LOCATED WITHIN THE SITE AND AS DIRECTED BY THE ENGINEER. ANY ADJACENT AREAS DISTURBED SHALL BE RESTORED TO THE ORIGINAL CONDITION AT THE CONTRACTOR'S EXPENSE.
3. THE CONTRACTOR SHALL CONDUCT AND COORDINATE THE CONSTRUCTION OPERATIONS FOR THIS PROJECT IN SUCH A MANNER SO AS TO KEEP ALL ROADS AND STREETS OPEN TO TRAFFIC AT ALL TIMES. NO OVERNIGHT LANE CLOSURES WILL BE PERMITTED.
4. THE CONTRACTOR SHALL BE RESPONSIBLE FOR KEEPING THE SITE SECURE AT ALL TIMES DURING CONSTRUCTION.
5. THE CONTRACTOR SHALL BE RESPONSIBLE FOR CLEARING THE SITE TO BE CLEAR OF DEBRIS AND ALL RUBBISH AND PRESENT A NEAT AND CLEAN APPEARANCE ON COMPLETION OF THE PROJECT.



FILE NAME = DBTRI-76C52-Shr-Rem-19.dgn	USER NAME = searsb	DESIGNED KM	REVISED -
		DRAWN KM	REVISED -
	PLOT SCALE = 40,000' / in.	CHECKED DBM	REVISED -
	PLOT DATE = 1/24/2012	DATE 1-20-12	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

REMOVAL PLAN - BOWMAN YARD SITE CLEARING

SCALE: 1" = 20' SHEET NO. 19 OF 19 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
•	82-1-R(A), 82-1-R(B)	ST. CLAIR	629	90
• 64/998/70			CONTRACT NO. 76C52	
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			