

SIGNING REMOVAL SCHEDULE										
LOCATION	OFFSET	REMOVE SIGN PANEL TYPE 1 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY TYPE B (EA)	REMOVE SIGN PANEL TYPE 2 (SQ FT)	REMOVE SIGN PANEL TYPE 3 (SQ FT)	REMOVE OVERHEAD SIGN STRUCTURE - SPAN (EA)	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER (EA)	ELECTRICAL EQUIPMENT REMOVAL AND SALVAGE (EA)	REMOVE CONCRETE FOUNDATION - OVERHEAD (EA)	REMOVE CONCRETE FOUNDATION - GROUND MOUNT (EA)
55N64E										
67+43	-					1			4	
75+36	20' RT	1								
64W55N										
54+00	24' LT	8								
54+05	22' LT			20.0						
57+50	31' LT			12.0						
58+37	31' LT			12.0						
59+37	31' LT			12.0						
64E										
27+39	-					1			4	
64W										
68+99	0'			21.0						
92+95	0'			21.0						
110+78	-					1			4	
MILE MARKER 4.4	0			21.0						
I-64 SUBTOTAL		9	0	119.0	0.0	3	0	0	12	0

55N										
61+07	LT/RT							1		
72+71	59' RT			16.0						
74+49	46' RT			16.0						
79+57	74' RT				168.0					2
81+83	78' RT				100.0					2
82+46	65' RT			16.0						
82+87	111' RT			15.0						
87+69	72' RT				90.0					2
90+68	63' RT						1		1	
64W55N										
57+16	LT/RT					1			4	
58+73	66' LT			12.0						
59+31	64' LT			12.0						
59+71	59' LT			12.0						
68+75	0'			12.0						
78+19.81	0'			18.0						
55S										
71+84	LT/RT					1			4	
74+44	86' RT		1							
78+05	26' RT			12.0						
78+81	26' RT	7.5								
81+84	15' RT			11.0						
83+43	LT/RT					1			4	
111+05	LT/RT							1		
MP 4.04				20.0						
MP 4.28				20.0						
I-55 SUBTOTAL		7.5	1	192.0	358.0	3	1	2	13	6
TOTAL		17	1	311	358	6	1	2	25	6

DELINEATOR SCHEDULE		
ALIGNMENT	STATION	DELINEATOR (EA)
55N64E	61+96 TO 69+44	9
64E	32+31 TO 44+43	10
64E	57+57 TO 60+57	3
64W55N	50+00 TO 60+25	103
64W55N	50+00 TO 53+25	7
64W55S	123+65 TO 131+50	10
70E64E	65+23 TO 74+13	9
70E64E	65+23 TO 69+00	4
RAMP A	10+30 TO 11+44	11
I-64 SUBTOTAL		165

I-64 QUANTITIES		
ALIGNMENT	STATION	DELINEATOR
55N		3
55S		10
64W55N		30
RAMP O		5
RAMP P		3
I-55 SUBTOTAL		51
TOTAL		216

DELINEATOR REMOVAL SCHEDULE		
ALIGNMENT	STATION	DELINEATOR (EA)
55N64E	61+96 TO 69+44	9
64E	32+31 TO 44+43	10
64E	57+57 TO 60+57	3
64W55N	50+00 TO 60+25	103
64W55N	50+00 TO 53+25	7
64W55S	123+65 TO 131+50	10
70E64E	65+23 TO 74+13	9
70E64E	65+23 TO 69+00	4
RAMP A	10+30 TO 11+44	11
I-64 SUBTOTAL		165

I-64 QUANTITIES		
I-55N		3
I-55S		10
I-64W/55N		30
RAMP O		5
RAMP P		3
I-55 SUBTOTAL		51
TOTAL		216

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL SCHEDULE		
LOCATION	ONE WAY CRYSTAL (EA)	
64W70W		
53+48.43 TO 61+46.65	20	
61+46.64 TO 64+00.00	6	
64+00.00 TO 64+87.96	2	
64W55		
61+96.34 TO 69+00.00	38	
64W55N		
50+00.00 TO 53+34.92	24	
53+24.92 TO 60+26.00	18	
64W		
105+00.00 TO 119+00.00	35	
105+15.26 TO 109+10.42	30	
82+56.64 TO 90+00.00	36	
90+00.00 TO 105+00.00	75	
64E		
26+70.53 TO 38+00.00	40	
34+31.62 TO 38+00.00	18	
38+00.00 TO 43+85.22	29	
38+00.00 TO 53+00.00	75	
57+56.03 TO 60+56.70	15	
60+49.34 TO 53+00.00	38	
60+54.89 TO 58+88.72		
70E64E		
65+23.00 TO 76+13.08	55	
55N55E		
69+00.00 TO 71+66.61	7	
RAMP A		
10+29.83 TO 11+44.22	3	
9+73.02 TO 11+44.22	9	
I-64 SUBTOTAL		572

I-64 QUANTITIES		
LOCATION	ONE WAY CRYSTAL (EA)	
55N		
64+50 TO 90+84	132	
82+28 TO 90+84	11	
55S		
68+68 TO 99+68	156	
70+91 TO 73+92	8	
68+68 TO 76+23	20	
64W55N		
67+91 TO 72+05	5	
	31	
RAMP O		
10+18 TO 14+27	20	
12+38 TO 15+35	8	
I-55 SUBTOTAL		363
TOTAL		935