

HBP: 80% FED & 20% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE					
				0003	0010				
50300265	SEAL COAT CONCRETE	CU YD	2065.2		2065.2				
50300280	CONCRETE ENCASEMENT	CU YD	60.2		60.2				
50300300	PROTECTIVE COAT	SQ YD	6,690		6,690				
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1				
50500505	STUD SHEAR CONNECTORS	EACH	15,504		15,504				
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1,192,890		1,192,890				
50800515	BAR SPLICERS	EACH	199		199				
50800530	MECHANICAL SPLICERS	EACH	3,248		3,248				
50901735	BRIDGE FENCE RAILING (SIDEWALK)	FOOT	575		575				
50901750	PARAPET RAILING	FOOT	571		571				
51201800	FURNISHING STEEL PILES HP14X73	FOOT	9,798		9,798				
51201900	FURNISHING STEEL PILES HP14X89	FOOT	9,435		9,435				
51202305	DRIVING PILES	FOOT	19,233		19,233				
51203800	TEST PILE STEEL HP14X73	EACH	8		8				

* SPECIALTY ITEM

FILE NAME =	USER NAME = default	DESIGNED -	REVISED -
m:\28018\mcr\station\0phase1\0978056-1	t-500.dgn	DRAWN -	REVISED -
	PLOT SCALE = 100.0000 / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/25/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITY SHEETS
IL RTE 13 OVER BIG MUDDY RIVER

SCALE: SHEET NO. 4 OF 10 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(12-1)-B-1	JACKSON	200	6
CONTRACT NO. 78056				
ILLINOIS FED. AID PROJECT				