

CONSTRUCTION CODE

| CODE NO. | ITEM | UNIT | TOTAL QUANTITY | CONSTRUCTION CODE | | | | | |
|----------|---|-------|----------------|-------------------|-------|--|--|--|--|
| | | | | 0003 | 0010 | | | | |
| 51203900 | TEST PILE STEEL HP14X89 | EACH | 4 | | 4 | | | | |
| 51500100 | NAME PLATES | EACH | 2 | | 2 | | | | |
| 52000110 | PREFORMED JOINT STRIP SEAL | FOOT | 217 | | 217 | | | | |
| 52100010 | ELASTOMERIC BEARING ASSEMBLY, TYPE I | EACH | 12 | | 12 | | | | |
| 52100020 | ELASTOMERIC BEARING ASSEMBLY, TYPE II | EACH | 24 | | 24 | | | | |
| 52100520 | ANCHOR BOLTS, 1" | EACH | 120 | | 120 | | | | |
| 52100540 | ANCHOR BOLTS, 1 1/2" | EACH | 24 | | 24 | | | | |
| 542A0217 | PIPE CULVERTS, CLASS A, TYPE 1 12" | FOOT | 501 | 501 | | | | | |
| 54213657 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12" | EACH | 1 | 1 | | | | | |
| 54213669 | PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" | EACH | 1 | 1 | | | | | |
| 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | FOOT | 8 | 8 | | | | | |
| 550A0120 | STORM SEWERS, CLASS A, TYPE 1 24" | FOOT | 48 | 48 | | | | | |
| 55100500 | STORM SEWER REMOVAL 12" | FOOT | 240 | 240 | | | | | |
| 58700300 | CONCRETE SEALER | SQ FT | 2,387 | | 2,387 | | | | |

* SPECIALTY ITEM

| | | | |
|---------------------------------|-------------------------------|------------|-----------|
| FILE NAME = | USER NAME = default | DESIGNED - | REVISED - |
| m:\28018\microstation\0978056-1 | 12-500.dgn | DRAWN - | REVISED - |
| | PLOT SCALE = 100.0000 ' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 1/25/2012 | DATE - | REVISED - |

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITY SHEETS
IL RTE 13 OVER BIG MUDDY RIVER

SCALE: SHEET NO. 5 OF 10 SHEETS STA. TO STA.

| | | | | |
|---------------------------|------------|---------|--------------|-----------|
| F.A.P. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 331 | (12-1)-B-1 | JACKSON | 200 | 7 |
| CONTRACT NO. 78056 | | | | |
| ILLINOIS FED. AID PROJECT | | | | |