HBP: 80% FED & 20% STATE

	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0003	0010				
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1,063	1,063					
*	78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	2,477	2,477					
*	78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	309	309					
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	175	175					
*	78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	32	32					
*	78200420	GUARDRAIL MARKERS, TYPE B	EACH	17	17					
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	6	6					
*	78200520	BARRIER WALL MARKERS, TYPE B	EACH	29	29					
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	1,649	1,649					
	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	155	155					
*	81028760	UNDERGROUND CONDUIT, COILABLE NONMETALIC CONDUIT, 2 1/2" DIA.	FOOT	182	182					
*	81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1,025	1,025					
*	81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12" X 10" X 6"	EACH	4	4					
*	81300610	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 14" X 12" X 6"	EACH	1	1					
*	81603030	UNIT DUCT, 600V, 2-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1" DIA. POLYETHYLENE	FOOT	1,102	1,102					

* SPECIALTY ITEM

FILE NAME = m:\28018\microstation\@phase1\D978056-sht-500.dgn	USER NAME = default	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 1/25/2012	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANITY SHEETS
IL RTE 13 OVER BIG MUDDY RIVER

SCALE: | SHEET NO. 8 OF 10 SHEETS | STA. | TO STA.

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(12-1)-8-1	JACKSON	200	10

CONTRACT NO. 78056

ILLINOIS FED. AID PROJECT