

HBP: 80% FED & 20% STATE

CONSTRUCTION CODE

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE			
				0003	0010		
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	1,025	1,025			
* 81702140	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 4	FOOT	2,050	2,050			
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	8	8			
* 83002200	LIGHT POLE, ALUMINUM, 40 FT. M.H., 6 FT. DAVIT ARM	EACH	6	6			
* 83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	2	2			
* 83600355	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 6'	EACH	2	2			
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	8	8			
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	5	5			
84200804	REMOVAL OF POLE FOUNDATION	EACH	3	3			
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5	0.5		
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	4		4		
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	340		340		
Z0075400	TIE RODS	EACH	30		30		
+ Z0076600	TRAINEES	HOUR	2,000		2,000		
X0321809	PERMANENT GROUND ANCHOR	EACH	30		30		

* SPECIALTY ITEM +0042

FILE NAME =	USER NAME = Invenderba	DESIGNED -	REVISED -
ct:\pwwork\pwwork\Invenderba\0297265\0778056-sht-500.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITY SHEETS
IL RTE 13 OVER BIG MUDDY RIVER

SCALE: SHEET NO. 9 OF 10 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	12-1-B-1	JACKSON	200	11
CONTRACT NO. 78056				
ILLINOIS FED. AID PROJECT				