

SUMMARY OF QUANTITIES			STP FUNDING
CODE NO.	ITEM	UNIT	80% FEDERAL 20% STATE 0011
50300225	CONCRETE STRUCTURES	CU YD	53.4
50300255	CONCRETE SUPERSTRUCTURE	CU YD	243.2
50300260	BRIDGE DECK GROOVING	SQ YD	524
50300280	CONCRETE ENCASEMENT	CU YD	4.2
50300300	PROTECTIVE COAT	SQ YD	664
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1
50500505	STUD SHEAR CONNECTORS	EACH	984
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	59660
50800515	BAR SPLICERS	EACH	610
51100300	SLOPE WALL 6"	SQ YD	106
51201610	FURNISHING STEEL PILES HP12X63	FOOT	366
51202305	DRIVING PILES	FOOT	366

SUMMARY OF QUANTITIES			STP FUNDING
CODE NO.	ITEM	UNIT	80% FEDERAL 20% STATE 0011
51204650	PILE SHOES	EACH	12
51500100	NAME PLATES	EACH	1
52100520	ANCHOR BOLTS, 1"	EACH	24
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	81
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	425
* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	1
63200310	GUARDRAIL REMOVAL	FOOT	729
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	1

* SPECIALTY ITEM

FILE NAME :	USER NAME : #USER#	DESIGNED -	REVISED -
c:\pwworksp\p101\lavenderba\0293530\078165-sh1-004-soq.dgn		DRAWN - CFC	REVISED -
		CHECKED - CCJ	REVISED -
		DATE - / /	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

CB Coombe-Bloxdorf P.C.
- CIVIL ENGINEERS -
- STRUCTURAL ENGINEERS -
- LAND SURVEYORS -
Design Firm License No. 184-002703

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	6B-3	POPE	41	4
CONTRACT NO. 78165				
ILLINOIS FED. AID PROJECT				