

WORK ZONE PAVEMENT MARKING REMOVAL SCHEDULE		
LOCATION STATION TO STATION	LENGTH (FT)	70301000 REMOVAL (SQ FT)
		SHORT-TERM EDGE LINES STA 1369+53.00 TO 1377+02.40 PRIOR TO SURF CSE
SHORT-TERM SKIP-DASH STA 1369+53.00 TO 1377+02.40 PRIOR TO SURF CSE	749.4	26
TEMPORARY EDGE LINES STA 1369+53.00 TO 1377+02.40 PRIOR TO FINAL MKG	749.4	500
TEMPORARY SKIP-DASH STA 1369+53.00 TO 1377+02.40 PRIOR TO FINAL MKG	749.4	62
<b>TOTAL</b>		<b>613</b>

STONE RIPRAP SCHEDULE			
APPROXIMATE STATION	LT/RT	28100107 STONE RIPRAP, CL A4 SQ YD	28200200 FILTER FABRIC SQ YD
		1372+48.5	LT
1372+48.5	RT	97	97
<b>TOTAL</b>		<b>183</b>	<b>183</b>

PAINT PAVEMENT MARKING SCHEDULE				
LOCATION STATION TO STATION (FROM STOP BAR TO STOP BAR)	LENGTH FT	78001110		70300220
		4" YELLOW SKIP-DASH FT	4" WHITE SOLID FT	4" TEMP PVT MARKING LN FT
IL 146 STA 1369+53.00 TO STA 1377+02.40	749.40	187.3	1498.8	1686.1
<b>TOTAL</b>	<b>749.4</b>	<b>1686</b>		<b>1686</b>

GUARDRAIL REMOVAL SCHEDULE	
LOCATION	63200310 GUARDRAIL REMOVAL FT
SE QUADRANT SN 076-0026	220
NE QUADRANT SN 076-0026	184
SW QUADRANT SN 076-0026	178
NW QUADRANT SN 076-0026	147
<b>TOTAL</b>	<b>729</b>

PAVEMENT MARKING REMOVAL SCHEDULE		
LOCATION STATION TO STATION	LENGTH FT	78300100 REMOVAL SQ FT
		CENTERLINE (4") STA 1369+53 TO STA 1377+02.40
EDGE LINES (4") STA 1369+53 TO STA 1377+02.40	749.4	499.60
<b>TOTAL</b>		<b>562</b>

STATION	GUARDRAIL SCHEDULE					
	63000001	63100085	63100167	63100169	78200410	78201000
	SPBGR TY A FOOT	TBT TY 6 EACH	TBT TY 1, SP - TANG EACH	TBT TY 1, SP - FL EACH	G/R MKR TY A EACH	TERM MKR DIR. APP. EACH
LT STA 1370+57.86 TO STA 1371+07.86			1			1
LT STA 1371+07.86 TO STA 1372+20.36	112.5				2	
LT STA 1372+20.36 TO STA 1372+66.00		1			1	
LT STA 1373+86.00 TO STA 1374+31.64		1				
LT STA 1374+31.64 TO STA 1375+81.64	150				2	
LT STA 1375+81.64 TO STA 1376+31.64			1		1	1
RT STA 1371+20.36 TO STA 1371+70.36				1		1
RT STA 1371+70.36 TO STA 1372+20.36	50.0				1	
RT STA 1372+20.36 TO STA 1372+66.00		1			1	
RT STA 1373+86.00 TO STA 1374+31.64		1				
RT STA 1374+31.64 TO STA 1375+44.14	112.5				2	
RT STA 1375+44.14 TO STA 1375+94.14			1		1	1
<b>TOTALS</b>	<b>425</b>	<b>4</b>	<b>3</b>	<b>1</b>	<b>11</b>	<b>4</b>

SHORT TERM PAVEMENT MARKING SCHEDULE		
LOCATION STATION TO STATION	LENGTH FT	70300100 SHORT TERM (3 APPS) FT
		4" SKIP-DASH CENTERLINE STA 1369+53.00 TO STA 1377+02.40
SHORT-TERM EDGE LINES STA 1369+53.00 TO STA 1377+02.40	749.4	179.9
<b>TOTAL</b>		<b>405</b>

PAVEMENT SCHEDULE					
APPROX. LOCATION	WIDTH FT	LOCATION DESCRIPTION	40600982 HMA SURFACE REMOVAL BUTT JOINT SQ. YD	40300100 BIT MATERIALS (PRIME COAT) GAL	40603320 HMA SURF CSE SUPER, MIX C, N90 1-1/2" TON
			1374+39.5	26	END OF JOB
<b>TOTAL</b>			<b>87</b>	<b>8</b>	<b>7</b>

TEMPORARY RAMP SCHEDULE			
APPROX. LOCATION	WIDTH FT	DESCRIPTION	40600990 TEMPORARY RAMP SQ. YD
			1374+39.5
<b>TOTAL</b>			<b>14</b>

**CB** Coombe-Bloxdorf P.C.  
 - CIVIL ENGINEERS -  
 - STRUCTURAL ENGINEERS -  
 - LAND SURVEYORS -  
 Design Firm License No. 184-002703

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	6B-3	POPE	41	9
CONTRACT NO. 78165				

ILLINOIS FED. AID PROJECT

FILE NAME =	USER NAME = \$USER\$	DESIGNED -	REVISED -
et:\pw\work\p\idot\lavenderba\d0293530\g78165-sh1-009-schedule.dgn		DRAWN - CFC	REVISED -
	PLOT SCALE = 100.000000' / 1"	CHECKED - CCJ	REVISED -
CB PROJECT NO 08056-14	PLOT DATE = 1/23/2012	DATE - / /	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO. OF	SHEETS	STA. TO STA.