

SUMMARY OF QUANTITIES

CODE NO.	ITEM	CONSTRUCTION CODE		0031		100% LOCAL QTY
		UNIT	TOTAL QUANTITY	50% ITEP 50% LOCAL QTY	80% ITEP 20% LOCAL QTY	
20101000	TEMPORARY FENCE	FOOT	100		100	
20200100	EARTH EXCAVATION	CU YD	265		265	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	25		25	
21101685	TOPSOIL FURNISH AND PLACE, 24"	SO YD	262		262	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	3	1	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	3	1	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	3	1	
25200110	SODDING, SALT TOLERANT	SO YD	308	288	20	
25200200	SUPPLEMENTAL WATERING	UNIT	4	3	1	
28000510	INLET FILTERS	EACH	11		11	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SO YD	87		87	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	20		20	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	45		25	20
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	40			40
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	55		30	25
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	71		71	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SO FT	2,578	89	2,489	
44000100	PAVEMENT REMOVAL	SO YD	152	6	146	
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	119		119	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	145		145	
44000600	SIDEWALK REMOVAL	SO FT	1,988	89	1,899	
60600605	CONCRETE CURB, TYPE B	FOOT	627		627	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	145		145	
67100100	MOBILIZATION	L SUM	1	0.6	0.3	0.1

• SEE SPECIAL PROVISIONS

CODE NO.	ITEM	CONSTRUCTION CODE		0031		100% LOCAL QTY
		UNIT	TOTAL QUANTITY	50% ITEP 50% LOCAL QTY	80% ITEP 20% LOCAL QTY	
△ 81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	3,120	3,120		
△ 81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	70	70		
△ 81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	500	500		
△ 81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	3	3		
△ 81400730	HANDHOLE, COMPOSITE CONCRETE	EACH	2	2		
△ 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,654	6,654		
△ 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	3,639	3,639		
△ 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	2	2		
△ 84200804	REMOVAL OF POLE FOUNDATION	EACH	2	2		
△ X0326654	ORNAMENTAL LIGHT UNIT, COMPLETE	EACH	18	18		
• X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	453		254	199
• X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	0.6	0.3	0.1
△ X8100863	INTERCEPT EXISTING CONDUIT	EACH	2	2		
△ X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	17	17		
△ X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1	1		
• XX003219	UNIT PAVERS	SO FT	778		778	
△ XX007797	LUMINAIRE (SPECIAL)	EACH	34	34		
• Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.6	0.3	0.1

• SEE SPECIAL PROVISIONS

△ SPECIALTY ITEMS

FILE NAME = p:\N0240094\...Plans\sheet\ 4-summary of quantities.dgn
 PLOT DATE = 1/18/2012 7:35:07 PM

DESIGNED - K.L.R. REVISED -
 DRAWN - K.L.R. REVISED -
 CHECKED - S.M.W. REVISED -
 DATE - 1-12 REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE : NONE SHEET NO. 4 OF 14 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	10-00242-00-LT	MCLEAN	14	4
FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT	
			CONTRACT NO. 91460	