

DETECTABLE WARNINGS SCHEDULE

LOCATION	DETECTABLE WARNINGS (SQ FT)
KEEBLER ROAD	
STA. 83+58.02 - 16.58' LT TO STA. 83+68.09 - 21.58' LT	18.6
STA. 84+20.02 - 21.58' LT TO STA. 84+30.14 - 16.58' LT	18.7
STA. 90+28.49 - 17.10' LT TO STA. 90+39.06 - 21.58' LT	18.5
STA. 91+03.06 - 21.58' LT TO STA. 91+13.53 - 17.09' LT	19.1
STA. 94+93.59 - 16.58' RT TO STA. 95+04.51 - 21.58' RT	19.9
STA. 95+68.83 - 21.58' RT TO STA. 95+79.77 - 16.60' RT	20.0
STA. 100+43.42 - 16.58' LT TO STA. 100+54.79 - 21.58' LT	20.6
STA. 101+15.95 - 21.58' LT TO STA. 101+27.22 - 16.58' LT	20.5
STA. 102+03.79 - 16.23' RT TO STA. 102+15.34 - 21.58' RT	21.6
STA. 102+69.17 - 21.58' RT TO STA. 102+80.60 - 16.27' RT	21.3
STA. 106+40.92 - 16.58' LT TO STA. 106+50.76 - 21.58' LT	18.3
STA. 107+11.12 - 21.58' LT TO STA. 107+20.79 - 16.58' LT	18.1
STA. 114+88.08 - 16.58' LT TO STA. 114+99.36 - 21.58' LT	20.3
STA. 115+62.24 - 21.58' LT TO STA. 115+73.68 - 16.58' LT	20.6
STA. 116+78.87 - 17.37' RT TO STA. 116+86.20 - 21.71' RT	13.3
STA. 117+41.17 - 21.58' RT TO STA. 117+51.91 - 16.28' RT	20.2
TOTAL	310

4" PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS, 4" "DOUBLE CENTERLINE" (FOOT)
KEEBLER ROAD	
STA. 83+50.50 TO STA. 117+90.68	6880
STA. 117+13.09 - 25.44' RT TO STA. 117+13.89 - 40.00' RT	29
TOTAL	6909

12" PAVEMENT MARKING SCHEDULE

LOCATION	THERMOPLASTIC PAVEMENT MARKINGS, 12" "CROSSWALK" (FOOT)
KEEBLER ROAD	
STA. 116+80.68 - 15.32' RT TO STA. 117+45.47 - 15.82' RT	65
STA. 116+89.55 - 21.30' LT TO STA. 117+37.19 - 21.73' LT	48
TOTAL	113

PAVEMENT SCHEDULE

LOCATION	BIT MATL PR CT (GALLON)	AGGREGATE (PRIME COAT) (TON)	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90, 2 1/2" (TON)
KEEBLER ROAD			
STA. 83+50.50 TO STA. 117+90.68	705.0	20	1410.0
TOTAL	705	20	1410

SIDEWALK SCHEDULE

LOCATION	P.C.C. SIDEWALK 4" (SQ FT)
KEEBLER ROAD	
STA. 83+51.02 - 15.58' RT TO STA. 83+68.72 - 22.08' LT	77.54
STA. 84+19.39 - 22.08' LT TO STA. 84+37.14 - 15.59' LT	77.68
STA. 90+21.49 - 15.58' LT TO STA. 90+40.73 - 22.08' LT	81.99
STA. 91+0.39 - 26.84' LT TO STA. 91+21.00 - 15.58' LT	129.54
STA. 94+86.59 - 15.60' RT TO STA. 95+05.20 - 22.08' RT	80.20
STA. 95+68.13 - 22.08' RT TO STA. 95+86.73 - 15.60' RT	80.06
STA. 100+36.42 - 15.61' LT TO STA. 100+55.51 - 22.08' LT	81.58
STA. 101+15.24 - 22.08' LT TO STA. 101+35.69 - 15.58' LT	90.77
STA. 101+96.79 - 15.58' RT TO STA. 102+15.97 - 22.08' RT	126.90
STA. 102+68.54 - 22.08' RT TO STA. 102+87.60 - 15.58' RT	127.80
STA. 160+34.58 - 15.60' LT TO STA. 106+51.38 - 22.08' LT	72.38
STA. 107+10.52 - 22.08' LT TO STA. 107+26.83 - 15.61' LT	70.43
STA. 114+82.02 - 15.65' LT TO STA. 115+00.08 - 22.08' LT	74.38
STA. 115+61.51 - 22.08' LT TO STA. 115+82.38 - 15.58' LT	91.74
STA. 116+71.57 - 15.67' RT TO STA. 116+91.52 - 27.78' RT	153.36
STA. 117+39.63 - 27.03' RT TO STA. 117+59.13 - 15.58' RT	132.42
TOTAL	1549

PAVEMENT MARKING SCHEDULE

LOCATION	TYPE	THERMOPLASTIC		PREFORMED PLASTIC	TEMPORARY PAVEMENT MARKING		
		4" YELLOW (FOOT)	12" WHITE (FOOT)	24" WHITE (FOOT)	LINE 4" (FOOT)	LINE 12" (FOOT)	LINE 24" (FOOT)
KEEBLER ROAD							
STA. 83+50.50 TO STA. 117+90.68							
	STOP BAR			20			20
	CROSSWALK		113			113	
	DOUBLE CENTERLINE	6909			6909		
TOTAL		6909	113	20	6909	113	20

24" PAVEMENT MARKING SCHEDULE

LOCATION	PRFM PLSTC PAVEMENT MARKINGS, 24" "STOP BAR" (FOOT)
KEEBLER ROAD	
STA. 117+13.09 - 25.44' RT TO STA. 117+66.71 - 25.68' RT	20
TOTAL	20

CURB AND GUTTER SCHEDULE

LOCATION	TYPE B-6.24 CURB & GUTTER SCHEDULE (FOOT)
KEEBLER ROAD	
STA. 83+51.02 - 15.00' LT TO STA. 83+69.09 - 21.63' LT	19.6
STA. 84+19.02 - 21.63' LT TO STA. 84+37.14 - 15.00' LT	19.6
STA. 90+21.94 - 15.00' LT TO STA. 90+41.06 - 21.60' LT	20.5
STA. 91+01.08 - 21.60' LT TO STA. 91+20.98 - 15.00' LT	21.3
STA. 94+86.60 - 15.02' RT TO STA. 95+05.55 - 21.61' RT	20.4
STA. 95+67.79 - 21.61' RT TO STA. 95+86.71 - 15.02' RT	20.4
STA. 100+36.44 - 15.02' LT TO STA. 100+55.85 - 21.61' LT	20.8
STA. 101+14.90 - 21.61' LT TO STA. 101+35.69 - 15.00' LT	22.2
STA. 101+96.79 - 15.00' RT TO STA. 102+16.34 - 21.63' RT	21.1
STA. 102+68.17 - 21.63' RT TO STA. 102+87.60 - 15.00' RT	21.0
STA. 106+34.60 - 15.02' LT TO STA. 106+51.75 - 21.63' LT	18.8
STA. 107+10.14 - 21.63' LT TO STA. 107+26.80 - 15.02' LT	18.3
STA. 114+82.06 - 15.07' LT TO STA. 115+0.43 - 21.61' LT	19.6
STA. 115+61.17 - 21.61' LT TO STA. 115+82.38 - 15.00' LT	22.4
STA. 116+71.61 - 15.09' RT TO STA. 116+92.00 - 27.47' RT	24.9
STA. 117+40.19 - 21.64' RT TO STA. 117+59.13 - 15.00' RT	20.6
TOTAL	332

FILE NAME = combschedulesKeebler.dgn	USER NAME = ramesh	DESIGNED - BFK	REVISED -
		DRAWN - JJB	REVISED -
		CHECKED - BFK	REVISED -
		DATE - 1/17/12	REVISED -

**VILLAGE OF MARYVILLE
KEEBLER ROAD**

QUANTITY SCHEDULES

SCALE: N.T.S. SHEET NO. 1 OF 2 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9135	10-00018-00-RS	MADISON	22	6
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 97486	