CURB AND GUTTER REMOVAL SCHEDULE

LOCATION	TYPE B-6.24 CURB & GUTTER REMOVAL (FOOT)
KEEBLER ROAD	
STA. 83+51.02 - 15.00' LT TO STA. 83+69.09 - 21.63' LT	19.6
STA. 84+19.02 - 21.63' LT TO STA. 84+37.14 - 15.00' LT	19.6
STA. 90+21.94 - 15.00' LT TO STA. 90+41.06 - 21.60' LT	20.5
STA. 91+01.08 - 21.60' LT TO STA. 91+20.98 - 15.00' LT	21.3
STA. 94+86.60 - 15.02' RT TO STA. 95+05.55 - 21.61' RT	20.4
STA. 95+67.79 - 21.61' RT TO STA. 95+86.71 - 15.02' RT	20.4
STA. 100+36.44 - 15.02' LT TO STA. 100+55.85 - 21.61' LT	20.8
STA. 101+14.90 - 21.61' LT TO STA. 101+35.69 - 15.00' LT	22.2
STA. 101+96.79 - 15.00' RT TO STA. 102+16.34 - 21.63' RT	21.1
STA. 102+68.17 - 21.63' RT TO STA. 102+87.60 - 15.00' RT	21.0
STA. 106+34.60 - 15.02' LT TO STA. 106+51.75 - 21.63' LT	18.8
STA. 107+10.14 - 21.63' LT TO STA. 107+26.80 - 15.02' LT	18.3
STA. 114+82.06 - 15.07' LT TO STA. 115+0.43 - 21.61' LT	19.6
STA. 115+61.17 - 21.61' LT TO STA. 115+82.38 - 15.00' LT	22.4
STA. 116+71.61 - 15.09' RT TO STA. 116+92.00 - 27.47' RT	24.9
STA. 117+40.19 - 21.64' RT TO STA. 117+59.13 - 15.00' RT	20.6
TOTAL	332

TEMPORARY RAMP SCHEDULE

LOCATION	TEMPORARY RAMP (SQ YD)
KEEBLER ROAD	
STA. 83+50.50 TO STA. 83+58.80	24
STA. 83+58.80 LT TO STA. 83+37.69 LT	18
STA. 90+21.94 LT TO STA. 91+21.00 LT	22
STA. 94+88.90 RT TO STA. 95+84.64 RT	21
STA. 100+38.56 LT TO STA. 101+32.04 LT	21
STA. 101+97.66 RT TO STA. 102+86.94 RT	20
STA. 106+33.52 LT TO STA. 107+28.09 LT	21
STA. 114+79.78 LT TO STA. 115+82.09 LT	23
STA. 116+98.00 RT TO STA. 117+28.78 RT	29
STA. 117+82.38 TO STA. 117+90.68	24
TOTAL	223

SIDEWALK REMOVAL SCHEDULE

LOCATION	SIDEWALK REMOVAL (SQ FT)
KEEBLER ROAD	
STA. 83+51.02 - 15.58' LT TO STA. 83+68.09 - 21.58' LT	68.84
STA. 84+20.02 - 21.58' LT TO STA. 84+37.14 - 15.59' LT	68.96
STA. 90+21.49 - 15.58' LT TO STA. 90+39.98 - 21.58' LT	72.56
STA. 91+0.79 - 27.14' LT TO STA. 91+21.00 - 15.58' LT	109.17
STA. 94+86.59 - 15.60' RT TO STA. 95+04.51 - 21.58' RT	71.06
STA. 95+68.83 - 21.58' RT TO STA. 95+86.73 - 15.60' RT	71.01
STA. 100+36.41 - 15.61' LT TO STA. 100+54.79 - 21.58' LT	72.22
STA. 101+15.95 - 21.58' LT TO STA. 101+35.69 - 15.58' LT	80.72
STA. 101+96.79 - 15.58' RT TO STA. 102+15.34 - 21.58' RT	111.55
STA. 102+69.17 - 21.58' RT TO STA. 102+87.60 - 15.58' RT	110.30
STA. 106+34.58 - 15.60' LT TO STA. 106+50.76 - 21.58' LT	64.17
STA. 107+11.12 - 21.58' LT TO STA. 107+26.82 - 15.61' LT	62.37
STA. 114+82.02 - 15.65' LT TO STA. 114+99.36 - 21.58' LT	65.64
STA. 115+62.24 - 21.58' LT TO STA. 115+82.38 - 15.58' LT	81.62
STA. 116+71.57 - 15.67' RT TO STA. 116+91.52 - 27.78' RT	112.32
STA. 117+40.00 - 27.37' RT TO STA. 117+59.13 - 15.58' RT	142.49
TOTAL	1365

HOT-MIX ASPHALT SURFACE REMOVAL SCHEDULE

LOCATION	HOT-MIX ASPHALT SURFACE REMOVAL 2 1/2" (SQ YD)
KEEBLER ROAD	
STA. 83+50.50 TO STA. 117+90.68	10071.0
TOTAL	10071

FILE NAME = combschedulesKeebler.dgn	USER NAME = ramesh	DESIGNED - BFK	REVISED -
		DRAWN - JJB	REVISED -
	PLOT SCALE = *SCALE*	CHECKED - BFK	REVISED -
	PLOT DATE = 3/8/2012	DATE - 1/17/12	REVISED -

VILLAGE OF MARYVILLE
KEEBLER ROAD

QUANTITY SCHEDULES

SCALE: N.T.S. | SHEET NO. 2 OF 2 SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9135	10-00018-00-RS	MADISON	22	7
		CONTRACT NO. 97486		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		