



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 19, 2018

SUBJECT: FAP Route 358 (US 6/IL 83)  
Project NHPP-ID9X(590)  
Section 0909.1-B  
Cook County  
Contract No. 60K78  
Item No. 1, April 27, 2018 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page iii of the Table of Contents to the Special Provisions
2. Revised pages 2 and 46 of the Special Provisions
3. Added page 188 to the Special Provisions
4. Revised sheet 4 of the Plans

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.  
Acting Bureau Chief  
Bureau of Design and Environment

A handwritten signature in black ink, appearing to read 'Ted B. Walschleger P.E.'.

By: Ted B. Walschleger, P. E.  
Engineer of Project Management

cc: Anthony Quigley, Region 1, District 1; Tim Kell

MS/kf

COMPENSABLE DELAY COSTS (BDE)..... 120  
 CONCRETE END SECTIONS FOR PIPE CULVERTS (BDE) ..... 124  
 CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE) ..... 126  
 DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)..... 128  
 EQUIPMENT PARKING AND STORAGE (BDE) ..... 139  
 HOT-MIX ASPHALT - DENSITY TESTING OF LONGITUDINAL JOINTS (BDE)..... 139  
 HOT-MIX ASPHALT – TACK COAT (BDE) ..... 140  
 LIGHTS ON BARRICADES (BDE) ..... 141  
 PAVEMENT MARKING REMOVAL (BDE) ..... 142  
 PAYMENTS TO SUBCONTRACTORS (BDE) ..... 143  
 PORTLAND CEMENT CONCRETE (BDE) ..... 143  
 PORTLAND CEMENT CONCRETE BRIDGE DECK CURING (BDE) ..... 144  
 PORTLAND CEMENT CONCRETE SIDEWALK (BDE)..... 145  
 PROGRESS PAYMENTS (BDE) ..... 146  
 SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)..... 147  
 SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) ..... 147  
 TEMPORARY PAVEMENT MARKING (BDE)..... 148  
 TRAINING SPECIAL PROVISIONS (BDE) ..... 150  
 IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION 153  
 WARM MIX ASPHALT (BDE) ..... 155  
 WEEKLY DBE TRUCKING REPORTS (BDE)..... 157  
 STEEL COST ADJUSTMENT (BDE)..... 157  
 IDNR PERMIT..... 161  
 STORM WATER POLLUTION PREVENTION PLAN ..... 164  
 404 PERMIT ..... 177  
 GENERAL CONDITIONS ..... 182  
 SEEDING, CLASS 4 (MODIFIED) - NATIVE GRASS ..... 188

Revised 4/19/18

**COMPLETION DATE PLUS WORKING DAYS**

Effective: September 30, 1985

Revised: January 1, 2007

Revise Article 108.05 (b) of the Standard Specifications as follows:

"When a completion date plus working days is specified, the Contractor shall complete all contract items and safely open all roadways to traffic by 11:59 PM on, **August 31, 2019** except as specified herein.

The Contractor will be allowed to complete all clean-up work and punch list items within **5 working days** after the completion date for opening the roadway to traffic. Under extenuating circumstances the Engineer may direct that certain items of work, not affecting the safe opening of the roadway to traffic, may be completed within the working days allowed for clean-up work and punch list items. Temporary lane closures for this work may be allowed at the discretion of the Engineer.

Article 108.09 or the Special Provision for "Failure to Complete the Work on Time", if included in this contract, shall apply to both the completion date and the number of working days.

**STATUS OF UTILITIES (D-1)**

Effective: June 1, 2016

Utility companies and/or municipal owners located within the construction limits of this project have provided the following information in regard to their facilities and the proposed improvements. The tables below contain a description of specific conflicts to be resolved and/or facilities which will require some action on the part of the Department's contractor to proceed with work. Each table entry includes an identification of the action necessary and, if applicable, the estimated duration required for the resolution.

**UTILITIES TO BE ADJUSTED**

Conflicts noted below have been identified by following the suggested staging plan included in the contract. The company has been notified of all conflicts and will be required to obtain the necessary permits to complete their work; in some instances, resolution will be a function of the construction staging. The responsible agency must relocate or complete new installations as noted in the action column; this work has been deemed necessary to be complete for the Department's contractor to then work in the stage under which the item has been listed.

Pre-Stage: No conflicts to be resolved.

Revised 4/19/18

**KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)**

Effective: January 22, 2003

Revised: August 10, 2017

The Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required in these Special Provisions, the Standard Specifications, the State Standards, and the District Details.

Arterial lane closures shall be in accordance with the Standard Specifications, Highway Standards, District Details, and the direction of the Engineer. The Contractor shall request and gain approval from the Engineer seventy-two (72) hours in advance of all long-term (24 hrs. or longer) lane closures.

Arterial lane closures not shown in the staging plans will not be permitted during **peak traffic volume hours**.

Peak traffic volume hours are defined as weekdays (Monday through Friday) from **6:00 AM to 8:30 AM and 4:30 PM to 6:00 PM**.

Private vehicles shall not be parked in the work zone. Contractor's equipment and/or vehicles shall not be parked on the shoulders or in the median during non-working hours. The parking of equipment and/or vehicles on State right-of-way will only be permitted at locations approved by the Engineer in accordance with Articles 701.08 and 701.11 of the Standard Specifications.

Should the Contractor fail to completely open and keep open all the traffic lanes to traffic in accordance with the limitations specified above, the Contractor shall be liable to the Department for the amount of:

One lane or ramp blocked = \$1,000

Two lanes blocked = \$ 2,500

Not as a penalty but as liquidated and ascertained damages for each and every 15 minute interval or a portion thereof that a lane is blocked outside the allowable time limitations. Such damages may be deducted by the Department from any monies due the Contractor. These damages shall apply during the contract time and during any extensions of the contract time.

Revised 4/19/18

**SEEDING, CLASS 4 (MODIFIED) - NATIVE GRASS**

This work shall consist of Seeding Class 4 (Modified) in areas as shown in the plans or as directed by the Engineer.

All work, materials, and equipment shall conform to Sections 250 and 1081 of the Standard Specifications except as modified herein.

The Class 4 (Modified) seed mixture shall be supplied in separate bags of the two mixture components: Temporary Cover and Permanent Grasses. All native species will be local genotype and verified that original seed collection source will be from a radius of 150 miles from project site. Fertilizer is not required.

Article 250.07 Seeding Mixtures – Delete sentence 4. Delete the following from Table 1 – Seeding Mixtures:

Perennial Ryegrass

Article 250.09 – Add Seeding, Class 4 (Modified)

Article 250.10 – Add Seeding, Class 4 (Modified)

Added 4/19/18