

62746

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90		COOK	81	4
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
- - - (1012, 1214, 1415, & 1517) RS-3				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		URBAN ROADWAY 100% STATE I000				
X4066570	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, STONE MATRIX ASPHALT, SUPERPAVE, N80	TON	36757	36757				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	9349	9349				
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	5537	5537				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	2331	2331				
X4409400	BITUMINOUS SURFACE REMOVAL 1 3/4"	SQ YD	544546	544546				
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1				
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	50	50				
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	9	9				
X8850102	INDUCTION LOOP	FOOT	1292	1292				
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	1	1				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	700	700				
Z0042200	PORTLAND CEMENT CONCRETE PAVEMENT SURFACE REMOVAL	SQ YD	911	911				

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT						

* SPECIALTY ITEM

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 KENNEDY EXPRESSWAY

PLOT DATE: 2/9/2006

2/9/2006 10:00:00 AM