

PAVEMENT MARKING SCHEDULE			
STATION	TYPE	PAINT PVT MK LINE 5"	
		WHITE	YELLOW
LT & RT 162+20.7 TO 173+61.0	EDGE LINE	1,934 FT	
LT & RT 162+20.7 TO 173+61.0	NO PASS		1,934 FT
TOTALS		1,934 FT	1,934 FT

CURB AND GUTTER REMOVAL	
STATION	
LT 164+33.2 TO 173+61.0	754.5 FT
RT 162+20.7 TO 173+61.0	967 FT
TOTALS	1,721.5

COMBINATION CURB AND GUTTER , TYPE B-6.24	
STATION	
LT 164+33.2 TO 173+61.0	754.5 FT
RT 162+20.7 TO 173+61.0	967 FT
TOTALS	1,721.5 FT

STA. EQ. 171+86.7bk = 173+60.0ah

MIXTURE REQUIREMENTS		
THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT		
MIXTURE USE(S):	B.C. S.C., SUPER, MIX C, N50	LEV. BIND. (M.M), SUPER, N50
AC/PG	PG 64-22	PG 64-22
RAP %: (MAX)	15%	20%
DESIGN AIR VOIDS:	4.0% @ N DESIGN = 50	4.0% @ N DESIGN = 50
MIXTURE COMP:	IL 9.5 OR 12.5	IL 9.5
FRICTION AGG:	MIX "C"	N/A

PORTLAND CEMENT CONCRETE PAVEMENT 9" (SPECIAL)	
STATION	
LT & RT 166+81.7 TO 168+41.7	356 SQ YD
TOTALS	356 SQ YD

MANHOLES TO BE ADJUSTED	
STATION	
RT 5'-0" - STA. 168+30.0	1 EACH
TOTALS	1 EACH

PAVEMENT MARKING REMOVAL	
STATION	
LT & RT STA. 165+11.7 TO 166+71.7	141.7 SQ FT
LT & RT STA. 168+41.7 TO 170+11.7	141.7 SQ FT
TOTALS	283.4 SQ FT

NOTES:

1. STATIONS ARE APPROXIMATE.

SCHEDULES
FAS 735 (SHIPMAN BLACKTOP)
SECTION TRS-5
MACOUPIN COUNTY