

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57		MARION	13	3
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

• D-7 JOINT REPAIRS 2006-1

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		SFTY-2A	
X0325233	SILICONE JOINT SEALER, 2.25"	FOOT	94	94	
20700400	POROUS GRANULAR EMBANKMENT (SPECIAL)	CU YD	129.8	129.8	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	143	143	
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	30	30	
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	1435	1435	
50102400	CONCRETE REMOVAL	CU YD	22.2	22.2	
50200100	STRUCTURE EXCAVATION	CU YD	129.8	129.8	
50300225	CONCRETE STRUCTURES	CU YD	22.2	22.2	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1640	1640	
51205200	TEMPORARY SHEET PILING	SQ FT	289	289	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	104	104	
67100100	MOBILIZATION	L SUM	1	1	
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1	
70100805	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	L SUM	1	1	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2720	2720	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2070	2070	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	330	330	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	330	330	
* 78008310	POLYUREA PAVEMENT MARKING TYPE II - LINE 4"	FOOT	2720	2720	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	905	905	
X0300136	BRIDGE APPROACH SHOULDER REMOVAL	SQ YD	30	30	
X0320887	POLYMER CONCRETE	CU FT	7.5	7.5	
X4066430	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N105	TON	121	121	
X6028300	INLETS TO BE REMOVED, SPECIAL	EACH	2	2	
Z0001500	APPROACH SLAB REMOVAL & REPLACEMENT	SQ YD	76	76	
Z0002600	BAR SPLICERS	EACH	104	104	
Δ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1	
Δ Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1	

Δ SFTY-3N

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY