

SUMMARY OF QUANTITIES

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
595	1 - 1	ROCK ISLAND	239	7
STA.	75+60.93	TO STA.	116+00.00	
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT # 84986				

URBAN

←—————→

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITIES	2 - LANE 75+61 - 86+07		4 - LANE 86+07 - 116+00		90% STATE 10% CITY Y031 - 1F	100% CITY OF ROCK ISLAND Y060	50% STATE 50% CITY SFTY-1B
				100% STATE 1000 - 2A	100% STATE 1000 - 2A	100% STATE 1000 - 2A	100% STATE 1000 - 2A			
56103000	DUCTILE IRON WATER MAIN 6"	FOOT	85						85	
56103200	DUCTILE IRON WATER MAIN 10"	FOOT	1085						1085	
56104900	WATER VALVES 6"	EACH	6						6	
56105100	WATER VALVES 10"	EACH	2						2	
56200700	WATER SERVICE LINES 2"	FOOT	300						300	
56300300	ADJUSTING WATER SERVICE LINES	FOOT	60						60	
56400500	FIRE HYDRANTS TO BE REMOVED	EACH	5						5	
56400600	FIRE HYDRANTS	EACH	5						5	
56500200	DOMESTIC WATER SERVICE BOXES TO BE MOVED	EACH	13						13	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	1149	898		251				
60100060	CONCRETE HEADWALL FOR PIPE UNDERDRAINS	EACH	1			1				
60107600	PIPE UNDERDRAINS 4"	FOOT	1859	411		1448				
60109580	PIPE UNDERDRAIN FOR STRUCTURES 4"	FOOT	1095	932		163				
60218400	MANHOLES, TYPE A, 4' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	8			8				
60223800	MANHOLES, TYPE A, 6' -DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2			2				
60240200	INLETS, TYPE A, SPECIAL	EACH	1	1						
60242400	INLETS, SPECIAL	EACH	4			4				
60242801	INLETS, SPECIAL, NO. 5	EACH	48	13		35				
60244110	INLETS, SPECIAL, WITH TYPE 9 FRAME AND GRATE	EACH	7	3		4				
60246605	MEDIAN INLET (604101)	EACH	1	1						
60249110	VALVE VAULTS, 4'-DIAMETER	EACH	1					1		
60255500	MANHOLES TO BE ADJUSTED	EACH	6					6		
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2					2		
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	3			3				
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1			1				
60260100	INLETS TO BE ADJUSTED	EACH	1			1				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	5			5				
60500040	REMOVING MANHOLES	EACH	7			7				
60500060	REMOVING INLETS	EACH	11	6		5				
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	3			3				
60602500	CONCRETE GUTTER, TYPE A	FOOT	1030.0	919.0		111.0				
60602800	CONCRETE GUTTER, TYPE B	FOOT	1012.7	849.2		163.5				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	8538.0	1826.0		6712.0				
60614600	PAVED DITCH (SPECIAL)	FOOT	437			437				
63000000	STEEL PLATE BEAM GUARDRAIL, TYPE A	FOOT	137.5	137.5						
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1						
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	1	1						
63200310	GUARDRAIL REMOVAL	FOOT	288			288				
63500105	DELINEATORS	EACH	17	2		15				
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	2	1		1				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	16	4		12				
67100100	MOBILIZATION	L SUM	1	0.2		0.8				

* SPECIALTY ITEM

SUMMARY OF QUANTITIES