

# SCHEDULE OF QUANTITIES

21101615	TOPSOIL FURNISH AND PLACE - 4"	SO. YD.
F.A. 595		
STA 75+61 TO STA 116+00		14,138
LEFT		
RIGHT		11,109
INDIAN HILL ROAD		
STA 10+75 TO STA 14+00		349
30TH STREET		
STA 298+10 TO STA 304+16		979
34TH STREET		
STA 18+23 TO STA 19+30		182
<b>TOTAL</b>		<b>26,757</b>

25100115	MULCH, METHOD 2	ACRE
F.A. 595		
STA 75+61 TO STA 110+00		3.00
LEFT (INCLUDES INDIAN HILL ROAD)		0.00
RIGHT		0.00
LT AND RT STAGE I TEMPORARY SLOPES		1.50
30TH STREET		
STA 301+00 TO STA 304+16 LT & RT		0.25
34TH STREET		
STA 18+23 TO STA 19+30		0.00
<b>TOTAL</b>		<b>4.75</b>

28000300	TEMPORARY DITCH CHECKS	EACH
F.A. 595		
LEFT STA 90+50 TO 92+50	100' SPACING	2
LEFT STA 93+50 TO 95+50	50' SPACING	4
LEFT STA 96+50 TO 101+50	100' SPACING	5
RIGHT STA 97+70 TO 100+20	100' SPACING	2
RIGHT STA 101+50 TO 103+80	100' SPACING	2
RIGHT STA 102+00 TO 105+00	100' SPACING	3
<b>TOTAL</b>		<b>18</b>

42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT
F.A. 595		
LEFT STA 76+50 TO STA 81+92		2679
LEFT STA 82+37 TO STA 88+19		2873
LEFT STA 88+32 TO STA 95+44		3568
LEFT STA 96+66 TO STA 100+95		2167
LEFT STA 101+19 TO STA 112+00		5405
LEFT STA 112+20 TO STA 116+00		1849
RIGHT STA 95+33		37
<b>TOTAL</b>		<b>18,578</b>

44000200	DRIVEWAY PAVEMENT REMOVAL	SO. YD.	EARTH EXC CU. YD.
F.A. 595			
78+26 RT	CONC	72	0
84+44 RT	BIT	0	49
86+35 RT	BIT	0	43
86+35 RT	CONC	307	0
88+17 RT	BIT	0	55
88+28 LT	CONC	138	0
90+50 RT	BIT	0	81
92+61 RT	BIT	0	50
96+50 RT	BIT	0	16
97+25 RT	BIT/CONC	184	18
98+10 RT	CONC	56	0
99+42 LT	CONC	27	0
99+42 LT	BIT	0	13
107+31 RT	CONC	110	0
108+39 RT	CONC	120	0
110+25 LT	CONC	182	0
114+83 RT	BIT	0	13
30TH STREET			
299+08 RT	BIT	0	41
34TH STREET			
19+34 RT	BIT	0	9
<b>TOTAL</b>		<b>1,196</b>	<b>388</b>

25000400	NITROGEN FERTILIZER NUTRIENT	POUND
F.A. 595		
STA 75+61 TO STA 116+00		288
LEFT		156
RIGHT		156
30TH STREET		
STA 298+10 TO STA 304+16 LT & RT		25
34TH STREET		
STA 18+23 TO STA 19+30		2
<b>TOTAL</b>		<b>472</b>

25100630	EROSION CONTROL BLANKET	SO YD
F.A. 595		
STA 76+50 TO STA 79+50 LT (BEHIND RET WALL D)		400
STA 81+00 TO STA 85+00 LT (BEHIND PE AND RET WALL F)		230
STA 82+40 TO STA 88+11 LT		634
STA 88+41 TO STA 93+05 LT		516
STA 93+65 TO STA 94+40 LT		83
STA 94+55 TO STA 95+50 LT		106
STA 96+75 TO STA 100+85 LT		456
STA 101+60 TO STA 101+90 LT		33
STA 102+05 TO STA 103+25 RT		133
30TH STREET		
STA 302+50 TO STA 304+10 LT (BEHIND RET WALL E)		178
STA 304+10 TO STA 304+20 LT (END RET WALL E)		28
<b>TOTAL</b>		<b>2,797</b>

28000400	PERIMETER EROSION BARRIER	FOOT
F.A. 595		
STA 79+00 TO STA 84+00 RT		500
STA 85+00 TO STA 85+70 RT		70
STA 86+80 TO STA 87+85 RT		185
STA 88+45 TO STA 90+25 RT		180
STA 91+00 TO STA 92+30 RT		135
STA 92+60 TO STA 95+25 RT		295
STA 100+40 TO STA 101+40 RT		100
STA 101+55 TO STA 101+95 RT		40
STA 105+10 TO STA 107+00 RT		190
STA 109+00 TO STA 109+60 RT		60
STA 114+00 TO STA 114+80 RT		180
STA 115+00 TO STA 116+00 RT		200
30TH STREET		
STA 301+60 TO STA 302+10 LT		50
<b>TOTAL</b>		<b>2,185</b>

42400800	DETECTABLE WARNINGS	SO FT
F.A. 595		
STA 81+89 LT		10
STA 82+38 LT		10
STA 88+19 LT		10
STA 88+33 LT		10
STA 93+33 RT		10
STA 95+43 LT		10
ISLAND NW QUADRANT		18
STA 96+64 LT		10
ISLAND NE QUADRANT		12
STA 100+93 LT		10
STA 101+21 LT		10
STA 111+93 LT		10
STA 112+23 LT		10
<b>TOTAL</b>		<b>140</b>

44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT
F.A. 595		
LEFT 76+89 TO 81+35		446
RIGHT 76+40 TO 79+30		290
RIGHT 96+75 TO 97+02		27
RIGHT 96+69 TO 97+07		38
RIGHT 97+46 TO 97+68		22
RIGHT 97+60 TO 97+95		35
LEFT 96+07 TO 100+58		451
LEFT 106+97 TO 106+97		12
LEFT 108+90 TO 116+00		710
INDIAN HILL RD (EXISTING)		
NW RADIUS RETURN AND LEFT		154
NE RADIUS RETURN AND RIGHT		114
30TH STREET		
SW RADIUS RETURN		123
SE RADIUS RETURN		45
NW RADIUS RETURN AND LEFT		466
NE RADIUS RETURN AND RIGHT		212
<b>TOTAL</b>		<b>3,145</b>

25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND
F.A. 595		
STA 75+61 TO STA 116+00		288
LEFT		156
RIGHT		156
30TH STREET		
STA 298+10 TO STA 304+16 LT & RT		25
34TH STREET		
STA 18+23 TO STA 19+30		2
<b>TOTAL</b>		<b>472</b>

25200100	SODDING	SO YD
F.A. 595		
LEFT STA 110+00 TO STA 116+00		1,491
RIGHT STA 75+61 TO STA 116+00		12,579
30TH STREET		
STA 298+10 TO STA 299+00 LT		231
34TH STREET		
STA 18+23 TO STA 19+30		182
<b>TOTAL</b>		<b>14,483</b>

28000500	INLET AND PIPE PROTECTION	EACH
F.A. 595		
STA 88+10 LT		1
STA 93+59 LT		1
STA 95+36 RT		1
STA 100+82 LT		1
STA 101+50 LT		2
STA 104+43 RT		1
INLETS (ENTIRE PROJECT)		61
<b>TOTAL</b>		<b>68</b>

44000030	BIT SURF REMOVAL (VARIABLE DEPTH)	SO YD
F.A. 595		
STA 76+89 TO 82+75		781.3
STA 87+56 TO 95+00 & 96+00 TO 112+00		3125.3
STA 76+44 TO 87+56		1482.7
STA 82+75 TO 95+00 & 97+00 TO 116+00		4166.7
<b>TOTAL</b>		<b>9556.0</b>

44002805	ISLAND REMOVAL	SO FT
F.A. 595		
30TH STREET		
NW CORNER ISLAND		183
NE CORNER ISLAND		443
<b>TOTAL</b>		<b>626</b>

25000600	POTASSIUM FERTILIZER NUTRIENT	POUND
F.A. 595		
STA 75+61 TO STA 116+00		288
LEFT		156
RIGHT		156
30TH STREET		
STA 298+10 TO STA 304+16 LT & RT		25
34TH STREET		
STA 18+23 TO STA 19+30		2
<b>TOTAL</b>		<b>472</b>

25200200	SUPPLEMENTAL WATERING	UNIT
F.A. 595		
LEFT STA 110+00 TO STA 116+00		13.4
RIGHT STA 75+61 TO STA 116+00		113.2
30TH STREET		
STA 298+10 TO STA 299+00 LT		2.1
34TH STREET		
STA 18+23 TO STA 19+30		1.6
<b>TOTAL</b>		<b>130.4</b>

28100707	STONE DUMPED RIPRAP, CLASS A4	SO YD
F.A. 595		
STA 76+35 TO STA 76+50 LT		11
STA 97+80 TO STA 97+95 RT		17
STA 99+90 TO STA 100+05 RT		17
STA 101+45 TO STA 101+65 RT		49
STA 101+90 TO STA 102+05 LT		17
STA 101+95 TO STA 102+05 RT		12
STA 112+20 TO STA 112+24 LT		2
30TH STREET		
STA 302+05 TO 302+50 LT		30
<b>TOTAL</b>		<b>155</b>

44000100	PAVEMENT REMOVAL	SO. YD.
F.A. 595		
75+61 TO 76+89		543
76+89 TO 79+37		1,010
79+37 TO 90+58		3,193
90+58 TO 93+25		899
93+25 TO 97+07		1,509
97+07 TO 98+34		616
98+34 TO 100+58		887
100+58 TO 102+00		445
102+00 TO 111+00		2,625
111+00 TO 116+00		1,752
INDIAN HILL ROAD		
10+13 TO 11+19		341
30TH STREET		
SOUTH INCLUDE RAD. RETURNS		707
NORTH INCLUDE RAD. RETURNS		840
34TH STREET		
		438
<b>TOTAL</b>		<b>15,805</b>

25000910	SEEDING, CLASS I (MODIFIED)	ACRE
F.A. 595		
STA 75+61 TO STA 110+00		3.00
LEFT (INCLUDES INDIAN HILL ROAD)		0.00
RIGHT		0.00
LT AND RT STAGE I TEMPORARY SLOPES		1.50
30TH STREET		
STA 301+00 TO STA 304+16 LT & RT		0.25
34TH STREET		
STA 18+23 TO STA 19+30		0.00
<b>TOTAL</b>		<b>4.75</b>

28000250	TEMPORARY EROSION CONTROL SEEDING	POUND
F.A. 595		
LEFT / RIGHT STA 75+61 TO 116+00		1000
30TH STREET		
LEFT / RIGHT 298+10 TO 304+16		100
34TH STREET		
LEFT / RIGHT 18+23 TO 19+30		100
<b>TOTAL</b>		<b>1,200</b>

28200200	FILTER FABRIC	SO YD
F.A. 595		
STA 76+35 TO STA 76+50 LT		11
STA 97+80 TO STA 97+95 RT		17
STA 99+90 TO STA 100+05 RT		17
STA 101+45 TO STA 101+65 RT		49
STA 101+90 TO STA 102+05 LT		17
STA 101+95 TO STA 102+05 RT		12
STA 112+20 TO STA 112+24 LT		2
30TH STREET		
STA 302+05 TO 302+50		30
<b>TOTAL</b>		<b>155</b>

40500300	BITUMINOUS MIXTURE COMPLETE	TON
F.A. 595		
STG IIA 76+89 TO 82+75		43.7
STG II 87+56 TO 95+00 & 96+00 TO 112+00		175.0
STG IIB 76+44 TO 87+56		83.0
STG III 82+75 TO 95+00 & 97+00 TO 116+00		233.3
<b>TOTAL</b>		<b>535.0</b>

TEMPORARY WEDGE AT GUTTER LIP FOR STAGED CONSTRUCTION

ILLINOIS PROFESSIONAL DESIGN FIRM NO. 184-001533



550 West Higgins Road, Suite 750, Chicago, Illinois 60634-2807  
www.stanleyconsultants.com

REVISIONS	
NAME	DATE