

PLOT DATE = 2/6/2006
FILE NAME = c:\p\projects\082105\082105.dwg
PLOT SCALE = 60.0' / 1" IN.
USER NAME = rds101

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
885	104 RS-4	UNION	24	10
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

REMOVAL SCHEDULE

LOCATION STATION TO STATION	BITUMINOUS SURFACE REMOVAL 2-1/4"	PAVEMENT REMOVAL	COMBINATION CURB AND GUTTER REMOVAL	DRIVEWAY PAVEMENT REMOVAL	SIDEWALK REMOVAL
	SQ YD	SQ YD	FOOT	SQYD	SQFT
STA 0+00 TO STA 0+53	233				
STA 100+00 TO STA 104+85	1889				
STA 101+23(RIGHT)				44	
STA 101+49 TO STA 102+21(RIGHT)			72		
STA 102+55(RIGHT)				62	
STA 102+85 TO STA 103+33(RIGHT)		51			
STA 103+44(RIGHT)				24	
STA 103+54 TO STA 104+38(RIGHT)		86			
STA 104+22 (LEFT)					40
SPRING STREET		47			
TOTALS	2122	184	72	130	40

DRAINAGE SCHEDULE

LOCATION STATION TO STATION	COMBINATION CONCRETE CURB & GUTTER TYPE B-6. 24	SUB-BASE GRANULAR MATERIAL TYPE A	FRAMES AND LIDS TO BE ADJUSTED	PROTECTIVE COAT
	FOOT	SQYD	EACH	SQYD
STA 101+47 TO STA 104+39(RIGHT)	298	136		86
STA 100+17 11' RIGHT			1	
STA 101+46 11' RIGHT			1	
STA 104+18 8' LEFT			1	
TOTALS	298	136	3	86

EARTHWORK AND EROSION CONTROL SCHEDULE

LOCATION STATION TO STATION	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT ADJUSTED FOR SHRINKAGE	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)	EROSION CONTROL BLANKET	TOPSOIL FURNISH AND PLACE, 12"	COMMENTS
	CU YD	CU YD	CU YD	CU YD	SQYD	SQYD	
STA 101+00 TO STA 104+50	91	68	5	63			
STA 101+47 TO STA 102+22					30		
STA 102+85 TO STA 103+33						28	
STA 102+85 TO STA 104+39					72		
STA 103+55 TO STA 104+37						44	
	91			63	102	72	

SHRINKAGE FACTOR: EARTH EXCAVATION 25%