

BILL OF MATERIALS

Pay Item No.	Item	Unit	Total
20700220	Porous Granular Embankment	Cu. Yd.	139
50200100	Structure Excavation	Cu. Yd.	178
50200400	Rock Excavation For Structures	Cu. Yd.	51
X6029003	Junction Box, Number 3	L Sum	1

DESIGN STRESSES PRECAST UNITS

f'c = 4,500 psi fy = 60,000 psi (Reinforcement) fy = 50,000 psi (M270 Grade 50)

DESIGN SPECIFICATIONS:

AASTHO LRFD Bridge Specifications. 7TH Addition

CORNER REINFORCEMENT DETAIL (Typ. at top slab and wall corners)

-#5 @ 12" *

#6 - 2'-7" x 2'-7" @ 12" *

a 4'-6" x 4'-6" bent bar

*At wall corners, #8 @ 6" with

3. The Contractor is to patch all lifting insert holes and place a minimum of one (1) inch of cover over the hardware of these devices on both top and bottom surfaces

2. Junction Box shall be constructed in accordance with the Special Provision "Junction Box, Number 3" and the Standard

signed and sealed by a Illinois Licensed Structural Engineer. Cost of temporary soil rentention system shall be included

- All existing pipe surfaces to abut new concrete shall be cleaned and roughened. (Cost shall be included in "Junction Box, Number 3").
- 5. It shall be at all times the responsibility of the Contractor to prevent the flow of existing storm sewer from entering the construction site.
- 6. The cost of the adjustment of existing pipe and connection to the proposed structure is included in the cost of "Junction Box, Number 3".
- 7. The Concrete Junction Box as shown in the contract plans is designed as a single unit. Should the Contractor decide to construct the Junction Box in horizontal segments, the Contractor shall submit signed and sealed calculations and plan details of the segment connections from an Illinois Licensed Structural Engineer. This work is included in the cost of "Junction Box, Number 3".
- 8. A Cast-In-Place alternative may be used at the Contractor's option.


in cost of "Junction Box, Number 3".

Specifications.

01	JNTY	SHEETS	NO.						
K	ISLAND	1504	402						
N	NTRACT NO 64CO8								

DET-44

	FILE NAME =	USER NAME = hehnØ1663	DESIGNED -	RLT	REVISED -				DRAIN	iage i	DETAILS		F.A.I	SECTION	COUNTY	TOTAL	SHEE
. G	D2CONAB-HPS-sht-drain25M.dgn		DRAWN -	RLT	REVISED -	STATE OF ILLINOIS		JU	NCTION	BOX,	NUMBER 3		74	(81-1)R & 81-1HVBR	ROCK ISLAN	ID 1504	40:
		PLOT SCALE = NTS	CHECKED -	JJW/LMS	REVISED -	DEPARTMENT OF TRANSPORTATION			STRU	UCTUR	E B42				CONTRACT	T NO.	64C0
김동		PLOT DATE = 1/19/2017	DATE -	1/20/2017	REVISED -		SCALE: NTS	SHEET NO.	OF	SHEET	TS STA.	TO STA.		ILLINOIS FED.	AID PROJECT		
			•					_								-	_



TEMPORARY SOIL RETENTION SYSTEM (NOT TO SCALE)

-#5 @ 9" *

BILL OF MATERIALS

Pay Item No.	Item	Unit	Total
20700220	Porous Granular Embankment	Cu. Yd.	114
50200100	Structure Excavation	Cu. Yd.	140
X6029004	Junction Box, Number 4	L Sum	1
 Community	for bootion Day Number 4 includes		フフ ハフフュ

L Sum quantity for Junction Box, Number 4 includes structure N33, N33a, and N33b.

DESIGN STRESSES PRECAST UNITS

f'c = 4,500 psi

fy = 60,000 psi (Reinforcement) fy = 50,000 psi (M270 Grade 50)

DESIGN SPECIFICATIONS:

AASTHO LRFD Bridge Specifications. 7TH Addition

#5 - 2'-2" x 2'-2" @ 9" *

CORNER REINFORCEMENT DETAIL (Typ. at top slab and wall corners)

* At wall corners, #7 @ 9" with a 3'-5" x 3'-5" bent bar.

8.	A Cast-In-Place	alternative may	be used at	the Contractor's	option.

4'-95/8'

PLAN VIEW (NOT TO SCALE)

 Manhole Lid STA. 1919+92.56, 39.80 RT.

in "Junction Box, Number 4".

these devices on both top and bottom surfaces

Specifications.

Number 4").

the construction site.

"Junction Box, Number 4".

"Junction Box, Number 4".

WP

-WP 2

9. Any pipe connections to the proposed riser shall be in accordance with Section 602 of the Standard Specifications.

GENERAL NOTES

1. A Cantilevered Sheet Piling Design does not appear feasible and additional members or other Retention Systems may be necessary. The Contractor shall submit a Temporary Soil Retention System design including plan details and calculations signed and sealed by a Illinois Licensed Structural Engineer. Cost of temporary soil retention system shall be included

2. Junction Box shall be constructed in accordance with the Special Provision "Junction Box, Number 4" and the Standard

3. The Contractor is to patch all lifting insert holes and place a minimum of one (1) inch of cover over the hardware of

4. All existing pipe surfaces to abut new concrete shall be cleaned and roughened. (Cost shall be included in "Junction Box,

5. It shall be at all times the responsibility of the Contractor to prevent the flow of existing storm sewer from entering

7. The Concrete Junction Box as shown in the contract plans is designed as a single unit. Should the Contractor decide to

construct the Junction Box in horizontal segments, the Contractor shall submit signed and sealed calculations and plan

details of the segment connections from an Illinois Licensed Structural Engineer. This work is included in the cost of

6. The cost of the adjustment of existing pipe and connection to the proposed structure is included in the cost of


											DET-46	
5	FILE NAME =	USER NAME = hehnØ1663	DESIGNED - RLT	REVISED -			DRAINAGE DETAILS		F.A.I	SECTION	COUNTY TOTAL SHEE	П
_ Q	D2CONAB-HPS-sht-drain31M.dgn		DRAWN - RLT	REVISED -	STATE OF ILLINOIS		JUNCTION BOX, NUMBER 4		74	(81-1)R & 81-1HVBR	ROCK ISLAND 1504 404	. –
		PLOT SCALE = NTS	CHECKED - JJW/LMS	REVISED -	DEPARTMENT OF TRANSPORTATION		STRUCTURE N33				CONTRACT NO. 64C08	از
시었다	! 	PLOT DATE - 1/19/2017	DATE - 1/20/2017	PEVISED -		SCALE NITS SHE	EET NO OF SHEETS STA	TO STA		III MOTE EED	AID DDO IECT	-

REVISED

PLOT DATE = 1/19/2017

DATE

1/20/2017



(NOT TO SCALE)

-#5 **@** 12" *

BILL OF MATERIALS

Pay Item No.	Item	Unit	Total
20700220	Porous Granular Embankment	Cu. Yd.	116
50200100	Structure Excavation	Cu. Yd.	150
X6029004	Junction Box, Number 4	L Sum	1
I Sum quantity	for Junction Pay Number 1 includes	ctructure N	77 1/770

and N33b.

DESIGN STRESSES PRECAST UNITS

f'c = 4,500 psi

fy = 60,000 psi (Reinforcement) fy = 50,000 psi (M270 Grade 50)

DESIGN SPECIFICATIONS:

AASTHO LRFD Bridge Specifications. 7TH Addition

CORNER REINFORCEMENT DETAIL (Typ. at top slab and wall corners)

#6 - 2'-7" x 2'-7" @ 12"

Pay Item No.	Item	Unit	Total
20700220	Porous Granular Embankment	Cu. Yd.	116
50200100	Structure Excavation	Cu. Yd.	150
X6029004	Junction Box, Number 4	L Sum	1

* At wall corners, #7 @ 6" with a 3'-5" x 3'-5" bent bar.

€ Structure N33a 6" Typ. 12" Typ. 4'-113/8' 10′-1/2′′

10'-1/2'

4'-7"

5'-51/2'

- **€** Manhole Lid

26.20 RT.

-WP 2

STA. 1919+41.31.

GENERAL NOTES

1. A Cantilevered Sheet Piling Design does not appear feasible and additional members or other Retention Systems may be necessary. The Contractor shall submit a Temporary Soil Retention System design including plan details and calculations signed and sealed by a Illinois Licensed Structural Engineer. Cost of temporary soil retention system shall be included in "Junction Box, Number4".

PLAN VIEW (NOT TO SCALE)

- 2. Junction Box shall be constructed in accordance with the Special Provision "Junction Box, Number 4" and the Standard Specifications.
- 3. The Contractor is to patch all lifting insert holes and place a minimum of one (1) inch of cover over the hardware of these devices on both top and bottom surfaces
- All existing pipe surfaces to abut new concrete shall be cleaned and roughened. (Cost shall be included in "Junction Box, 4. Number 4").
- 5. It shall be at all times the responsibility of the Contractor to prevent the flow of existing storm sewer from entering the construction site.
- 6. The cost of the adjustment of existing pipe and connection to the proposed structure is included in the cost of "Junction Box, Number 4".
- 7. The Concrete Junction Box as shown in the contract plans is designed as a single unit. Should the Contractor decide to construct the Junction Box in horizontal segments, the Contractor shall submit signed and sealed calculations and plan details of the segment connections from an Illinois Licensed Structural Engineer. This work is included in the cost of "Junction Box, Number 4".
- 8. A Cast-In-Place alternative may be used at the Contractor's option.

										DET-48
FILE NAME =	USER NAME = hehnØ1663	DESIGNED - RLT	REVISED -			DRAINAGE DE	TAILS	F.A.I	SECTION	COUNTY TOTAL SHEET
D2CONAB-HPS-sht-drain30M.dgn		DRAWN - RLT	REVISED -	STATE OF ILLINOIS		JUNCTION BOX, N	UMBER 4	74	(81-1)R & 81-1HVBR	ROCK ISLAND 1504 406
	PLOT SCALE = NTS	CHECKED - JJW/LMS	REVISED -	DEPARTMENT OF TRANSPORTATION		STRUCTURE I	N33a			CONTRACT NO. 64C08
	PLOT DATE = 1/19/2017	DATE - 1/20/2017	REVISED -		SCALE: NTS	SHEET NO. OF SHEETS	STA. TO STA.		ILLINOIS FED. A	ID PROJECT

WP 1 = 1919+38.68, 34.35 RT. WP 2 = 1919+41.60, 25.25 RT.

Remove and replace existing storm sewer

to first joint. Pipe removal and replacement

D

shall be included in the contract price for

Junction Box, Number 4.

DESIGN STRESSES PRECAST UNITS

fy = 60,000 psi (Reinforcement)


 $fy = 50,000 \, psi \, (M270 \, Grade \, 50)$

DESIGN SPECIFICATIONS:

AASTHO LRFD Bridge Specifications.


f'c = 4,500 psi

7TH Addition



TEMPORARY SOIL RETENTION SYSTEM (NOT TO SCALE)

BILL OF MATERIALS




GENERAL NOTES

N

- A Cantilevered Sheet Piling Design does not appear feasible and additional members or other Retention Systems may be necessary. The Contractor shall submit a Temporary Soil Retention System design including plan details and calculations signed and sealed by a Illinois Licensed Structural Engineer. Cost of temporary soil retention system shall be included in "Junction Box, Number 4".
- 2. Junction Box shall be constructed in accordance with the Special Provision "Junction Box, Number 4" and the Standard Specifications.
- 3. The Contractor is to patch all lifting insert holes and place a minimum of one (1) inch of cover over the hardware of these devices on both top and bottom surfaces
- 4. All existing pipe surfaces to abut new concrete shall be cleaned and roughened. (Cost shall be included in "Junction Box, Number 4").
- 5. It shall be at all times the responsibility of the Contractor to prevent the flow of existing storm sewer from entering the construction site.
- 6. The cost of the adjustment of existing pipe and connection to the proposed structure is included in the cost of "Junction Box, Number 4".
- 7. The Concrete Junction Box as shown in the contract plans is designed as a single unit. Should the Contractor decide to construct the Junction Box in horizontal segments, the Contractor shall submit signed and sealed calculations and plan details of the segment connections from an Illinois Licensed Structural Engineer. This work is included in the cost of "Junction Box, Number 4".
- 8. A Cast-In-Place alternative may be used at the Contractor's option.
- 9. Any pipe connections to the proposed riser shall be in accordance with Section 602 of the Standard Specifications.

DET-50													RL I JW /LMS
COUNTY TOTAL SHEET	SECTION COUNTY	F.A.I	TAILS	RAINAGE DET	DRA			REVISED -	RLT	DESIGNE	USER NAME = hehnØ1663	FILE NAME =	-5
ROCK ISLAND 1504 408	(81-1)R & 81-1HVBR ROCK ISLAND	74	UMBER 4	TON BOX, N	JUNCTI		STATE OF ILLINOIS	REVISED -	· RLT	DRAWN		D2C0NAB-HPS-sht-drain32M.dgn	
CONTRACT NO. 64C08	CONTRACT		N33b	TRUCTURE N	ST		DEPARTMENT OF TRANSPORTATION	REVISED -	- JJW/LMS	CHECKED	PLOT SCALE = NTS		YOUT AWN VIEW
	ILLINOIS FED. AID PROJECT	STA.	STA. TO STA	F SHEETS	EET NO. OF	ALE: NTS		REVISED -	1/20/2017	DATE	PLOT DATE = 1/19/2017		지임뿐
ΑIC	ILLINOIS FED.	STA.	STA. TO STA		EET NO. OF	ALE: NTS		REVISED -	1/20/2017	DATE	PLOT DATE = 1/19/2017		_101&1



TEMPORARY SOIL RETENTION SYSTEM (NOT TO SCALE)

-#4 @ 12" *

BILL OF MATERIALS

Pay Item No.	Item	Unit	Total
20700220	Porous Granular Embankment	Cu. Yd.	210
50200100	Structure Excavation	Cu. Yd.	224
X6029005	Junction Box, Number 5	L Sum	1
I Cum quantitu	for Lipstica Day Number E includes	atruatura (TO and NIZE

CORNER REINFORCEMENT DETAIL (Typ. at top slab and wall corners)

#5 - 2'-2" x 2'-2" @ 12"

* At wall corners, #6 @ 9" with a 2'-7" x 2'-7" bent bar,

Pay Item No.	Item	Unit	Total
20700220	Porous Granular Embankment	Cu. Yd.	210
50200100	Structure Excavation	Cu. Yd.	224
X6029005	Junction Box, Number 5	L Sum	1
I Sum quantity	for Junction Box Number 5 includes	structure	F.8 and N36

Remove and replace existing storm sewer to first joint. Pipe removal and replacement included in contract price for Junction Box, Number 5. **€** Manhole Lid STA. 1922+66.52, 38.48 RT.

GENERAL NOTES

1. A Cantilevered Sheet Piling Design does not appear feasible and additional members or other Retention Systems may be necessary. The Contractor shall submit a Temporary Soil Retention System design including plan details and calculations signed and sealed by a Illinois Licensed Structural Engineer. Cost of temporary soil retention system shall be included in "Junction Box, Number 5".

PLAN VIEW (NOT TO SCALE)

- 2. Junction Box shall be constructed in accordance with the Special Provision "Junction Box, Number 5" and the Standard Specifications.
- 3. The Contractor is to patch all lifting insert holes and place a minimum of one (1) inch of cover over the hardware of these devices on both top and bottom surfaces
- 4. All existing pipe surfaces to abut new concrete shall be cleaned and roughened. (Cost shall be included in "Junction Box, Number 5").
- 5. It shall be at all times the responsibility of the Contractor to prevent the flow of existing storm sewer from entering the construction site.
- 6. The cost of the adjustment of existing pipe and connection to the proposed structure is included in the cost of "Junction Box, Number 5".
- 7. The Concrete Junction Box as shown in the contract plans is designed as a single unit. Should the Contractor decide to construct the Junction Box in horizontal segments, the Contractor shall submit signed and sealed calculations and plan details of the segment connections from an Illinois Licensed Structural Engineer. This work is included in the cost of "Junction Box, Number 5".
- 8. A Cast-In-Place alternative may be used at the Contractor's option.
- 9. Any pipe connections to the proposed riser shall be in accordance with Section 602 of the Standard Specifications.

FILE NAME = USER NAME = hehnØ1663 DESIGNED - RLT REVISED DRAINAGE DETAILS SECTION COUNTY STATE OF ILLINOIS JUNCTION BOX, NUMBER 5 D2CONAB-HPS-sht-drain33M.dqn DRAWN RI T REVISED (81-1)R & 81-1HVBR ROCK ISLAND 1504 410 STRUCTURE E8

OF SHEETS STA. CHECKED JJW/LMS REVISED **DEPARTMENT OF TRANSPORTATION** CONTRACT NO. 64C08 SCALE: NTS TO STA. SHEET NO. PLOT DATE = 1/19/2017 DATE 1/20/2017 REVISED

DESIGN SPECIFICATIONS: AASTHO LRFD Bridge Specifications. 7TH Addition

DESIGN STRESSES

fy = 60,000 psi (Reinforcement)

fy = 50,000 psi (M270 Grade 50)

PRECAST UNITS

f'c = 4,500 psi

DEPARTMENT OF TRANSPORTATION

SCALE: NTS

SHEET NO.

TO STA.

CHECKED

DATE

PLOT DATE = 1/19/2017

JJW/LMS

1/20/2017

REVISED


REVISED

COUNTY

ROCK ISLAND 1504 411

CONTRACT NO. 64C08


HANSON



TEMPORARY SOIL RETENTION SYSTEM

-#5 **@** 12" *

BILL OF MATERIALS



DESIGN STRESSES PRECAST UNITS

f'c = 4,500 psi fy = 60,000 psi (Reinforcement) fy = 50,000 psi (M270 Grade 50)

DESIGN SPECIFICATIONS: AASTHO LRFD Bridge Specifications. 7TH Addition

CORNER REINFORCEMENT DETAIL (Typ. at top slab and wall corners)

DATE

CHECKED

JJW/LMS

1/20/2017

REVISED

REVISED

#5 - 2'-2" x 2'-2" @ 12" *-

PLOT DATE = 1/19/2017

* At wall corners, #6 @ 9" with a 2'-7" x 2'-7" bent bar.

GENERAL NOTES

-WP 2

1. A Cantilevered Sheet Piling Design does not appear feasible and additional members or other Retention Systems may be necessary. The Contractor shall submit a Temporary Soil Retention System design including plan details and calculations signed and sealed by a Illinois Licensed Structural Engineer. Cost of temporary soil retention system shall be included in "Junction Box. Number 5".

PLAN VIEW

 Manhole Lid STA. 1922+82.3 18.64 RT.


139°47′34′′


- 2. Junction Box shall be constructed in accordance with the Special Provision "Junction Box, Number 5" and the Standard Specifications.
- 3. The Contractor is to patch all lifting insert holes and place a minimum of one (1) inch of cover over the hardware of these devices on both top and bottom surfaces
- 4. All existing pipe surfaces to abut new concrete shall be cleaned and roughened. (Cost shall be included in "Junction Box,
- 5. It shall be at all times the responsibility of the Contractor to prevent the flow of existing storm sewer from entering the construction site.
- 6. The cost of the adjustment of existing pipe and connection to the proposed structure is included in the cost of "Junction Box, Number 5".
- 7. The Concrete Junction Box as shown in the contract plans is designed as a single unit. Should the Contractor decide to construct the Junction Box in horizontal segments, the Contractor shall submit signed and sealed calculations and plan details of the segment connections from an Illinois Licensed Structural Engineer. This work is included in the cost of "Junction Box, Number 5".
- 8. A Cast-in-Place alternative may be used at the Contractor's option.


뒫									
	FILE NAME =	USER NAME = hehnØ1663	DESIGNED - RLT	REVISED -		DRAINAGE DETAILS			
	D2CONAB-HPS-sht-drain34M.dgn		DRAWN - RLT	REVISED -	STATE OF ILLINOIS	JUNCTION BOX, NUMBER			


DEPARTMENT OF TRANSPORTATION


DRAINAGE DETAILS F.A.I RTE. SECTION	COUNTY	TOTAL	SHEET
		SHEETS	NO.
	ROCK ISLAND	1504	412
STRUCTURE N36 C	CONTRACT	NO. 6	4C08
SCALE: NTS SHEET NO. OF SHEETS STA. TO STA. ILLINOIS FED. AID P	ILLINOIS FED. AID PROJECT		





















D2CONAB-HPS-sht-pmk008L.dgn





PMK-04

DESIGNED - CBP USER NAME = hehn@1663 REVISED DRAWN CBP REVISED CHECKED REVISED PLOT DATE = 1/19/2017 - 1/20/2017 REVISED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION** PAVEMENT MARKINGS PLANS RIVER DRIVE

SECTION COUNTY (81-1)R & 81-1HVBR ROCK ISLAND 1504 432 CONTRACT NO. 64C08 SCALE: 1" = 20' SHEET NO. OF SHEETS STA. 3006+50 TO STA. 3011+50

USER NAME = hehn@1663

PLOT DATE = 1/19/2017

D2CONAB-HPS-sht-pmk014L.dgn

DESIGNED -

DRAWN

CHECKED

CBP


CBP

1/20/2017

REVISED

REVISED

REVISED



2. LANE WIDTH DIMENSIONS SHOWN ARE BASED ON PROPOSED JOINT LOCATIONS.
SEE DISTRICT STANDARDS 41.1 & 44.1 FOR ADDITIONAL PAVEMENT MARKING
DETAILS AND PLACEMENT/OFFSET OF MARKINGS RELATIVE TO JOINTS AND EOP.

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKINGS PLANS

6TH AVENUE

TO STA.

SCALE: 1" = 20' SHEET NO. OF SHEETS STA.

SECTION


(81-1)R & 81-1HVBR

COUNTY

ROCK ISLAND 1504 438

CONTRACT NO. 64C08

© Copyright Hanson Professional Services Inc.	19.00.0 - ANNO 19.00 -
10/8/2014 10/8/2014 10/8/2014	
LAYOUT CBP DRAWN CBP REVIEWED AAP	FILE NAME = NAME





HANSON





SEEDING LEGEND:

SODDING - SMALL URBAN AREAS

SEEDING, CLASS 2A - ON FORESLOPES AND DITCH BOTTOMS

SEEDING, CLASS 4 - BEYOND FORESLOPES AND DITCH BOTTOMS INCLUDING BACKSLOPES

MULCH, METHOD 3 - EROSION CONTROL MEASURES IN PREPARATION FOR SUBSEQUENT LANDSCAPING CONTRACT BY OTHERS



TURF REINFORCEMENT MAT - EROSION CONTROL MEASURES IN PREPARATION FOR SUBSEQUENT LANDSCAPING CONTRACT BY OTHERS



PRECAST BLOCK REVETMENT MAT

Ρ

	FILE NAME =
VIEWEU	D2CONAB-HPS-sht-lndscp006M.dgn

USER NAME = hehnØ1663	DESIGNED - CBP
	DRAWN - CBP
PLOT SCALE = 1" = 50"	CHECKED - AAP
PLOT DATE = 1/19/2017	DATE - 1/20/2017

		SEE	DING PLA			F.A.I RTE.	SECTION	COUNT
			7TH AVE			74	(81-1)R & 81-1HVBR	ROCK ISL
								CONTR
LE: 1" = 50"	SHEET NO.	OF	SHEETS	STA. 7000+00	TO STA. 7007+00		ILLINOIS FED. A	ID PROJECT


 SD-05

 NTY
 TOTAL SHEET NO.

 ISLAND
 1504
 455

REVISED STATE OF ILLINOIS REVISED **DEPARTMENT OF TRANSPORTATION** REVISED REVISED


7004+20.79 41.01′ LT




© Copyright Hanson Professional Services Inc.	\$\text{\$\text{\$\text{\$\text{\$PR\$} 21ST ST}}}{\text{\$\text{\$2.0'} MIN.}}\$\$ \$\text{\$\text{\$\text{\$\text{\$\text{\$2.0'} MIN.}}}\$\$ \$\$\text{\$\	x x x x x x x x x x x x x x x x x x x	SEE SHEET JT-05 FOR CONNECTOR JOINTING	DE-SAC 12 00 00 00 00 00 00 00	12.00::12.00::16.00' STA 13+37.40 20.00' RT PAVEMENT LIMIT PAVEMENT LIMIT
	NAME = USER NAME = hehn@1663 NAB-HPS-sht-plan22L.dgn	DESIGNED - CBP REVISED - DRAWN - CBP REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LEGEND: SAWED LONGITUDNAL JOINT OR LONGITUDNAL CONSTRUCTION JOINT DOWELED TRANSVERSE CONSTRUCTION JOINT	SECTION COUNTY TOTAL SHEET NO.


© Copyright Harson Professional Sonvices Inc.	STA 6000-23.00 PAVEMENT LIMIT STA 6000-23.00 PAVEMENT LIMIT STA 6000-23.00 PAVEMENT LIMIT STA 6000-23.00 PAVEMENT LIMIT PAVEMENT LIMIT	GERWISE SPECIFIED 6002 6TH AVE (IL 92 EB) 6002	4/10.84', 15' SPACING (TYP.) 12.71', 12.71', 15.00', UNLESS OTHERWISE SPECIFIED
FILE NAME = USER NAME = het DZCONAB-HPS-sht-plan@7L.dgn DZCONAB-HPS-sht-plan@7L.dgn PLOT SCALE = 1' = PLOT DATE = 1/1	LEGEND: SAWED LONGITUDNAL JOINT OR DIMENSIONS SHOWN ON CURVE ARE ALONG CENTERLINE. EDGE LONGITUDNAL CONSTRUCTION JOINT OF PAVEMENT DIMENSIONS BETWEEN JOINTS WILL VARY. DOWNLED TRANSVERSE CONSTRUCTION JOINT	<u> </u>	0 20' 40' SCALE: JT-04


© Copyright Hanson Professional Services Inc.	\$\text{TTH AVE} \tag{2.00\text{TTM}} \tag{3.00\text{TTM}} 3.00\text
10/9/2014 10/16/2014 10/23/2015	LEGEND: SAWED LONGITUDNAL JOINT OR LONGITUDNAL JOINT OR COPPAGENT DIMENSIONS SHOWN ON CURVES ARE ALONG CENTERLINE. EDGE OF PAYEMENT DIMENSIONS BETWEEN JOINT WILL VARY. DOWELED TRANSVERSE CONSTRUCTION JOINT EXPANSION JOINT LONGITUDNAL KEYED JOINT WITHOUT TIE BARS DESCRIPTION OF THE BARS
	SCALE SCAL





SUMMARY	OF QUANTITIES		
PAYITEM	DESCRIPTION	UNIT	QUANTITY
89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1
Z0073510	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	6
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	5





BAGGED OR COVERED SIGNAL HEAD

 THE CONTRACTOR SHALL PROVIDE AND INSTALL EQUIPMENT WITH RESPECT TO THE TEMPORARY TRAFFIC SIGNAL INSTALLATION. THIS SHALL INCLUDE ALL CABLES. SIGNAL HEADS, CONDUIT, WOOD POLES, GUY WIRE ASSEMBLIES, CONTROLLERS, LIGHTING, AND ALL OTHER EQUIPMENT REQUIRED FOR THE INSTALLATION.

ALL TRAFFIC SIGNAL EQUIPMENT SCHEDULED FOR REMOVAL MAY BE USED FOR TEMPORARY TRAFFIC SIGNALS. ANY MAINTENANCE OF THIS EQUIPMENT WHEN USED FOR TEMPORARY TRAFFIC SIGNALS SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR. ALL EQUIPMENT (EXISTING AND PROVIDED BY THE DEPARTMENT) SHALL BE DELIVERED IN GOOD WORKING CONDITION UPON THE REMOVAL OF THE TEMPORARY TRAFFIC SIGNAL INSTALLATION.

3. NEW AERIAL TRAFFIC SIGNAL CABLE SHALL BE FURNISHED AND INSTALLED AS SHOWN ON THE PLAN SHEETS. ALL EXISTING TRAFFIC SIGNAL CABLE WILL BE

4. ALL CABLES SHALL MAINTAIN AN 18 FT. MINIMUM CLEARANCE ABOVE THE EXISTING OR PROPOSED POINT OF THE ROADWAY, WHICHEVER IS HIGHEST.

- 5. ALL TRAFFIC SIGNAL SECTIONS SHALL HAVE 12" LENSES.
- THE TEMPORARY TRAFFIC SIGNAL HEADS SHALL BE PLACED AS INDICATED ON THE PLANS OR AS INDICATED BY THE ENGINEER.
- 7. THE TRAFFIC SIGNAL INSTALLATION SHALL CONFORM TO ALL APPLICABLE MUTCD STANDARDS AND ALL WORK SHALL CONFORM TO NEC REQUIREMENTS.
- 8. ALL LABOR, MATERIALS, AND EQUIPMENT REQUIRED TO COMPLY WITH THESE REQUIREMENTS SHALL BE INCLUDED IN THE PRICE FOR THE TEMPORARY TRAFFIC SIGNAL INSTALLATION.

9. ALL EXISTING TRAFFIC SIGNAL EQUIPMENT, INCLUDING BUT NOT LIMITED TO HANDHOLES, SIGNAL POSTS, MAST ARMS, CONCRETE FOUNDATIONS, CABLE, AND VEHICLE SIGNAL HEADS TO BE REMOVED. SEE SPECIAL PROVISION FOR REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT SPECIFICS.

10. PER IDOT D2 STANDARDS, A 24 INCH BY 24 INCH "TO ACTIVATE SIGNAL" SIGN SHALL BE PLACED AT THE STOP LINE AS DIRECTED BY THE ENGINEER.

11. ALL TRAFFIC SIGNAL HEADS SHALL BE POSITIONED SO THAT THEY FACE THE TRAFFIC LANE THEY CONTROL.

12. ALL FIVE SECTION SIGNAL HEADS PLACED ON SPAN WIRE SHALL HAVE A R10-12 SIGN PLACED IMMEDIATELY TO THE RIGHT OF THE SIGNAL HEAD.

13. FIELD ADJUSTMENTS DURING INSTALLATION MAY BE NECESSARY TO AVOID UTILITIES. THIS IS INCLUDED IN THE COST OF THE TEMPORARY SIGNAL.

14. STOP BARS MUST BE PLACED SO THAT THE FIRST STOPPED CAR CAN CLEARLY SEE THE TRAFFIC SIGNAL FOR THEIR CORRESPONDING MOVEMENT.

FILE NAME =

D2CONAB-HPS-sht-ts340

THE INTERSECTIONS OF 19TH ST WITH 6TH AVE AND 7TH AVE WILL OPERATE WITH THEIR EXISTING SEQUENCE

TRAFFIC SIGNAL PLAN LEGEND

EXISTING	PROPOSED	DESCRIPTION
	⊕ №	TEMP SIGNAL HEAD WITH BACKPLATE TEMPORARY WOOD POLE CONTROLLER
	<u> </u>	CONDUIT VIDEO DETECTION CAMERA LUMINAIRE

		TEMPOR	ARY WOOD PO	LES	
POLE I.D.	STATION	OFFSET	POLE I.D.	STATION	OFFSET
1	7011+14	86' LT	6	7012+47	83' LT
2	7010+25	121' RT	0	7013+29	101' LT
3	7011+09	160' RT	8	7013+21	111' RT
4	7011+97	135' LT	9	7014+26	96' LT
(5)	7012+05	85' LT			

7TH AVENUE / RAMPS

TH WENLE

SUGGESTED TIMINGS (SECONDS)

⋖

PHASE	1	 				7	8
		 			_ •		
MINIMUM GREEN	5		5	5		5	5
PASSAGE	2		2	2		2	2
MAXIMUM 1	16		44	16		23	16
YELLOW CHANGE	4		4	4		4	4
RED CLEARANCE	1		1	1		1	1
RECALL MODE	OFF		MAX	OFF		OFF	MAX
ACTUATED CYCLE LENGTH = 70							

SCALE: 1" = 20' SHEET NO.

TRAFFIC SIGNAL PLANS

TEMPORARY SIGNALS

PRE-STAGE 1

SHEETS STA

TO STA.

PHASE SEQUENCE CHART --08-

PHASE DESIGNATION DIAGRAM


-@→ SECTION COUNTY (81-1)R & 81-1HVBR ROCK ISLAND 1504 468 CONTRACT NO. 64C08


7TH AVENUE

USER NAME = hehn@1663 DESIGNED -DRAWN CHECKED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

TMA REVISED ТМА REVISED KNB REVISED PLOT DATE = 1/19/2017 REVISED DATE 1/20/2017





THE INTERSECTIONS OF 7TH AVE AND THE I-74 RAMPS WILL OPERATE WITH THEIR EXISTING SEQUENCE AND TIMING.

- 1	
	FILE NAME =
EWED	D2CONAB-HPS-sht-ts328

T	USER NAME = hehnØ1663	DESIGNED	-	TMA	REVISED	-
		DRAWN	-	TMA	REVISED	-
	PLOT SCALE = 1" = 20"	CHECKED	-	KNB	REVISED	-
	PLOT DATE = 1/19/2017	DATE	-	1/20/2017	REVISED	-

STATE OF ILLINOIS						
DEPARTMENT	0F	TRANSPORTATION				

7TH AVENUE / RAMPS

TRAFFIC SIGNAL PLANS						F.A.I RTE.	SECTION	
TEMPORARY SIGNALS					74	(81-1)R & 81-1HVBR	F	
PRE-STAGE 3								
CALE: 1" = 20"	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. AI	D

TS-03

COUNTY SHEETS NO.

ROCK ISLAND 1504 470

CONTRACT NO. 64C08

AID PROJECT

FILE NAME =

DEAWNN DEAWNN DSCH-REVIEWED DS

7IH AVENUE • -17011--<u> 1 7013</u> 7TH AVENUE 7TH AVENUE / RAMPS

NOTES:

THE INTERSECTIONS OF 7TH AVE AND THE I-74 RAMPS WILL OPERATE WITH THEIR EXISTING SEQUENCE AND TIMING.

TS-04

COUNTY TOTAL SHEET NO.

ROCK ISLAND 1504 471

CONTRACT NO. 64C08 TRAFFIC SIGNAL PLANS TEMPORARY SIGNALS USER NAME = hehn@1663 DESIGNED - TMA REVISED SECTION STATE OF ILLINOIS DRAWN TMA REVISED (81-1)R & 81-1HVBR SCALE: 1" = 20' SHEET NO. OF SHEETS STA. **DEPARTMENT OF TRANSPORTATION** PLOT SCALE = 1" = 20" CHECKED KNB REVISED PLOT DATE = 1/19/2017 TO STA. DATE 1/20/2017 REVISED

FILE NAME =

DZCONAB-HPS-sht-ts334


7TH AVENUE 7TH AVENUE 7TH AVENUE / RAMPS NOTES: THE INTERSECTIONS OF 7TH AVE AND THE I-74 RAMPS WILL OPERATE WITH THEIR EXISTING SEQUENCE AND TIMING.


TS-05

COUNTY TOTAL SHEET NO.

ROCK ISLAND 1504 472

CONTRACT NO. 64C08 TRAFFIC SIGNAL PLANS
TEMPORARY SIGNALS
STAGE 1-1
SCALE: 1" = 20' SHEET NO. OF SHEETS STA. USER NAME = hehn@1663 DESIGNED - TMA REVISED SECTION STATE OF ILLINOIS DRAWN TMA REVISED (81-1)R & 81-1HVBR **DEPARTMENT OF TRANSPORTATION** PLOT SCALE = 1" = 20" CHECKED KNB REVISED PLOT DATE = 1/19/2017 TO STA. DATE 1/20/2017 REVISED






SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN		5		5		5		
PASSAGE		2		2		2		
MAXIMUM 1		19		31		19		
YELLOW CHANGE		4		4		4		
RED CLEARANCE		1		1		1		
RECALL MODE		MAX		OFF		MAX		
ACTUATED CYCLE	LENGTI	H = 60						

19TH STREET / 7TH AVENUE




PHASE DESIGNATION DIAGRAM

PHASE SEQUENCE CHART

	LGCLITO	'		
@ 	-00	4	- ®-	® @

SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN	5	5	5	5	5	5	5	5
PASSAGE	2	2	2	2	2	2	2	2
MAXIMUM 1	46	16	18	21	10	52	5	33
YELLOW CHANGE	4	4	4	4	4	4	4	4
RED CLEARANCE	1	1	1	1	1	1	1	1
RECALL MODE	OFF	MAX	OFF	MAX	OFF	MAX	OFF	MAX
ACTUATED CYCLE	LENGTH	H = 120						



TMA 11/14/2 TMA 11/16/2 KNB 11/21/2

FILE NAME = D2CONAB-HPS-sht-ts351

 DESIGNED
 TMA
 REVISED


 DRAWN
 TMA
 REVISED


 CHECKED
 KNB
 REVISED

 DATE
 1/20/2017
 REVISED

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION








PHASE DESIGNATION DIAGRAM


PHASE SEQUENCE CHART



SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN		5		5		5		
PASSAGE		2		2		2		
MAXIMUM 1		20		45		20		
YELLOW CHANGE		4		4		4		
RED CLEARANCE		1		1		1		
RECALL MODE		MAX		OFF		MAX		
ACTUATED CYCLE	LENGTI	H = 75						

19TH STREET / 7TH AVENUE




PHASE DESIGNATION DIAGRAM

PHASE SEQUENCE CHART

	L & C L . 1 C	_ 0117111	•		
@ _@_	6 6			- @-	® ®

SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN	5	5	5	5	5	5	5	5
PASSAGE	2	2	2	2	2	2	2	2
MAXIMUM 1	71	16	20	23	21	75	5	38
YELLOW CHANGE	4	4	4	4	4	4	4	4
RED CLEARANCE	1	1	1	1	1	1	1	1
RECALL MODE	OFF	MAX	OFF	MAX	OFF	MAX	OFF	MAX
ACTUATED CYCLE	LENGTH	H = 150						



FILE NAME = D2CONAB-HPS-sht-ts352


USER NAME = hehn@1663 DRAWN PLOT SCALE = 1" = 20" PLOT DATE = 1/19/2017 DATE

DESIGNED -TMA REVISED TMA REVISED CHECKED KNB REVISED REVISED 1/20/2017


STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

TRAFFIC SIGNAL PLANS TEMPORARY SIGNALS SECTION ROCK ISLAND 1504 476

CONTRACT NO. 64C08 (81-1)R & 81-1HVBR STAGE 1-5
OF SHEETS STA. SCALE: 1" = 20' SHEET NO. TO STA.




PHASE SEQUENCE CHART




SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN	5	5	5	5	5	5	5	5
PASSAGE	2	2	2	2	2	2	2	2
MAXIMUM 1	54	61	8	38	8	106	19	27
YELLOW CHANGE	4	4	4	4	4	4	4	4
RED CLEARANCE	1	1	1	1	1	1	1	1
RECALL MODE	OFF	MAX	OFF	OFF	OFF	MAX	OFF	OFF
ACTUATED CYCLE LENGTH = 180								

STAGE 2 - 7TH AVENUE AND 19TH STREET




PHASE SEQUENCE CHART



SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN		5		5		5		
PASSAGE		2		2		2		
MAXIMUM 1		64		16		64		
YELLOW CHANGE		4		4		4		
RED CLEARANCE		1		1		1		
RECALL MODE		MAX		OFF		MAX		
ACTUATED CYCLE LENGTH = 90								

STAGE 2 - 6TH AVENUE AND 19TH STREET




1		

Р	HASE S	EQUENC	E CHAR	Γ
	-®-	-@ -	708—	

SUGGESTED TIMINGS (SECONDS)


6 7 5	8
5	5
2	2
135	25
4	4
1	1
/AX	OFF
	1

STAGE 2 - 4TH AVENUE AND 19TH STREET



PHASE DESIGNATION DIAGRAM


PHASE SEQUENCE CHART




SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN		5	5	5		5	5	5
PASSAGE		2	2	2		2	2	2
MAXIMUM 1		82	5	57		16	5	57
YELLOW CHANGE		4	4	4		4	4	4
RED CLEARANCE		1	1	1		1	1	1
RECALL MODE		MAX	OFF	OFF		MAX	OFF	OFF
ACTUATED CYCLE LENGTH = 180								

STAGE 2 - RIVER DRIVE AND 19TH STREET



PHASE SEQUENCE CHART



SUGGESTED TIMINGS (SECONDS)

000020			1		0 0 .			
PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN			5	5	5			5
PASSAGE			2	2	2			2
MAXIMUM 1			11	48	16			64
YELLOW CHANGE			4	4	4			4
RED CLEARANCE			1	1	1			1
RECALL MODE			OFF	OFF	MAX			OFF
ACTUATED CYCLE LENGTH = 90)							

STAGE 2 - RIVER DRIVE AND I-74 RAMPS


SCALE: NTS

- 1					
	FILE NAME =	USER NAME = hehnØ1663	DESIGNED -	TMA	REVISED -
3	D2CONAB-HPS-sht-ts337		DRAWN -	TMA	REVISED -
		PLOT SCALE = NTS	CHECKED -	KNB	REVISED -
١!		DI DT DATE 1 (10 (DOL)	DATE	1 (20 (2017	DEVICED

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**


								T	S-11
TRAFFIC SIGNAL PLANS					F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TEMPORARY SIGNALS					74	(81-1)R & 81-1HVBR	ROCK ISLAND	1504	478
		STAGE 2					CONTRACT	NO. 6	4C08
SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. A	D PROJECT		





PHASE DESIGNATION DIAGRAM


PHASE SEQUENCE CHART



SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN				5	5			5
PASSAGE				2	2			2
MAXIMUM 1				124	46			124
YELLOW CHANGE				4	4			4
RED CLEARANCE				1	1			1
RECALL MODE				MAX	OFF			MAX
ACTUATED CYCLE LENGTH = 180								

WINTER STAGE - 7TH AVENUE AND RAMPS




PHASE SEQUENCE CHART

•	11/136 3	_ 40,0		<u>'</u>	
	@ 	-@-	-(j) (j) -(j)		-® -Ø


SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	٦.	4	5	6	7	8
MINIMUM GREEN	5	5	5	5	5	5	5	5
PASSAGE	2	2	2	2	2	2	2	2
MAXIMUM 1	74	23	8	55	12	85	5	58
YELLOW CHANGE	4	4	4	4	4	4	4	4
RED CLEARANCE	1	1	1	1	1	1	1	1
RECALL MODE	OFF	MAX	OFF	OFF	OFF	MAX	OFF	OFF
ACTUATED CYCLE LENGTH = 180								

WINTER STAGE - 7TH AVENUE AND 19TH STREET




PHASE SEQUENCE CHART




SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN		5				5	5	
PASSAGE		2				2	2	
MAXIMUM 1		72				72	98	
YELLOW CHANGE		4				4	4	
RED CLEARANCE		1				1	1	
RECALL MODE		MAX				MAX	OFF	
ACTUATED CYCLE LENGTH = 180								

WINTER STAGE - 6TH AVENUE AND 19TH STREET




PHASE SEQUENCE CHART



SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN				5	5			5
PASSAGE				2	2			2
MAXIMUM 1				63	37			63
YELLOW CHANGE				4	4			4
RED CLEARANCE				1	1			1
RECALL MODE				MAX	OFF			MAX
ACTUATED CYCLE LENGTH = 110								

STAGE 3 - 7TH AVENUE AND RAMPS




PHASE SEQUENCE CHART

	@		@-
		<u>-@</u> −	- @-


SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN	5	5	5	5	5	5	5	5
PASSAGE	2	2	2	2	2	2	2	2
MAXIMUM 1	21	24	19	26	14	31	5	40
YELLOW CHANGE	4	4	4	4	4	4	4	4
RED CLEARANCE	1	1	1	1	1	1	1	1
RECALL MODE	OFF	MAX	OFF	OFF	OFF	MAX	OFF	OFF
ACTUATED CYCLE LENGTH = 110								

STAGE 3 - 7TH AVENUE AND 19TH STREET



PHASE DESIGNATION DIAGRAM



SUGGESTED TIMINGS (SECONDS)

PHASE	1	2	3	4	5	6	7	8
MINIMUM GREEN		5		5		5		
PASSAGE		2		2		2		
MAXIMUM 1		74		26		74		
YELLOW CHANGE		4		4		4		
RED CLEARANCE		1		1		1		
RECALL MODE		MAX		OFF		MAX		
ACTUATED CYCLE LENGTH = 110							•	


STAGE 3 - 6TH AVENUE AND 19TH STREET

SCALE: NTS


	FILE NAME =
EWED	D2CONAB-HPS-sht-ts339

USER NAME = hehn@1663	DESIGNED	-	TMA	REVISED	-
	DRAWN	-	TMA	REVISED	-
PLOT SCALE = NTS	CHECKED	-	KNB	REVISED	-
PLOT DATE = 1/19/2017	DATE	-	1/20/2017	REVISED	-


				TS	5-12
TRAFFIC SIGNAL PLANS	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
TEMPORARY SIGNALS	74	(81-1)R & 81-1HVBR	ROCK ISLAND	1504	479
WINTER STAGE AND STAGE 3			CONTRACT	NO. 6	4C08
SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. AI	D PROJECT		







PAYITEM	DESCRIPTION	UNIT	QUANTITY
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2
80500100	SERVICE INSTALLATION, TYPE A	EACH	1
81028190	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.	FOOT	11
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	80
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	28
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	16
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	28
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1153
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3200
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	28
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	644
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	5
87702860	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 26 FT.	EACH	1
87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1
87700410	STEEL MAST ARM ASSEMBLY AND POLE, 65 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	15
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	13
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	16
87900200	DRILL EXISTING HANDHOLE	EACH	9
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	7
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	1
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	15
	PEDESTRIAN PUSH-BUTTON	EACH	3
X0322281	WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1



PHASE DESIGNATION DIAGRAM

- 1. SEE STANDARD PLAN 857001 FOR SEQUENCING
- 2. SEE LIGHTING SHEETS FOR LUMIAIRE WIRING AND DETAILS

TRAFFIC SIGNAL PLANS COUNTY SECTION STATE OF ILLINOIS CABLE PLAN ROCK ISLAND 1504 481


CONTRACT NO. 64C08 74 (81-1)R & 81-1HVBR RIVER DRIVE AND RAMP RD-G
SHEET NO. OF SHEETS STA. SCALE: NTS TO STA.

TMA	TMA	Вим	
			FILE NAME =
Г		0	D2CONAB-HPS-sht-ts004L.dgn

USER NAME = hehn@1663 DESIGNED - TMA REVISED REVISED DRAWN TMA CHECKED BWW REVISED PLOT DATE = 1/19/2017 DATE REVISED 1/20/2017

DEPARTMENT OF TRANSPORTATION





SUMMARY OF QUANTITIES

PAY ITEM	DESCRIPTION	UNIT	QUANTITY
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	1
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	106
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	20
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	153
81400100	HANDHOLE	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	571
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	609
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1719
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	258
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	386
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	1
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	3
87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1
87700220	STEEL MAST ARM ASSEMBLY AND POLE, 36 FT.	EACH	1
87700300	STEEL MAST ARM ASSEMBLY AND POLE, 52 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	18
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	29
87900200	DRILL EXISTING HANDHOLE	EACH	8
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	4
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	6
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	1
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	1
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	12
88800100	PEDESTRIAN PUSH-BUTTON	EACH	6
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
X0322281	WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1
X0327008	REMOVE AND RELOCATE SIGN (SPECIAL)	EACH	1
X8140115	HANDHOLE TO BE ADJUSTED	EACH	2
X0325206	RELOCATE INTERCONNECT CABLE	FOOT	163

1. THE RAILROAD INTERCONNECT AND PREEMMPTION SHALL BE MAINTAINED.

COUNTY TOTAL SHEET NO.

ROCK ISLAND 1504 483 TRAFFIC SIGNAL PLANS SECTION STATE OF ILLINOIS CABLE PLAN (81-1)R & 81-1HVBR SHEET NO. OF SHEETS STA. CONTRACT NO. 64C08 SCALE: NTS TO STA.

|2CONAB-HPS-sht-ts202.dgn

EXISTING SERVICE

USER NAME = hehn@1663 DESIGNED -TMA REVISED DRAWN TMA REVISED CHECKED BWW REVISED REVISED PLOT DATE = 1/19/2017 DATE 1/20/2017

DEPARTMENT OF TRANSPORTATION



C k \$ \$ \$ \$ R R C R Y C C G ≺ R [O] × 70 - (5)-NO. 6-**▶V**-Vo≺⊅-5o≺¬-5-6TH AVENUE ≫ € -NUMBER OF GROUND CABLES AS PER PLAN NO. 6 - INTERCONNECT TO 7TH AVENUE (SEE INTERCONNECT PLAN) TRAFFIC SIGNAL WIRING DIAGRAM LEGEND DESCRIPTION ELECTRIC CABLE DENOTING NUMBER OF CONDUCTORS m ≻o SIGNAL FACE WITH BACKPLATE (P2) DIRECTIONAL SIGNAL SECTION R 12" SIGNAL SECTION WALK/DON'T WALK SECTION + COUNT DOWN P2 -GROUND WIRE (POLE) GROUND WIRE (MAST ARM) PEDESTRIAN PUSHBUTTON PHASE DESIGNATION DIAGRAM CONDUIT V● VIDEO DETECTION CAMERA 1. SEE STANDARD PLAN 857001 FOR SEQUENCING 2. SEE LIGHTING SHEETS FOR LUMINAIRE WIRING AND DETAILS COAXIAL CABLE UPS UNINTERUPTIBLE POWER SUPPLY \boxtimes CONTROLLER

DESIGNED -

DRAWN

DATE

CHECKED

TMA

TMA

BWW

1/20/2017

REVISED

REVISED

REVISED

REVISED

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION

USER NAME = hehn@1663

PLOT DATE = 1/19/2017

D2CONAB-HPS-sht-ts308

TRAFFIC SIGNAL PLANS

TRAFFIC SIGNAL CABLE PLAN

 6TH
 AVENUE AND RAMP 6TH-C AND RAMP 6TH-D

 SCALE: NTS
 SHEET NO. OF SHEETS STA. TO STA.

PAY ITEM	DESCRIPTION	UNIT	QUANTITY
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	1
80500100	SERVICE INSTALLATION, TYPE A	EACH	1
81028190	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.	FOOT	14
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	138
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	16
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	288
81400100	HANDHOLE	EACH	3
81400300	DOUBLE HANDHOLE	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1268
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1319
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 145C	FOOT	2681
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	17
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	571
87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL 10 FT.	EACH	1
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	3
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1
87704516	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 48 FT. AND 30 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12
	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	29
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	9
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	4
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	14
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8
X0322281	WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1

ROCK ISLAND 1504 485

CONTRACT NO. 64C08


COUNTY


F.A.I RTE. 74


SECTION

(81-1)R & 81-1HVBR









NOTES:

1. ALL DISTURBED AREAS SHALL BE RESTORED LANDSCAPED AND TO PRIOR CONDITION.

2. THE POWER SUPPLY SHALL BE TAKEN FROM THE EXISTING METER, IN COORDINATION WITH THE UTILITY COMPANY, AND RELOCATED FROM EXISTING CONTROLLER TO THE PROPOSED CONTROLLER. ADDITIONAL ELECTRICAL SERVICE CABLE AND 1.5" GALVANIZED STEEL CONDUIT MAY BE NEEDED. TO BE INCLUDED IN COST OF CONTROLLER.

3. ALL PUSH BUTTONS SHALL BE PLACED IMMEDIATELY NEXT TO PEDESTRIAN LANDING AREAS. ALL PUSH BUTTONS SHALL BE A MINIMUM OF 10 FEET APART.

DEAWN I AM BELL NAME = DZCONAB-HPS-sht-ts309


USER NAME = hehnØ1663	DESIGNED	-	TMA	REVISED	-
	DRAWN	-	TMA	REVISED	-
PLOT SCALE = 1" = 20"	CHECKED	-	BWW	REVISED	-
PLOT DATE = 1/19/2017	DATE	-	1/20/2017	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

				Τ.	S-19
TRAFFIC SIGNAL PLANS	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEE'
6TH AVENUE AND 19TH STREET	74	(81-1)R & 81-1HVBR	ROCK ISLAND	1504	486
			CONTRACT	NO. 6	4C08
SCALE: 1" = 20' SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. A	ID PROJECT		



D2CONAB-HPS-sht-ts310



DESIGNED -

TMA

BWW

1/20/2017

DRAWN

DATE

PLOT DATE = 1/19/2017

CHECKED

REVISED

REVISED

REVISED

REVISED

STATE OF ILLINOIS

DEPARTMENT OF TRANSPORTATION


SUMMARY OF QUANTITIES

PAYITEM	DESCRIPTION	UNIT	QUANTITY
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	61
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	53
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	294
81400100	HANDHOLE	EACH	1
81400300	DOUBLE HANDHOLE	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1184
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	1227
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2516
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	590
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	4
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	2
87700150	STEEL MAST ARM ASSEMBLY AND POLE, 22 FT.	EACH	1
87700230	STEEL MAST ARM ASSEMBLY AND POLE, 38 FT.	EACH	2
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	12
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	48
87900200	DRILL EXISTING HANDHOLE	EACH	6
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	7
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	4
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	13
88800100	PEDESTRIAN PUSH-BUTTON	EACH	8
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
X0322281	WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1

TRAFFIC SIGNAL PLANS F.A.I RTE. 74 SECTION COUNTY TRAFFIC SIGNAL CABLE PLAN ROCK ISLAND 1504 487

CONTRACT NO. 64C08 (81-1)R & 81-1HVBR 6TH AVENUE AND 19TH STREET
SHEET NO. OF SHEETS STA. SCALE: NTS TO STA.





CHECKED

DATE

PLOT DATE = 1/19/2017

BWW

1/20/2017

REVISED

REVISED


DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

PAYITEM	DESCRIPTION	UNIT	QUANTITY
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	2
80500100	SERVICE INSTALLATION, TYPE A	EACH	1
81028190	UNDERGROUND CONDUIT, GALVANIZED STEEL, 1 1/2" DIA.	FOOT	13
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	66
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	41
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	336
81400100	HANDHOLE	EACH	3
81400300	DOUBLE HANDHOLE	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 142C	FOOT	197
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 143C	FOOT	211
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	3605
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	16
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	549
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	2
87702950	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 44 FT.	EACH	1
87702985	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 52 FT.	EACH	1
87700430	STEEL MAST ARM ASSEMBLY AND POLE, 75 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	6
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	35
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	25
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	6
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	8
88102825	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED WITH COUNT DOWN TIMER	EACH	2
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	14
88800100	PEDESTRIAN PUSH-BUTTON	EACH	2
X0322281	WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1

TRAFFIC SIGNAL PLANS SECTION COUNTY TRAFFIC SIGNAL CABLE PLAN 74 ROCK ISLAND 1504 489 (81-1)R & 81-1HVBR 7TH AVENUE AND CONNECTOR (RAMP 7TH-A)
SHEET NO. OF SHEETS STA. TO STA. CONTRACT NO. 64C08





SUMMARY OF QUANTITIES

PAYITEM	DESCRIPTION	UNIT	QUANTIT
50200400	ROCK EXCAVATION FOR STRUCTURES	CU YD	3
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	238
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	60
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	538
81400100	HANDHOLE	EACH	4
81400300	DOUBLE HANDHOLE	EACH	1
85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	1
86200200	UNINTERRUPTABLE POWER SUPPLY, STANDARD	EACH	1
86400100	TRANSCEIVER - FIBER OPTIC	EACH	1
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	2350
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2440
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	4101
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	2315
87301900	ELECTRIC CABLE IN CONDUIT, EQUIPMENT GROUNDING CONDUCTOR, NO. 6 1C	FOOT	1066
87502510	TRAFFIC SIGNAL POST, GALVANIZED STEEL 17 FT.	EACH	6
87600100	PEDESTRIAN PUSH-BUTTON POST, TYPE I	EACH	4
87703060	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 65 FT.	EACH	1
87703090	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 70 FT.	EACH	1
87703110	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 74 FT.	EACH	1
87702198	STEEL MAST ARM ASSEMBLY AND POLE WITH DUAL MAST ARMS, 16 FT. AND 42 FT.	EACH	1
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	18
87800150	CONCRETE FOUNDATION, TYPE C	FOOT	3
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	14
87800420	CONCRETE FOUNDATION, TYPE E 42-INCH DIAMETER	FOOT	75
88040070	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, BRACKET MOUNTED	EACH	5
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	11
88040150	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, BRACKET MOUNTED	EACH	5
88040160	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	3
00400005	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, BRACKET MOUNTED	E 4 O L I	
88102825	WITH COUNT DOWN TIMER	EACH	6
88102845	PEDESTRIAN SIGNAL HEAD, POLYCARBONATE, LED, 2-FACE, BRACKET MOUNTED	EACH	
00102045	WITH COUNT DOWN TIMER	EACH	2
88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	24
88800100	PEDESTRIAN PUSH-BUTTON	EACH	10
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
X0322281	WIDE AREA VIDEO DETECTION SYSTEM COMPLETE	EACH	1

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**

TRAFFIC SIGNAL PLANS TRAFFIC SIGNAL CABLE PLAN 7TH AVENUE AND 19TH STREET
SHEET NO. OF SHEETS STA. TO STA.

SECTION COUNTY ROCK ISLAND 1504 491 (81-1)R & 81-1HVBR CONTRACT NO. 64C08

D2CONAB-HPS-sht-ts314

USER NAME = hehn@1663

PLOT DATE = 1/19/2017

DESIGNED -

DRAWN

DATE

CHECKED

TMA

TMA

BWW

1/20/2017

OVERLAP .ETTER	PERMISSIVE PHASE	PROTECTED PHASE
Α	2	3
С	6	7


REVISED

REVISED

REVISED

REVISED

PAY ITEM	DESCRIPTION	UNIT	QUANTITY
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	42
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	546
87800100	CONCRETE FOUNDATION, TYPE A	FOOT	3
87900200	DRILL EXISTING HANDHOLE	EACH	1
88040090	SIGNAL HEAD, POLYCARBONATE, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2
89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1
89501150	RELOCATE EXISTING TRAFFIC SIGNAL POST	EACH	1
89502200	MODIFY EXISTING CONTROLLER	EACH	1




NOTE: SEE STANDARD PLAN 857001 FOR SEQUENCING

NOTES:

- ALL DISTURBED AREAS SHALL BE LANDSCAPED AND RESTORED TO PRIOR
- 2. 5c#14 CABLE SHALL BE USED TO WIRE PROPOSED SIGNAL HEADS. ALL CABLES SHALL RUN FROM APPARATUS TO CONTROLLER. CABLE SPLICING IS NOT ALLOWED.

 3. EXISTING CONTROLLER TO BE MODIFIED FOR UPDATED PHASING AND SEQUENCING.

TRAFFIC SIGNAL PLAN LEGEND



VIDEO DETECTION CAMERA SIGN ON MAST ARM


SERVICE INSTALLATION

USER NAME = hehnØ1663	DESIGNED	-	TMA	REVISED	-
	DRAWN	-	TMA	REVISED	-
PLOT SCALE = 1" = 20"	CHECKED	-	BWW	REVISED	-
PLOT DATE = 1/19/2017	DATE	-	1/20/2017	REVISED	-

STATE OF ILLINOIS **DEPARTMENT OF TRANSPORTATION**


TRAFFIC SIGNAL PLANS RIVER DRIVE AND RAMP RD-H

SECTION COUNTY (81-1)R & 81-1HVBR ROCK ISLAND 1504 492 CONTRACT NO. 64C08 SCALE: 1" = 20' SHEET NO. OF SHEETS STA. TO STA.





THIS SIGN SHALL BE LOCATED 0'-9"

FILE NAME = D2CONAB-HPS-sht-tsl01L.dgn









NOTE: SEE SIGNING SCHEDULE FOR SIGNAGE DETAILS AND QUANTITIES

TRAFFIC SIGNAL GENERAL NOTES

- ALL TRAFFIC SIGNAL SECTIONS SHALL HAVE 12" SINGLE LED LENSES.
 ALL PEDESTRIAN SECTIONS SHALL HAVE 16" LENSES WITH A MAN/HAND OVERLAY AND COUNTDOWN TIMER.
 THE RED SECTIONS OF THE SIGNAL HEADS SHARING THE SAME MAST ARM SHALL BE LEVEL WITH ONE ANOTHER AND MAINTAIN A 16' MINIMUM CLEARANCE FROM THE HIGHEST POINT OF THE

- ROADWAY.

 4. THE PROPOSED MAST ARM MOUNTED TRAFFIC SIGNAL HEADS SHALL BE MOUNTED DIRECTLY OVER THE CENTER OF THEIR RESPECTIVE LANES.

 5. ALL TRAFFIC SIGNAL HEAD BRACKETS ARE TO BE ALUMINUM WITH A NATURAL FINISH.

 6. ALL TRAFFIC SIGNAL POSTS ARE TO BE GALVANIZED STEEL.

 7. PROPOSED HANDHOLES SHALL BE CAST IN PLACE CONCRETE HANDHOLES.

 8. THE HANDHOLES SHALL BE CONSTRUCTED SO THAT THE TOP OF THE FRAME WILL BE FLUSH WITH THE SURFACE OF THE MEDIAN, SIDEWALK, OR GROUND LINE.

 9. THE LOCATION OF ALL UTILITIES SHALL BE FIELD VERIFIED BY THE CONTRACTOR BEFORE THE INSTALLATION OF ANY TRAFFIC SIGNAL COMPONENTS.

 10. COILABLE POLYETHYLENE DUCT MAY BE SUBSTITUTED FOR PVC CONDUIT 2" FOR THE INTERCONNECT.

 11. THE CONTRACTOR MAY ELECT TO PUSH A CONDUIT THAT IS SHOWN TO BE TRENCHED ON THE PLANS. HOWEVER, THIS WORK WILL BE MEASURED FOR PAYMENT AND PAID FOR AS CONDUIT IN TRENCH OF THE TYPE AND SIZE SPECIFIED AND TRENCH AND BACKFILL FOR ELECTRICAL WORK.

 12. THE LOCATIONS FOR HANDHOLES, TRAFFIC SIGNAL POST FOUNDATIONS, AND MAST ARM FOUNDATIONS ARE PROVIDED FOR REFERENCE ONLY. THE ENGINEER SHALL BE NOTIFIED FOR LOCATION VERIFICATIONS BEFORE INSTALLATION.

- 13. ALL SURPLUS MATERIALS SHALL BE DISPOSED OF IN ACCORDANCE WITH ARTICLE 202.03 OF THE STANDARD SPECIFICATIONS.

 14. NO ADDITIONAL COMPENSATION SHALL BE ALLOWED FOR PLACING CONDUIT AT GREATER THAN 2 FT. MINIMUM DEPTH TO AVOID OBSTACLES SUCH AS UNDERGROUND UTILITIES.

 15. THE CONTRACTOR IS RESPONSIBLE FOR THE COST OF UNCOVERING OR HAND DIGGING AROUND UTILITIES AS NECESSARY. THIS COST OF THIS WORK SHALL BE INCLUDED IN THE UNIT PRICES FOR THE CONDUITS.
- 16. ALL TRAFFIC SIGNAL MAST ARMS, POSTS, HANDHOLE LIDS AND RINGS, HANDHOLE FRAMES, CONTROLLER CABINETS, SERVICE RISERS, EXPOSED METALLIC CONDUITS, AND PHOTOCELL RELAYS SHALL BE GROUNDED IN ACCORDANCE WITH NEC REQUIREMENTS.

 17. A 1/4" DIAMETER CONTINUOUS NYLON ROPE SHALL BE FURNISHED AND LEFT IN PLACE IN ALL CONDUITS BETWEEN HANDHOLES AND FOUNDATIONS OR CONTROLLER.


 18. STREET SIGNS WILL MEET MUTCD, CITY OF MOLINE, AND IDOT STANDARDS. DETAILS ARE NOT PROVIDED. INFORMATION PROVIDED IS FOR VISUAL REPRESENTATION ONLY.


NOTES FOR NON-STANDARD, "REVISED DESIGN", CONCRETE FOUNDATION, TYPE E

- THESE FOUNDATIONS HAVE BEEN DESIGNED FOR THE SITE-SPECIFIC SOIL CONDITIONS.
 MINIMUM SOIL STRENGTH REQUIREMENTS SHOWN IN STD 878001 DO NOT APPLY TO THESE
- 2. MINIMUM SOIL STRENGTH REGISTRATIONS.
 3. WHERE THE PLANS INDICATE A ROCK SOCKET, THIS IS THE MINIMUM LENGTH OF FOUNDATION EMBEDDED IN BEDROCK. THE FOUNDATION SHALL BE LENGTHENED IF NECESSARY TO SATISFY THIS REQUIREMENT.
 4. WHERE THE PLANS INDICATE BEARING ON ROCK, THE FOUNDATION SHALL HAVE FULL BOTTOM CONTACT ON BEDROCK. THE FOUNDATION SHALL BE LENGTHENED IF NECESSARY TO
- REINFORCEMENT SHALL BE AS SHOWN IN STD 878001 FOR THE DIAMETER INDICATED.

<u>a</u>								15-27
FILE NAME =	USER NAME = hehnØ1663	DESIGNED - TMA	REVISED -		TRAFFIC SIGNAL PLANS	F.A.I	SECTION	COUNTY TOTAL SHEET
D2CONAB-HPS-sht-ts008L.dgn		DRAWN - TMA	REVISED -	STATE OF ILLINOIS	TRAFFIC SIGNAL NOTES AND LOADING DIAGRAMS	74	(81-1)R & 81-1HVBR	ROCK ISLAND 1504 494
NATE NATIONAL PROPERTY OF THE	PLOT SCALE = NTS	CHECKED - BWW	REVISED -	DEPARTMENT OF TRANSPORTATION				CONTRACT NO. 64C08
뿐	PLOT DATE = 1/19/2017	DATE - 1/20/2017	REVISED -		SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.		ILLINOIS FED. A	







NOTE: SEE SIGNING SCHEDULE FOR SIGNAGE DETAILS AND QUANTITIES

19TH STREET AND 6TH AVENUE

													TS-28
	FILE NAME =	USER NAME = hehnØ1663	DESIGNED -	TMA	REVISED -			TRAFFIC SIGNAL PLANS		F.A.I	SECTION	COUNTY	TOTAL SHEET
_ Q	D2CONAB-HPS-sht-ts322		DRAWN -	TMA	REVISED -	STATE OF ILLINOIS		LOADING DIAGRAMS		74	(81-1)R & 81-1HVBR	ROCK ISLAND	1504 495
YOU		PLOT SCALE = NTS	CHECKED -	BWW	REVISED -	DEPARTMENT OF TRANSPORTATION						CONTRACT	NO. 64C08
LAY BEVI]	PLOT DATE = 1/19/2017	DATE -	1/20/2017	REVISED -		SCALE: NTS	SHEET NO. OF SHEETS STA.	TO STA.		ILLINOIS FED.	AID PROJECT	

LAYOUT TWA

NOTE: SEE SIGNING SCHEDULE FOR SIGNAGE DETAILS AND QUANTITIES USER NAME = hehnØ1663 DESIGNED - TMA D2CONAB-HPS-sht-ts323 DRAWN

PLOT DATE = 1/19/2017

NW CORNER

NW CORNER

<u>ne island</u>

TMA

- 1/20/2017

CHECKED - BWW

DATE

SE CORNER

REVISED

REVISED

REVISED

REVISED

SE CORNER

<u>19TH</u>	STREET	AND	7TH	AVENUE

SW CORNER

NE ISLAND X2 NW CORNER SE CORNER

										T:	S-29
OTATE OF HAMBIOLO	TRAFFIC SIGNAL PLANS						F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
STATE OF ILLINOIS	LOADING DIAGRAMS					74	(81-1)R & 81-1HVBR	ROCK ISLAND	1504	496	
DEPARTMENT OF TRANSPORTATION									CONTRACT	NO. 6	54C08
	SCALE: NTS	SHEET NO.	OF	SHEETS	STA.	TO STA.		ILLINOIS FED. A	ID PROJECT		

NW CORNER

ROADWAY LIGHTING GENERAL NOTES

- 1. ELECTRICAL EQUIPMENT, RACEWAY, ETC. ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. CONTRACTOR SHALL INSTALL ELECTRICAL EQUIPMENT, RACEWAYS, ETC. WHERE DIRECTED BY THE ENGINEER IN ORDER TO BEST SUIT JOB CONDITIONS.
- 2. ALL REPLACEMENT AND TEMPORARY WIRING SHALL BE EQUAL TO OR GREATER THAN THE EXISTING WIRE GAUGE.
- 3. NO SPLICING OF EXISTING-TO-NEW WIRING IS ALLOWED INSIDE ELECTRICAL DUCTS. ALL WIRING INTERCONNECTIONS SHALL BE INSTALLED IN ACCESSIBLE AREAS AND SHALL BE MADE WITH ILLINOIS DOT APPROVED CONNECTORS.
- 4. ALL LIQUID-TIGHT FLEXIBLE CONDUIT SHALL BE INCIDENTAL TO THE CONDUIT ATTACHED TO STRUCTURE OF THE SIZE SPECIFIED.
- 5. NO POLES TO BE INSTALLED IN THE FLOWLINE OF THE DITCH. POLE SETBACK SHALL BE ADJUSTED IF NECESSARY AS DIRECTED BY THE ENGINEER.
- 6. ELECTRIC SERVICE INSTALLATION SHALL INCLUDE ALL CONDUIT AND CABLE REQUIRED BETWEEN THE UTILITY SERVICE AND THE LIGHTING CONTROLLER.
- 7. ALL CONDUIT UNDER ROADWAYS SHALL BE PVC SCHEDULE 80.
- 8. THE GROUND CONDUCTOR SHALL HAVE NO SPLICE OR KINCKS BELOW GRADE. IT SHALL BE SOLIDLY CONNECTED TO THE GROUNDING LUG OF EACH POLE, JUNCTION BOX, AND TO THE GROUND ROD AT THE SERVICE INSTALLATION.

IN AREAS WHERE MULTIPLE CIRCUIT CONDUCTORS SHARE A COMMON CONDUIT, A COMMON EQUIPMENT GROUND SHALL BE UTILIZED.

- 9. THE CONTRACTOR SHALL PROVIDE A 1/4" POLY PULL-LINE THROUGH EACH PVC CONDUIT IN WHICH NO CONDUCTORS ARE PLACED IN THIS CONTRACT. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE PRICE FOR THE CONDUIT SPECIFIED.
- 10. JUNCTION BOXES OF "SLIGHTLY" LARGER SIZE THAN THOSE SPECIFIED ON THE PLANS MAY BE USED WHEN APPROVED BY ENGINEER AT NO ADDITIONAL COST TO THE CONTRACT.
- 11. EXISTING AND/OR TEMPORARY LIGHTING UNITS SHALL NOT BE REMOVED UNTIL NEW LIGHTING SYSTEM IS COMPLETELY INSTALLED AND FULLY OPERATIONAL TO THE SATISFACTION OF THE
- 12. CONTRACTOR SHALL PROVIDE STAINLESS STEEL SCREEN UNDERNEATH THE ALUMINUM SKIRT OF THE BREAKAWAY COUPLINGS. THE COST OF THE SCREEN SHALL BE INCLUDED IN THE COST OF THE COUPLINGS. SKIRT SHALL BE PAINTED BLACK TO MATCH LIGHT POLES.
- 13. REMOVAL AND DISPOSAL OF ALL LIGHT POLES AND UNDERPASS LUMINAIRES ATTACHED TO BRIDGE STRUCTURES SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED "REMOVAL OF EXISTING STRUCTURES" PAY ITEM. PLEASE SEE STRUCTURAL REMOVAL PLANS DEMOLITION PLAN FOR ADDITIONAL INFORMATION.
- 14. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING STATE OWNED LIGHTING AND/OR TRAFFIC SIGNAL UTILITIES WITHIN THE LIMITS OF THE CONTRACT.
- 15. EXPANSION/DEFLECTION COUPLINGS SHALL BE INSTALLED IN ALL LOCATIONS BETWEEN STRUCTURES, AT EXPANSION JOINTS, AND WHERE NECESSARY TO CONTROL MOVEMENT THAT WOULD DAMAGE THE CONDUIT. THE COST OF EXPANSION/DEFLECTION COUPLINGS SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED CONDUIT AS CALLED OUT ON THE PLANS.

ESTIMATED PROJECT QUANTITIES

PAY ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	86
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	4,997
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	1,404
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	2,292
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	3,845
81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA. PVC	FOOT	2,646
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA. PVC	FOOT	8,191
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	90
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	50
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x12"x6"	EACH	6
81301290	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12"x12"x6"	EACH	4
81400100	HANDHOLE	EACH	10
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,497
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	74,255
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	22,605
82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP	EACH	1
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	10
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	126
83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	60
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	38
84200804	REMOVAL OF POLE FOUNDATION	EACH	36
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	4
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	4
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	3
87900200	DRILL EXISTING HANDHOLE	EACH	1
X0326357	ROADWAY LIGHTING MODIFICATIONS	L SUM	1
X0327006	ROADWAY LIGHT POLE, INSTALL ONLY	EACH	41
X1400128	REMOVE AND REPLACE EXISTING CIRCUIT BREAKER WITH 40 AMP, 2-POLE	EACH	2
X8110454	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., STAINLESS STEEL	FOOT	10
X8110458	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., STAINLESS STEEL	FOOT	80
X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	1
X8360310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	9
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1
#2000324	ROADWAY LUMINAIRE, SPECIAL (INSTALL ONLY)	EACH	59
#2000325	AESTHETIC LUMINAIRE, (INSTALL ONLY)	EACH	71
#2000326	UNDERPASS LUMINAIRE, (INSTALL ONLY)	EACH	25

LIGHTING LEGEND

PROPOSED ELECTRIC SERVICE INSTALLATION

PROPOSED LIGHTING CONTROLLER, 240V, 100A (UNLESS OTHERWISE NOTED)

PROPOSED HANDHOLE

PROPOSED LED STREET LIGHT, 50 FT MOUNTING HEIGHT, 14 FT MAST ARM (UNLESS OTHERWISE NOTED)

PROPOSED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, TWIN 14 FT MAST ARMS (UNLESS OTHERWISE NOTED)

PROPOSED BRIDGE MOUNTED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, 14 FT MAST ARM (UNLESS OTHERWISE STATED)

PROPOSED BRIDGE MOUNTED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, TWIN 14 FT MAST ARMS, (UNLESS OTHERWISE NOTED)

PROPOSED TRAFFIC SIGNAL / STREET LIGHT COMBINATION

PROPOSED UNDERPASS LUMINAIRE, LED. VERY LOW WATTAGE

PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AS NOTED

PROPOSED CONDUIT EMBEDDED IN STRUCTURE, SIZE AS NOTED

EXISTING LIGHTING CONTROLLER TO REMAIN \bowtie EXISTING LIGHTING UNIT TO REMAIN

EXISTING LIGHT TO BE MODIFIED

EXISTING LIGHT TO BE REMOVED

EXISTING LIGHT TO BE RELOCATED

EXISTING LIGHTING CONTROLLER TO BE REMOVED \boxtimes .

-□; EXISTING ELECTRIC SERVICE INSTALLATION TO BE REMOVED

TEMPORARY LIGHTING UNIT, AS NOTED ON PLANS

3"-72'-T) CONDUIT CALLOUT INSTALLATION METHOD (UNDERGROUND UNLESS OTHERWISE SPECIFIED, EMBEDDED IN STRUCTURE OR ATTACHED TO STRUCTURE)

- CONDUIT LENGTH

- CONDUIT DIAMETER

1-A-01 LIGHT POLE DESIGNATION

- POLE NUMBER

CIRCUIT

CONTROL CABINET

	*	beneschengineers - scientists - planne) ers
- 1	FILE NAME	-	119

D2CONAB-AB-sht-light400.dgn

Alfred Benesch & Company 205 North Michigan Avenue, Suite 2400 Chicago, Illinois 60601 Job No. 10064

USER NAME =	DESIGNED	-	GHT	REVISED	-
	DRAWN	-	JLW	REVISED	-
PLOT SCALE = NO SCALE	CHECKED	-	GRR	REVISED	-
PLOT DATE = 1/30/2017	DATE	-	2/5/2016	REVISED	-

LIGHTING REMOVAL DATA									
	LOCAT	ION							
STATION	OFFSET	ALIGNMENT	OWNER	REMARKS					
162+98	20' RT	EX I-74	IDOT						
166+24	12' RT	EX I-74	IDOT						
169+93	10' RT	EX I-74	IDOT						
172+12	48' LT	EX I-74	IDOT						
173+76	22' RT	EX I-74	IDOT						
368+31	18' LT	EX I-74	IDOT						
370+27	26' LT	EX I-74	IDOT						
403+35	25' RT	EX 4TH AVENUE	CITY OF MOLINE	RELOCATE LIGHT POLE					
407+46	15' RT	EX 4TH AVENUE	CITY OF MOLINE	REMOVE/MODIFY LIGHT POLE					
408+58	16' RT	EX 4TH AVENUE	CITY OF MOLINE	REMOVE/RELOCATE LIGHT POLE					
5001+15	18' LT	EX 5TH AVENUE	CITY OF MOLINE						
5003+35	23' LT	EX 5TH AVENUE	CITY OF MOLINE						
5003+89	24' RT	EX 5TH AVENUE	CITY OF MOLINE						
5005+09	23' LT	EX 5TH AVENUE	CITY OF MOLINE						
5006+07	23' RT	EX 5TH AVENUE	CITY OF MOLINE						
106+45	35′ RT	EX 7TH AVENUE	IDOT						
109+04	55′ RT	EX 7TH AVENUE	IDOT						
109+47	76′ RT	EX 7TH AVENUE	IDOT						
112+25	62' RT	EX 7TH AVENUE	IDOT						
115+70	34' RT	EX 7TH AVENUE	IDOT						
118+68	169' RT	EX 7TH AVENUE	IDOT						
206+09	29' LT	EX 7TH AVENUE	IDOT						
208+73	50' LT	EX 7TH AVENUE	IDOT						
209+96	107' LT	EX 7TH AVENUE	IDOT						
210+67	49' LT	EX 7TH AVENUE	IDOT						
212+43	41' LT	EX 7TH AVENUE	IDOT						
212+84	102' LT	EX 7TH AVENUE	IDOT						
214+90	149' LT	EX 7TH AVENUE	IDOT						
215+14	46' LT	EX 7TH AVENUE	IDOT						
217+37	38' LT	EX 7TH AVENUE	IDOT						
3012+20	45' LT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE					
3013+40	45' LT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE					
3013+40	59' RT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE					
3014+40	45' LT	EX RIVER ROAD	IDOT						
3014+40	62' RT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE					
3016+55	50' RT	EX RIVER ROAD	IDOT	REMOVE ONE COMBO LIGHT/ARM					
365+80	165' LT	EX I-74	CITY OF MOLINE	FLAG POLE FLOOD LIGHT					
366+70	95' LT	EX I-74	CITY OF MOLINE	FLAG POLE FLOOD LIGHT					
=	-	JOHN DEERE PARKING LOT	JOHN DEERE	REMOVE SEVEN (7) LIGHT POLES					

LIGHTING INSTALLATION DATA										
	LC	CATION				TYPE				
NO.	STATION	OFFSET	ALIGNMENT	POLE	M.A.	POLE DETAIL*	LUMINAIRE(S) **	REMARKS		
1-G-03/1-G-04	30+60.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-H-03/1-H-04	33+44.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-G-05/1-G-06	36+22.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-H-05/1-H-06	38+97.0	PARAPET WALL	I-74 ML	45′	14′	TYPE I	TYPE A	SEE NOTE 1		
1-G-07/1-G-08	41+66.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-E-08	129+15.0	BARRIER WALL	RAMP RD-G	29′	4′	TYPE IV	TYPE A	SEE NOTE 1		
1-F-08	132+15.0	RETAINING WALL	RAMP RD-G	29′	4′	TYPE IV	TYPE A	SEE NOTE 1		
1-E-09	135+15.0	50.94' RT	RAMP RD-G	29′	4'	TYPE IV	TYPE A			
1-C-19	215+30.0	RETAINING WALL	RAMP RD-H	45′	14′	TYPE II	TYPE A	SEE NOTE 1		
1-D-17	211+54.0	38.0′ RT	RAMP RD-H	50′	14′	TYPE III	TYPE A			
1-C-01	439+55.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-D-01	436+45.0	BARRIER WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-C-02	433+30.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-D-02	430+05.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-C-03	426+81.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-D-03	423+65.0	RETAINING WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-G-01/1-G-02	25+32.00	I-74 CL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-H-01/1-H-02	28+10.00	I-74 CL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-E-01	24+25.00	BARRIER WALL	I-74 ML	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-F-01/1-F-09	320+65.00	RETAINING WALL	RAMP 6TH-C	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-E-02/1-E-10	323+97.50	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-F-02	327+25.00	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-E-03	331+08.00	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE II	TYPE A	SEE NOTE 1		
1-F-03	334+22.00	16.00' RT	RAMP 6TH-C	50′	14'	TYPE III	TYPE A	SEE NOTE 1		
13-B-01	403+09.30	27.71' RT	4TH AVE	-	-		-	RELOCATED POLE		
1-H-07/1-H-08	44+48.0	BARRIER WALL	I-74	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-G-09/1-G-10	47+16.0	BARRIER WALL	I-74	45′	14'	TYPE I	TYPE A	SEE NOTE 1		
1-C-04	6007+04.5	40.2' LT	6TH AVE	45′	15'	-	TYPE A	COMBINATION POLE		
1-D-04	6007+12.2	48.0′ RT	6TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION FOLL		
1-C-05	6006+11.7	30.4' RT	6TH AVE	45′	15'	-	TYPE A	COMBINATION POLE		
1-D-16	7007+32.0	95.0' RT	7TH AVE	45′	15'	-	TYPE A	COMBINATION POLE		
1-D-13	7008+64.0	82.0′ LT	7TH AVE	45′	15'	_	TYPE A	COMBINATION FOLE		
1-C-13	7010+50.0	70.6′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION TOLL		
1-C-13	7010+30.0	74.0′ LT	7TH AVE	45′	15'	-	TYPE A	COMBINATION POLE		
1-D-12	7010+50.0	76.6′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION TOLL		
1-D-15	7010+30.0	66.6′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	+		
1-D-13	7013+47.2	76.5′ RT	7TH AVE	45′	15'	-	TYPE A	COMBINATION POLE		
1-C-07	7013+47.2	65.4' LT	7TH AVE	50'	14'	TYPE III	TYPE A	COMBINATION OLL		
1-C-06	644+49.0		7TH AVE	50'	14'	TYPE III	TYPE A	+		
1-C-06 1-C-09		30.6′ LT	7TH-RAMP A	50'	14'	TYPE III	TYPE A			
1-C-09 1-D-05	642+15.0	25.2′ RT	7TH-RAMP A	50'	14'	TYPE III	TYPE A			
1-D-05 1-D-06	645+83.0	41.6′ LT	7TH AVE	45′	15'	TIPE III	TYPE A	COMBINATION POLE		
1-D-06 1-D-07	7013+75.0	54.3′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION FULE		
1-D-07 1-C-08	7016+50.0	39.6′ LT		50'	14'		TYPE A			
	7014+29.0	56.5′ RT	7TH AVE			TYPE III				
1-C-14	7008+91.9	76.6′ LT	7TH AVE	50′	14'	TYPE III	TYPE A			
1-C-15	7006+31.0	88.0′ LT	7TH AVE	50′	14'	TYPE III	TYPE A			
1-C-16	7008+55.0	98.0′ RT	7TH AVE	50′	14'	TYPE III	TYPE A			
1-C-17	7006+93.0	71.0′ RT	7TH AVE	50′	14'	TYPE III	TYPE A			
1-C-18	7005+00.0	48.6′ LT	7TH AVE	50′	14'	TYPE III	TYPE A			

- SEE LIGHTING DETAIL SHEETS FOR POLE DETAILS
- •• TYPE A SHALL BE A LED, MEDIUM WATTAGE, 240 VOLT LUMINAIRE

NOTE 1: LIGHT POLE MOUNTED TO BARRIER WALL, BRIDGE PARAPET, OR RETAINING WALL


Alfred Benesch & Company
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450
Job No. 10064


DRAWN REVENUE THE PROPERTY OF THE PROPERTY OF

USER NAME =	DESIGNED	-	GHT	REVISED -
	DRAWN	-	JLW	REVISED -
PLOT SCALE = NO SCALE	CHECKED	-	GRR	REVISED -
PLOT DATE = 1/30/2017	DATE	-	2/5/2016	REVISED -

STATE	OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

					F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
LIGHTING QUANTITIES						(81-1)R & 81-1HVBR	ROCK ISLAND	1504	498
							CONTRACT	NO. 6	4C08
SCALE: NO SCALE	SHEET NO. 2 OF 29	SHEETS	STA.	TO STA.		ILLINOIS FED. A	D PROJECT		





ROADWAY LIGHTING GENERAL NOTES

- 1. ELECTRICAL EQUIPMENT, RACEWAY, ETC. ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. CONTRACTOR SHALL INSTALL ELECTRICAL EQUIPMENT, RACEWAYS, ETC. WHERE DIRECTED BY THE ENGINEER IN ORDER TO BEST SUIT JOB CONDITIONS.
- 2. ALL REPLACEMENT AND TEMPORARY WIRING SHALL BE EQUAL TO OR GREATER THAN THE EXISTING WIRE GAUGE.
- 3. NO SPLICING OF EXISTING-TO-NEW WIRING IS ALLOWED INSIDE ELECTRICAL DUCTS. ALL WIRING INTERCONNECTIONS SHALL BE INSTALLED IN ACCESSIBLE AREAS AND SHALL BE MADE WITH ILLINOIS DOT APPROVED CONNECTORS.
- 4. ALL LIQUID-TIGHT FLEXIBLE CONDUIT SHALL BE INCIDENTAL TO THE CONDUIT ATTACHED TO STRUCTURE OF THE SIZE SPECIFIED.
- 5. NO POLES TO BE INSTALLED IN THE FLOWLINE OF THE DITCH. POLE SETBACK SHALL BE ADJUSTED IF NECESSARY AS DIRECTED BY THE ENGINEER.
- 6. ELECTRIC SERVICE INSTALLATION SHALL INCLUDE ALL CONDUIT AND CABLE REQUIRED BETWEEN THE UTILITY SERVICE AND THE LIGHTING CONTROLLER.
- 7. ALL CONDUIT UNDER ROADWAYS SHALL BE PVC SCHEDULE 80.
- 8. THE GROUND CONDUCTOR SHALL HAVE NO SPLICE OR KINCKS BELOW GRADE. IT SHALL BE SOLIDLY CONNECTED TO THE GROUNDING LUG OF EACH POLE, JUNCTION BOX, AND TO THE GROUND ROD AT THE SERVICE INSTALLATION.

IN AREAS WHERE MULTIPLE CIRCUIT CONDUCTORS SHARE A COMMON CONDUIT, A COMMON EQUIPMENT GROUND SHALL BE UTILIZED.

- 9. THE CONTRACTOR SHALL PROVIDE A 1/4" POLY PULL-LINE THROUGH EACH PVC CONDUIT IN WHICH NO CONDUCTORS ARE PLACED IN THIS CONTRACT. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE PRICE FOR THE CONDUIT SPECIFIED.
- 10. JUNCTION BOXES OF "SLIGHTLY" LARGER SIZE THAN THOSE SPECIFIED ON THE PLANS MAY BE USED WHEN APPROVED BY ENGINEER AT NO ADDITIONAL COST TO THE CONTRACT.
- 11. EXISTING AND/OR TEMPORARY LIGHTING UNITS SHALL NOT BE REMOVED UNTIL NEW LIGHTING SYSTEM IS COMPLETELY INSTALLED AND FULLY OPERATIONAL TO THE SATISFACTION OF THE
- 12. CONTRACTOR SHALL PROVIDE STAINLESS STEEL SCREEN UNDERNEATH THE ALUMINUM SKIRT OF THE BREAKAWAY COUPLINGS. THE COST OF THE SCREEN SHALL BE INCLUDED IN THE COST OF THE COUPLINGS. SKIRT SHALL BE PAINTED BLACK TO MATCH LIGHT POLES.
- 13. REMOVAL AND DISPOSAL OF ALL LIGHT POLES AND UNDERPASS LUMINAIRES ATTACHED TO BRIDGE STRUCTURES SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED "REMOVAL OF EXISTING STRUCTURES" PAY ITEM. PLEASE SEE STRUCTURAL REMOVAL PLANS DEMOLITION PLAN FOR ADDITIONAL INFORMATION.
- 14. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING STATE OWNED LIGHTING AND/OR TRAFFIC SIGNAL UTILITIES WITHIN THE LIMITS OF THE CONTRACT.
- 15. EXPANSION/DEFLECTION COUPLINGS SHALL BE INSTALLED IN ALL LOCATIONS BETWEEN STRUCTURES, AT EXPANSION JOINTS, AND WHERE NECESSARY TO CONTROL MOVEMENT THAT WOULD DAMAGE THE CONDUIT. THE COST OF EXPANSION/DEFLECTION COUPLINGS SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED CONDUIT AS CALLED OUT ON THE PLANS.

ESTIMATED PROJECT QUANTITIES

PAY ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	86
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	4,997
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	1,404
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	2,292
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	3,845
81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA. PVC	FOOT	2,646
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA. PVC	FOOT	8,191
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	90
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	50
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x12"x6"	EACH	6
81301290	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12"x12"x6"	EACH	4
81400100	HANDHOLE	EACH	10
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,497
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	74,255
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	22,605
82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP	EACH	1
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	10
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	126
83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	60
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	38
84200804	REMOVAL OF POLE FOUNDATION	EACH	36
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	4
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	4
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	3
87900200	DRILL EXISTING HANDHOLE	EACH	1
X0326357	ROADWAY LIGHTING MODIFICATIONS	L SUM	1
X0327006	ROADWAY LIGHT POLE, INSTALL ONLY	EACH	41
X1400128	REMOVE AND REPLACE EXISTING CIRCUIT BREAKER WITH 40 AMP, 2-POLE	EACH	2
X8110454	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., STAINLESS STEEL	FOOT	10
X8110458	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., STAINLESS STEEL	FOOT	80
X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	1
X8360310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	9
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1
#2000324	ROADWAY LUMINAIRE, SPECIAL (INSTALL ONLY)	EACH	59
#2000325	AESTHETIC LUMINAIRE, (INSTALL ONLY)	EACH	71
#2000326	UNDERPASS LUMINAIRE, (INSTALL ONLY)	EACH	25

LIGHTING LEGEND

PROPOSED ELECTRIC SERVICE INSTALLATION

PROPOSED LIGHTING CONTROLLER, 240V, 100A (UNLESS OTHERWISE NOTED)

PROPOSED HANDHOLE

PROPOSED LED STREET LIGHT, 50 FT MOUNTING HEIGHT, 14 FT MAST ARM (UNLESS OTHERWISE NOTED)

PROPOSED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, TWIN 14 FT MAST ARMS (UNLESS OTHERWISE NOTED)

PROPOSED BRIDGE MOUNTED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, 14 FT MAST ARM (UNLESS OTHERWISE STATED)

PROPOSED BRIDGE MOUNTED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, TWIN 14 FT MAST ARMS, (UNLESS OTHERWISE NOTED)

PROPOSED TRAFFIC SIGNAL / STREET LIGHT COMBINATION

PROPOSED UNDERPASS LUMINAIRE, LED. VERY LOW WATTAGE

PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AS NOTED

PROPOSED CONDUIT EMBEDDED IN STRUCTURE, SIZE AS NOTED

EXISTING LIGHTING CONTROLLER TO REMAIN \bowtie EXISTING LIGHTING UNIT TO REMAIN

EXISTING LIGHT TO BE MODIFIED

EXISTING LIGHT TO BE REMOVED

EXISTING LIGHT TO BE RELOCATED

EXISTING LIGHTING CONTROLLER TO BE REMOVED \boxtimes .

-□; EXISTING ELECTRIC SERVICE INSTALLATION TO BE REMOVED

TEMPORARY LIGHTING UNIT, AS NOTED ON PLANS

3"-72'-T) CONDUIT CALLOUT INSTALLATION METHOD (UNDERGROUND UNLESS OTHERWISE SPECIFIED, EMBEDDED IN STRUCTURE OR ATTACHED TO STRUCTURE)

- CONDUIT LENGTH

- CONDUIT DIAMETER

1-A-01 LIGHT POLE DESIGNATION

- POLE NUMBER

CIRCUIT

- CONTROL CABINET

2	benesch
	engineers · scientists · planners

Alfred Benesch & Company 205 North Michigan Avenue, Suite 2400 Chicago, Illinois 60601 Job No. 10064

USER NAME =	DESIGNED	-	GHT	REVISED	-
	DRAWN	-	JLW	REVISED	-
PLOT SCALE = NO SCALE	CHECKED	-	GRR	REVISED	-
PLOT DATE = 1/30/2017	DATE	-	2/5/2016	REVISED	-

FILE NAME =

D2CONAB-AB-sht-light400.dgr

	LIGHTING REMOVAL DATA						
	LOCAT	ION					
STATION	OFFSET	ALIGNMENT	OWNER	REMARKS			
162+98	20' RT	EX I-74	IDOT				
166+24	12' RT	EX I-74	IDOT				
169+93	10' RT	EX I-74	IDOT				
172+12	48' LT	EX I-74	IDOT				
173+76	22' RT	EX I-74	IDOT				
368+31	18' LT	EX I-74	IDOT				
370+27	26' LT	EX I-74	IDOT				
403+35	25' RT	EX 4TH AVENUE	CITY OF MOLINE	RELOCATE LIGHT POLE			
407+46	15' RT	EX 4TH AVENUE	CITY OF MOLINE	REMOVE/MODIFY LIGHT POLE			
408+58	16' RT	EX 4TH AVENUE	CITY OF MOLINE	REMOVE/RELOCATE LIGHT POLE			
5001+15	18' LT	EX 5TH AVENUE	CITY OF MOLINE				
5003+35	23' LT	EX 5TH AVENUE	CITY OF MOLINE				
5003+89	24' RT	EX 5TH AVENUE	CITY OF MOLINE				
5005+09	23' LT	EX 5TH AVENUE	CITY OF MOLINE				
5006+07	23' RT	EX 5TH AVENUE	CITY OF MOLINE				
106+45	35′ RT	EX 7TH AVENUE	IDOT				
109+04	55′ RT	EX 7TH AVENUE	IDOT				
109+47	76′ RT	EX 7TH AVENUE	IDOT				
112+25	62' RT	EX 7TH AVENUE	IDOT				
115+70	34' RT	EX 7TH AVENUE	IDOT				
118+68	169' RT	EX 7TH AVENUE	IDOT				
206+09	29' LT	EX 7TH AVENUE	IDOT				
208+73	50' LT	EX 7TH AVENUE	IDOT				
209+96	107' LT	EX 7TH AVENUE	IDOT				
210+67	49' LT	EX 7TH AVENUE	IDOT				
212+43	41' LT	EX 7TH AVENUE	IDOT				
212+84	102' LT	EX 7TH AVENUE	IDOT				
214+90	149' LT	EX 7TH AVENUE	IDOT				
215+14	46' LT	EX 7TH AVENUE	IDOT				
217+37	38' LT	EX 7TH AVENUE	IDOT				
3012+20	45' LT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE			
3013+40	45' LT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE			
3013+40	59' RT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE			
3014+40	45' LT	EX RIVER ROAD	IDOT				
3014+40	62' RT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE			
3016+55	50' RT	EX RIVER ROAD	IDOT	REMOVE ONE COMBO LIGHT/ARM			
365+80	165' LT	EX I-74	CITY OF MOLINE	FLAG POLE FLOOD LIGHT			
366+70	95' LT	EX I-74	CITY OF MOLINE	FLAG POLE FLOOD LIGHT			
=	-	JOHN DEERE PARKING LOT	JOHN DEERE	REMOVE SEVEN (7) LIGHT POLES			

LIGHTING INSTALLATION DATA								
	LC	CATION				TYPE		
NO.	STATION	OFFSET	ALIGNMENT	POLE	M.A.	POLE DETAIL*	LUMINAIRE(S) **	REMARKS
1-G-03/1-G-04	30+60.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-H-03/1-H-04	33+44.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-G-05/1-G-06	36+22.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-H-05/1-H-06	38+97.0	PARAPET WALL	I-74 ML	45′	14′	TYPE I	TYPE A	SEE NOTE 1
1-G-07/1-G-08	41+66.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-E-08	129+15.0	BARRIER WALL	RAMP RD-G	29′	4′	TYPE IV	TYPE A	SEE NOTE 1
1-F-08	132+15.0	RETAINING WALL	RAMP RD-G	29′	4′	TYPE IV	TYPE A	SEE NOTE 1
1-E-09	135+15.0	50.94' RT	RAMP RD-G	29′	4'	TYPE IV	TYPE A	
1-C-19	215+30.0	RETAINING WALL	RAMP RD-H	45′	14′	TYPE II	TYPE A	SEE NOTE 1
1-D-17	211+54.0	38.0′ RT	RAMP RD-H	50′	14′	TYPE III	TYPE A	
1-C-01	439+55.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-D-01	436+45.0	BARRIER WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-C-02	433+30.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-D-02	430+05.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-C-03	426+81.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-D-03	423+65.0	RETAINING WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-G-01/1-G-02	25+32.00	I-74 CL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-H-01/1-H-02	28+10.00	I-74 CL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-E-01	24+25.00	BARRIER WALL	I-74 ML	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-F-01/1-F-09	320+65.00	RETAINING WALL	RAMP 6TH-C	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-E-02/1-E-10	323+97.50	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-F-02	327+25.00	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-E-03	331+08.00	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-F-03	334+22.00	16.00' RT	RAMP 6TH-C	50′	14'	TYPE III	TYPE A	SEE NOTE 1
13-B-01	403+09.30	27.71' RT	4TH AVE	-	-		-	RELOCATED POLE
1-H-07/1-H-08	44+48.0	BARRIER WALL	I-74	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-G-09/1-G-10	47+16.0	BARRIER WALL	I-74	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-C-04	6007+04.5	40.2' LT	6TH AVE	45′	15'	-	TYPE A	COMBINATION POLE
1-D-04	6007+12.2	48.0′ RT	6TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION FOLL
1-C-05	6006+11.7	30.4' RT	6TH AVE	45′	15'	-	TYPE A	COMBINATION POLE
1-D-16	7007+32.0	95.0' RT	7TH AVE	45′	15'	-	TYPE A	COMBINATION POLE
1-D-13	7008+64.0	82.0′ LT	7TH AVE	45′	15'	_	TYPE A	COMBINATION FOLE
1-C-13	7010+50.0	70.6′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION TOLL
1-C-13	7010+30.0	74.0′ LT	7TH AVE	45′	15'	-	TYPE A	COMBINATION POLE
1-D-12	7010+50.0	76.6′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION TOLL
1-D-15	7010+30.0	66.6′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	+
1-D-13	7013+47.2	76.5′ RT	7TH AVE	45′	15'	-	TYPE A	COMBINATION POLE
1-C-07	7013+47.2	65.4' LT	7TH AVE	50'	14'	TYPE III	TYPE A	COMBINATION OLL
1-C-06	644+49.0		7TH AVE	50'	14'	TYPE III	TYPE A	+
1-C-06 1-C-09		30.6′ LT	7TH-RAMP A	50'	14'	TYPE III	TYPE A	
1-C-09 1-D-05	642+15.0	25.2′ RT	7TH-RAMP A	50'	14'	TYPE III	TYPE A	
1-D-05 1-D-06	645+83.0	41.6′ LT	7TH AVE	45′	15'	TIPE III	TYPE A	COMBINATION POLE
1-D-06 1-D-07	7013+75.0	54.3′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	COMBINATION FULE
1-D-07 1-C-08	7016+50.0	39.6′ LT		50'	14'		TYPE A	
	7014+29.0	56.5′ RT	7TH AVE			TYPE III		
1-C-14	7008+91.9	76.6′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	
1-C-15	7006+31.0	88.0′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	
1-C-16	7008+55.0	98.0′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	
1-C-17	7006+93.0	71.0′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	
1-C-18	7005+00.0	48.6′ LT	7TH AVE	50′	14'	TYPE III	TYPE A	

- SEE LIGHTING DETAIL SHEETS FOR POLE DETAILS
- •• TYPE A SHALL BE A LED, MEDIUM WATTAGE, 240 VOLT LUMINAIRE

NOTE 1: LIGHT POLE MOUNTED TO BARRIER WALL, BRIDGE PARAPET, OR RETAINING WALL


Alfred Benesch & Company
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450
Job No. 10064


DRAWN REVENUE THE PROPERTY OF THE PROPERTY OF


USER NAME =	DESIGNED	-	GHT	REVISED -
	DRAWN	-	JLW	REVISED -
PLOT SCALE = NO SCALE	CHECKED	-	GRR	REVISED -
PLOT DATE = 1/30/2017	DATE	-	2/5/2016	REVISED -

STATE	OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

					F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
LIGHTING QUANTITIES						(81-1)R & 81-1HVBR	ROCK ISLAND	1504	498
							CONTRACT	NO. 6	4C08
SCALE: NO SCALE	SHEET NO. 2 OF 29	SHEETS	STA.	TO STA.		ILLINOIS FED. A	D PROJECT		







ROADWAY LIGHTING GENERAL NOTES

- 1. ELECTRICAL EQUIPMENT, RACEWAY, ETC. ARE SHOWN IN APPROXIMATE LOCATIONS ONLY. CONTRACTOR SHALL INSTALL ELECTRICAL EQUIPMENT, RACEWAYS, ETC. WHERE DIRECTED BY THE ENGINEER IN ORDER TO BEST SUIT JOB CONDITIONS.
- ALL REPLACEMENT AND TEMPORARY WIRING SHALL BE EQUAL TO OR GREATER THAN THE EXISTING WIRE GAUGE.
- 3. NO SPLICING OF EXISTING-TO-NEW WIRING IS ALLOWED INSIDE ELECTRICAL DUCTS. ALL WIRING INTERCONNECTIONS SHALL BE INSTALLED IN ACCESSIBLE AREAS AND SHALL BE MADE WITH ILLINOIS DOT APPROVED CONNECTORS.
- 4. ALL LIQUID-TIGHT FLEXIBLE CONDUIT SHALL BE INCIDENTAL TO THE CONDUIT ATTACHED TO STRUCTURE OF THE SIZE SPECIFIED.
- 5. NO POLES TO BE INSTALLED IN THE FLOWLINE OF THE DITCH. POLE SETBACK SHALL BE ADJUSTED IF NECESSARY AS DIRECTED BY THE ENGINEER.
- 6. ELECTRIC SERVICE INSTALLATION SHALL INCLUDE ALL CONDUIT AND CABLE REQUIRED BETWEEN THE UTILITY SERVICE AND THE LIGHTING CONTROLLER.
- 7. ALL CONDUIT UNDER ROADWAYS SHALL BE PVC SCHEDULE 80.
- 8. THE GROUND CONDUCTOR SHALL HAVE NO SPLICE OR KINCKS BELOW GRADE. IT SHALL BE SOLIDLY CONNECTED TO THE GROUNDING LUG OF EACH POLE, JUNCTION BOX, AND TO THE GROUND ROD AT THE SERVICE INSTALLATION.

IN AREAS WHERE MULTIPLE CIRCUIT CONDUCTORS SHARE A COMMON CONDUIT, A COMMON EQUIPMENT GROUND SHALL BE UTILIZED.

- 9. THE CONTRACTOR SHALL PROVIDE A 1/4" POLY PULL-LINE THROUGH EACH PVC CONDUIT IN WHICH NO CONDUCTORS ARE PLACED IN THIS CONTRACT. THIS WORK SHALL BE CONSIDERED INCLUDED IN THE PRICE FOR THE CONDUIT SPECIFIED.
- 10. JUNCTION BOXES OF "SLIGHTLY" LARGER SIZE THAN THOSE SPECIFIED ON THE PLANS MAY BE USED WHEN APPROVED BY ENGINEER AT NO ADDITIONAL COST TO THE CONTRACT.
- 11. EXISTING AND/OR TEMPORARY LIGHTING UNITS SHALL NOT BE REMOVED UNTIL NEW LIGHTING SYSTEM IS COMPLETELY INSTALLED AND FULLY OPERATIONAL TO THE SATISFACTION OF THE ENGINEER.
- 12. CONTRACTOR SHALL PROVIDE STAINLESS STEEL SCREEN UNDERNEATH THE ALUMINUM SKIRT OF THE BREAKAWAY COUPLINGS. THE COST OF THE SCREEN SHALL BE INCLUDED IN THE COST OF THE COUPLINGS. SKIRT SHALL BE PAINTED BLACK TO MATCH LIGHT POLES.
- 13. REMOVAL AND DISPOSAL OF ALL LIGHT POLES AND UNDERPASS LUMINAIRES ATTACHED TO BRIDGE STRUCTURES SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED "REMOVAL OF EXISTING STRUCTURES" PAY ITEM. PLEASE SEE STRUCTURAL REMOVAL PLANS DEMOLITION PLAN FOR ADDITIONAL INFORMATION.
- 14. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL EXISTING STATE OWNED LIGHTING AND/OR TRAFFIC SIGNAL UTILITIES WITHIN THE LIMITS OF THE CONTRACT.
- 15. EXPANSION/DEFLECTION COUPLINGS SHALL BE INSTALLED IN ALL LOCATIONS BETWEEN STRUCTURES, AT EXPANSION JOINTS, AND WHERE NECESSARY TO CONTROL MOVEMENT THAT WOULD DAMAGE THE CONDUIT. THE COST OF EXPANSION/DEFLECTION COUPLINGS SHALL BE INCLUDED IN THE COST OF THE ASSOCIATED CONDUIT AS CALLED OUT ON THE PLANS.

ESTIMATED PROJECT QUANTITIES

PAY ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITY
80400100	ELECTRIC SERVICE INSTALLATION	EACH	1
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	86
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	4,997
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	1,404
81100300	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., GALVANIZED STEEL	FOOT	2,292
81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., GALVANIZED STEEL	FOOT	3,845
81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA. PVC	FOOT	2,646
81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA. PVC	FOOT	8,191
81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 6"x6"x4"	EACH	90
81300530	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x10"x6"	EACH	50
81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 12"x12"x6"	EACH	6
81301290	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 12"x12"x6"	EACH	4
81400100	HANDHOLE	EACH	10
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	6,497
81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	74,255
81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	22,605
82500335	LIGHTING CONTROLLER, PEDESTAL MOUNTED, 240VOLT, 100AMP	EACH	1
83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	10
83600300	LIGHT POLE FOUNDATION, 30" DIAMETER	FOOT	126
83800505	BREAKAWAY DEVICE, COUPLING WITH ALUMINUM SKIRT	EACH	60
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	38
84200804	REMOVAL OF POLE FOUNDATION	EACH	36
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	6
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	4
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	4
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	3
87900200	DRILL EXISTING HANDHOLE	EACH	1
X0326357	ROADWAY LIGHTING MODIFICATIONS	L SUM	1
X0327006	ROADWAY LIGHT POLE, INSTALL ONLY	EACH	41
X1400128	REMOVE AND REPLACE EXISTING CIRCUIT BREAKER WITH 40 AMP, 2-POLE	EACH	2
X8110454	CONDUIT ATTACHED TO STRUCTURE, 1" DIA., STAINLESS STEEL	FOOT	10
X8110458	CONDUIT ATTACHED TO STRUCTURE, 2" DIA., STAINLESS STEEL	FOOT	80
X8360120	LIGHT POLE FOUNDATION, SPECIAL	EACH	1
X8360310	LIGHT POLE FOUNDATION, 30" DIAMETER, SPECIAL	FOOT	9
X8410102	TEMPORARY LIGHTING SYSTEM	L SUM	1
#2000324	ROADWAY LUMINAIRE, SPECIAL (INSTALL ONLY)	EACH	59
#2000325	AESTHETIC LUMINAIRE, (INSTALL ONLY)	EACH	71
#2000326	UNDERPASS LUMINAIRE, (INSTALL ONLY)	EACH	25

LIGHTING LEGEND

---- PROPOSED ELECTRIC SERVICE INSTALLATION

PROPOSED LIGHTING CONTROLLER, 240V, 100A (UNLESS OTHERWISE NOTED)

PROPOSED HANDHOLE

PROPOSED LED STREET LIGHT, 50 FT MOUNTING HEIGHT, 14 FT MAST ARM (UNLESS OTHERWISE NOTED)

PROPOSED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, TWIN 14 FT MAST ARMS (UNLESS OTHERWISE NOTED)

PROPOSED BRIDGE MOUNTED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, 14 FT MAST ARM (UNLESS OTHERWISE STATED)

PROPOSED BRIDGE MOUNTED LED STREET LIGHT, 48.5 FT MOUNTING HEIGHT, TWIN 14 FT MAST ARMS, (UNLESS OTHERWISE NOTED)

PROPOSED TRAFFIC SIGNAL / STREET LIGHT COMBINATION

PROPOSED UNDERPASS LUMINAIRE, LED, VERY LOW WATTAGE

PROPOSED UNDERGROUND CONDUIT, TYPE AND SIZE AS NOTED

PROPOSED CONDUIT ATTACHED TO STRUCTURE, SIZE AS NOTED

--- PROPOSED CONDUIT EMBEDDED IN STRUCTURE, SIZE AS NOTED

EXISTING LIGHTING CONTROLLER TO REMAIN

EXISTING LIGHTING UNIT TO REMAIN

EXISTING LIGHT TO BE MODIFIED

EXISTING LIGHT TO BE REMOVED

EXISTING LIGHT TO BE RELOCATED

EXISTING LIGHTING CONTROLLER TO BE REMOVED

EXISTING ELECTRIC SERVICE INSTALLATION TO BE REMOVED

TEMPORARY LIGHTING UNIT, AS NOTED ON PLANS

3"-72'-T) CONDUIT CALLOUT

INSTALLATION METHOD (UNDERGROUND UNLESS OTHERWISE - SPECIFIED, EMBEDDED IN STRUCTURE OR ATTACHED TO STRUCTURE)

- CONDUIT LENGTH

- CONDUIT DIAMETER

1-A-01 LIGHT POLE DESIGNATION

- POLE NUMBER

— CIRCUIT

CONTROL CABINET

2	benesch
	engineers · scientists · planners

FILE NAME =

D2CONAB-AB-sht-light400.dgr

Alfred Benesch & Company 205 North Michigan Avenue, Suite 2400 Chicago, Illinois 60601 312-565-0450 Job No. 10064

USER N	IAME =	DESIGNED	-	GHT	REVISED	-
		DRAWN	-	JLW	REVISED	-
PLOT S	CALE = NO SCALE	CHECKED	-	GRR	REVISED	-
PLOT D	ATE = 1/30/2017	DATE	-	2/5/2016	REVISED	-

	LIGHTING REMOVAL DATA										
	LOCATION										
STATION	OFFSET	ALIGNMENT	OWNER	REMARKS							
162+98	20' RT	EX I-74	IDOT								
166+24	12' RT	EX I-74	IDOT								
169+93	10' RT	EX I-74	IDOT								
172+12	48' LT	EX I-74	IDOT								
173+76	22' RT	EX I-74	IDOT								
368+31	18' LT	EX I-74	IDOT								
370+27	26' LT	EX I-74	IDOT								
403+35	25′ RT	EX 4TH AVENUE	CITY OF MOLINE	RELOCATE LIGHT POLE							
407+46	15' RT	EX 4TH AVENUE	CITY OF MOLINE	REMOVE/MODIFY LIGHT POLE							
408+58	16' RT	EX 4TH AVENUE	CITY OF MOLINE	REMOVE/RELOCATE LIGHT POLE							
5001+15	18' LT	EX 5TH AVENUE	CITY OF MOLINE								
5003+35	23' LT	EX 5TH AVENUE	CITY OF MOLINE								
5003+89	24' RT	EX 5TH AVENUE	CITY OF MOLINE								
5005+09	23' LT	EX 5TH AVENUE	CITY OF MOLINE								
5006+07	23' RT	EX 5TH AVENUE	CITY OF MOLINE								
106+45	35' RT	EX 7TH AVENUE	IDOT								
109+04	55' RT	EX 7TH AVENUE	IDOT								
109+47	76′ RT	EX 7TH AVENUE	IDOT								
112+25	62' RT	EX 7TH AVENUE	IDOT								
115+70	34' RT	EX 7TH AVENUE	IDOT								
118+68	169' RT	EX 7TH AVENUE	IDOT								
206+09	29' LT	EX 7TH AVENUE	IDOT								
208+73	50' LT	EX 7TH AVENUE	IDOT								
209+96	107' LT	EX 7TH AVENUE	IDOT								
210+67	49' LT	EX 7TH AVENUE	IDOT								
212+43	41' LT	EX 7TH AVENUE	IDOT								
212+84	102' LT	EX 7TH AVENUE	IDOT								
214+90	149' LT	EX 7TH AVENUE	IDOT								
215+14	46' LT	EX 7TH AVENUE	IDOT								
217+37	38' LT	EX 7TH AVENUE	IDOT								
3012+20	45' LT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE							
3013+40	45' LT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE							
3013+40	59' RT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE							
3014+40	45' LT	EX RIVER ROAD	IDOT								
3014+40	62' RT	EX RIVER ROAD	IDOT	RELOCATE LIGHT POLE							
3016+55	50' RT	EX RIVER ROAD	IDOT	REMOVE ONE COMBO LIGHT/ARM							
365+80	165' LT	EX I-74	CITY OF MOLINE	FLAG POLE FLOOD LIGHT							
366+70	95' LT	EX I-74	CITY OF MOLINE	FLAG POLE FLOOD LIGHT							
-	-	JOHN DEERE PARKING LOT	JOHN DEERE	REMOVE SEVEN (7) LIGHT POLES							

				LIGHTING	INSTALL	ATION DAT	ΓΑ	
	LC	CATION				TYPE		
NO.	STATION	OFFSET	ALIGNMENT	POLE	M.A.	POLE DETAIL*	LUMINAIRE(S) **	REMARKS
1-G-03/1-G-04	30+60.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-H-03/1-H-04	33+44.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-G-05/1-G-06	36+22.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-H-05/1-H-06	38+97.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-G-07/1-G-08	41+66.0	PARAPET WALL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-E-08	129+15.0	BARRIER WALL	RAMP RD-G	29′	4'	TYPE IV	TYPE A	SEE NOTE 1
1-F-08	132+15.0	RETAINING WALL	RAMP RD-G	29′	4′	TYPE IV	TYPE A	SEE NOTE 1
1-E-09	135+15.0	50.94' RT	RAMP RD-G	29′	4′	TYPE IV	TYPE A	
1-C-19	215+30.0	RETAINING WALL	RAMP RD-H	45′	14′	TYPE II	TYPE A	SEE NOTE 1
1-D-17	211+54.0	38.0′ RT	RAMP RD-H	50′	14'	TYPE III	TYPE A	
1-C-01	439+55.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-D-01	436+45.0	BARRIER WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-C-02	433+30.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-D-02	430+05.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-C-03	426+81.0	PARAPET WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-D-03	423+65.0	RETAINING WALL	RAMP 6TH-D	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-G-01/1-G-02	25+32.00	I-74 CL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-H-01/1-H-02	28+10.00	I-74 CL	I-74 ML	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-E-01	24+25.00	BARRIER WALL	I-74 ML	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-F-01/1-F-09	320+65.00	RETAINING WALL	RAMP 6TH-C	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-E-02/1-E-10	323+97.50	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-F-02	327+25.00	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-E-03	331+08.00	PARAPET WALL	RAMP 6TH-C	45′	14'	TYPE II	TYPE A	SEE NOTE 1
1-F-03	334+22.00	16.00' RT	RAMP 6TH-C	50′	14'	TYPE III	TYPE A	
13-B-01	403+09.30	27.71' RT	4TH AVE	-	-	-	-	RELOCATED POLE
1-H-07/1-H-08	44+48.0	BARRIER WALL	I-74	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-G-09/1-G-10	47+16.0	BARRIER WALL	I-74	45′	14'	TYPE I	TYPE A	SEE NOTE 1
1-C-04	6007+04.5	40.2′ LT	6TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-D-04	6007+12.2	48.0' RT	6TH AVE	50′	14'	TYPE III	TYPE A	
1-C-05	6006+11.7	30.4' RT	6TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-D-16	7007+32.0	95.0' RT	7TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-D-13	7008+64.0	82.0′ LT	7TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-C-13	7010+50.0	70 . 6′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	
1-D-14	7006+86.0	74.0′ LT	7TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-D-12	7010+50.0	76.6′ LT	7TH AVE	50'	14'	TYPE III	TYPE A	
1-D-15	7008+91.9	66.6′ RT	7TH AVE	50′	14'	TYPE III	TYPE A	
1-D-08	7013+47.2	76.5′ RT	7TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-C-07	7014+39.6	65.4' LT	7TH AVE	50'	14'	TYPE III	TYPE A	
1-C-06	644+49.0	30.6′ LT	7TH-RAMP A	50′	14′	TYPE III	TYPE A	
1-C-09	642+15.0	25.2′ RT	7TH-RAMP A	50′	14′	TYPE III	TYPE A	
1-D-05	645+83.0	41.6′ LT	7TH-RAMP A	50'	14'	TYPE III	TYPE A	
1-D-06	7013+75.0	54 . 3′ LT	7TH AVE	45′	15′	-	TYPE A	COMBINATION POLE
1-D-07	7016+50.0	39.6′ LT	7TH AVE	50′	14′	TYPE III	TYPE A	
1-C-08	7014+29.0	56.5′ RT	7TH AVE	50'	14'	TYPE III	TYPE A	
1-C-14	7008+91.9	76.6′ LT	7TH AVE	50′	14′	TYPE III	TYPE A	
1-C-15	7006+31.0	88.0′ LT	7TH AVE	50′	14′	TYPE III	TYPE A	
1-C-16	7008+55.0	98.0' RT	7TH AVE	50'	14'	TYPE III	TYPE A	
1-C-17	7006+93.0	71 . 0′ RT	7TH AVE	50′	14′	TYPE III	TYPE A	
1-C-18	7005+00.0	48.6′ LT	7TH AVE	50′	14′	TYPE III	TYPE A	

- SEE LIGHTING DETAIL SHEETS FOR POLE DETAILS
- •• TYPE A SHALL BE A LED, MEDIUM WATTAGE, 240 VOLT LUMINAIRE

NOTE 1: LIGHT POLE MOUNTED TO BARRIER WALL, BRIDGE PARAPET, OR RETAINING WALL

Alfred Benesch & Company
205 North Michigan Avenue, Suite 2400
Chicago, Illinois 60601
312-565-0450
Job No. 10064

DRAWN REVENUE THE PROPERTY OF THE PROPERTY OF

USER NAME =	DESIGNED	-	GHT	REVISED -
	DRAWN	-	JLW	REVISED -
PLOT SCALE = NO SCALE	CHECKED	-	GRR	REVISED -
PLOT DATE = 1/30/2017	DATE	-	2/5/2016	REVISED -

STATE	OF	ILLINOIS
DEPARTMENT	0F	TRANSPORTATION

		F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.			
LIGHTING QUANTITIES						(81-1)R & 81-1HVBR	ROCK ISLAND	1504	498
				CONTRACT	NO. 6	4C08			
SCALE: NO SCALE	SHEET NO. 2 OF 29	SHEETS	STA.	TO STA.		ILLINOIS FED. AID PROJECT			

