



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 12, 2023

SUBJECT: FAI Route 74A (I-74)
Project NHPP-1DSY(203)
Section (57-7)RS-3,(57-20)RS-4
McLean County
Contract No. 70G08
Item No. 38, April 28, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Revised page 66 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

| | |
|---|----|
| FUEL COST ADJUSTMENT (BDE) | 37 |
| HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)..... | 40 |
| MATERIAL TRANSFER DEVICE (BDE) | 41 |
| PERFORMANCE GRADED ASPHALT BINDER (BDE) | 42 |
| SEEDING (BDE)..... | 47 |
| SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE) | 52 |
| SPEED DISPLAY TRAILER (BDE) | 53 |
| STEEL COST ADJUSTMENT (BDE) | 54 |
| SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)..... | 56 |
| SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)..... | 57 |
| SUBMISSION OF PAYROLL RECORDS (BDE)..... | 57 |
| TRAFFIC SPOTTERS (BDE)..... | 58 |
| TRAINING SPECIAL PROVISIONS (BDE) | 59 |
| IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION...62 | |
| VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)..... | 64 |
| WEEKLY DBE TRUCKING REPORTS (BDE)..... | 64 |
| WORK ZONE TRAFFIC CONTROL DEVICES (BDE)..... | 64 |
| WORKING DAYS (BDE)..... | 66 |
| TRAFFIC BARRIER TERMINAL, TYPE 6A (MODIFIED)..... | 66 |

“(g) Truck Mounted/Trailer Mounted Attenuators. The attenuator shall be approved for use at Test Level 3. Test Level 2 may be used for normal posted speeds less than or equal to 45 mph.

(k) Temporary Water Filled Barrier. The water filled barrier shall be a lightweight plastic shell designed to accept water ballast and be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings.

(l) Movable Traffic Barrier. The movable traffic barrier shall be on the Department’s qualified product list.

Shop drawings shall be furnished by the manufacturer and shall indicate the deflection of the barrier as determined by acceptance testing; the configuration of the barrier in that test; and the vehicle weight, velocity, and angle of impact of the deflection test. The Engineer shall be provided one copy of the shop drawings. The barrier shall be capable of being moved on and off the roadway on a daily basis.”

WORKING DAYS (BDE)

Effective: January 1, 2002

The Contractor shall complete the work within **70** working days.

TRAFFIC BARRIER TERMINAL, TYPE 6A (MODIFIED)

Description This work shall consist of furnishing and erecting Traffic Barrier Terminal, Type 6A (Modified) and re-galvanizing of all exposed metal surfaces.

This work shall conform to the applicable portions of Section 631 of the Standard Specifications, Highway Standard 631032, and as shown in the plan detail for TRAFFIC BARRIER TERMINAL, TYPE 6A (MODIFIED) MOUNTING DETAIL.

This work shall also include the shop manufacturing of the GUARDRAIL CONNECTION PLATE ASSEMBLY as shown in the plan details.

The terminal shall be installed according to the manufacturer’s specifications and shall include all necessary transitions between the terminal and the items to which it is attached.

Method of Measurement The method of measurement shall be in accordance with Article 631.12 of the Standard Specifications.

Basis of Payment The basis of payment shall be the contract unit price each for TRAFFIC BARRIER TERMINAL, TYPE 6A (MODIFIED).

Revised April 12, 2023