April 18, 2023

SUBJECT FAP Route 713 (IL 61/101)
Project STP-VPAK(372)
Section (102RS-10, 119RS-3)SW,I
Hancock County
Contract No. 72G00

Item No. 44, April 28th, 2023 Letting Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

- 1. Revised pages i-ii of the Table of Contents of the Special Provisions.
- 2. Revised page 10 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

Jack A. Elston, P.E.

Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

DESCRIPTION OF PROJECT	. 1
TRAFFIC CONTROL PLAN	.2
STATUS OF UTILITIES TO BE ADJUSTED	.3
SEQUENCE OF CONSTRUCTION	.4
AGGREGATE SHOULDERS (SPECIAL)	.4
HMA SURFACE REMOVAL, 2"	.5
HOT-MIX ASPHALT SURFACE REMOVAL (VARIABLE DEPTH)	.5
PAVEMENT STATIONING NUMBERS AND PLACEMENT	.6
PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH, SPECIAL	.6
EXCAVATING AND GRADING EXISTING SHOULDER (SPECIAL)	.7
HMA ANTI-STRIP ADDITIVE REQUIREMENTS	.8
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	.8
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES	10
AUTOMATED FLAGGER ASSISTANCE DEVICES (BDE)	11
BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE)1	12
BLENDED FINELY DIVIDED MINERALS (BDE)1	13
COMPENSABLE DELAY COSTS (BDE)1	14
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE)1	17
FUEL COST ADJUSTMENT (BDE)2	25
HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE)2	28
MATERIAL TRANSFER DEVICE (BDE)2	29
PERFORMANCE GRADED ASPHALT BINDER (BDE)3	30
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE)3	35
SEEDING (BDE)3	36
SOURCE OF SUPPLY AND QUALITY REQUIREMENTS (BDE)4	11
STEEL COST ADJUSTMENT (BDE)4	12
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE)4	14
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE)4	15
SUBMISSION OF PAYROLL RECORDS (BDE)4	15
SURFACE TESTING OF PAVEMENTS – IRI (BDE)4	16
TRAINING SPECIAL PROVISIONS (BDE)5	52
DOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION5	55
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE)5	57

FAP ROUTE 713 (IL 61/101) PROJECT STP-VPAK(372) SECTION (102RS-10, 119RS-3)SW,I HANCOCK COUNTY CONTRACT NO. 72G00

WEEKLY DBE TRUCKING REPORTS (BDE)	57
WORK ZONE TRAFFIC CONTROL DEVICES (BDE)	57
WORKING DAYS (BDE)	59

FAP ROUTE 713 (IL 61/101) PROJECT STP-VPAK(372) SECTION (102RS-10, 119RS-3)SW,I HANCOCK COUNTY CONTRACT NO. 72G00

ISGS Site 4317-37 - Residence, 709 Main Street, Augusta, Hancock County

• Station 20+30 to Station 21+10 LT and RT. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

ISGS Site 4317-42 - Shed, 903 Main Street, Augusta, Hancock County

• Station 26+40 to Station 27+00 LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

ISGS Site 4317-44 - Residence, 904 Main Street, Augusta, Hancock County

• Station 30+90 to Station 31+50 LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

ISGS Site 4317-47 - Residence, 1104 Main Street, Augusta, Hancock County

 Station 35+60 to Station 36+20 LT. The Engineer has determined this material meets the criteria of and shall be managed in accordance to Article 669.05(a)(1). Contaminants of concern sampling parameters: VOCs, SVOCs, and Metals.

Work Zones

Three distinct OSHA HAZWOPER work zones (exclusion, decontamination, and support) shall apply to projects adjacent to or within sites with documented leaking underground storage tank (LUST) incidents or sites under management in accordance with the requirements of the Site Remediation Program (SRP), Resource Conservation and Recovery Act (RCRA), Comprehensive Environmental Response, Compensation and Liability Act (CERCLA), or as deemed necessary. For this project, the work zones apply for the following ISGS PESA Sites: **None**

Additional information on the contract specific work areas listed above collected during the regulated substances due-diligence process is available through the District's Environmental Studies Unit (DESU).

CONSTRUCTION PROCEDURE FOR PUBLIC EVENTS

Effective: October 1, 1990 Revised: April 14, 2020

There shall be no construction activity within the Village of Augusta on August 12-13, 2023. No broken pavement, open holes, or trenches shall remain on, or adjacent to, the traveled way during this event. Barricades, cones, drums, or other warning devices shall also be removed from the traveled way during these periods. These periods shall begin at 3:30 pm on the day preceding the beginning day of each event and end at 12:00 midnight on the final day of each event.

Any inconvenience caused to the Contractor in complying with this special provision shall be considered as incidental to the contract, and no additional compensation will be allowed.

