



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2023

SUBJECT FAP Route 112 (IL-7/53)
Project NHPP-W07U(134)
Section FAP 0112 22 BJ
Will County
Contract No. 62R93
Item No. 113, April 28, 2023 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions
2. Revised page 59 of the Special Provisions

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT	1
DESCRIPTION OF PROJECT	1
MAINTENANCE OF ROADWAYS (D1)	2
PUBLIC CONVENIENCE AND SAFETY (D1)	2
STATUS OF UTILITIES (D1)	2
TRAFFIC CONTROL PLAN (D1)	6
CONSTRUCTION LAYOUT SPECIAL FOR RESURFACING WITH ADA AND STAND ALONE ADA (D1)7	
HOT-MIX ASPHALT BINDER AND SURFACE COURSE (D1)	9
CLEANING EXISTING DRAINAGE STRUCTURES (D1)	14
ADJUSTMENTS AND RECONSTRUCTIONS (D1)	15
DRAINAGE AND INLET PROTECTION UNDER TRAFFIC (D1).....	16
CURB OR COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT (D1).....	17
ENGINEER'S FIELD OFFICE TYPE A (D1).....	19
FRICTION AGGREGATE (D1)	19
HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (D1).....	22
RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE)	23
RIGHT OF ENTRY LICENSE AGREEMENT INFORMATION	25
CERTIFICATE OF LIABILITY INSURANCE.....	30
TEMPORARY INFORMATION SIGNING	32
KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC (LANE CLOSURES ONLY)	33
TRAFFIC SIGNAL GENERAL REQUIREMENTS	34
UNDERGROUND RACEWAYS.....	45
MAINTENANCE OF EXISTING TRAFFIC SIGNAL AND FLASHING BEACON INSTALLATION.....	46
ELECTRIC CABLE.....	49
CONCRETE FOUNDATION, PEDESTRIAN POST	49
MODIFY EXISTING CONTROLLER CABINET	49
REBUILD EXISTING HANDHOLE.....	50
TRAFFIC CONTROL AND PROTECTION (ARTERIALS) (D1)	51
APPROACH SLAB REPAIR	51
TRAFFIC SIGNAL POST	56
REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES (PROJECT SPECIFIC)	57
TEMPORARY RAMP (SPECIAL)	59
TEMPORARY SUPPORT SYSTEM.....	61

Revised 4/13/2023

TEMPORARY RAMP (SPECIAL)

Description. This work shall consist of the construction and removal of temporary HMA ramps.

The ramps shall be constructed at all driveway entrances immediately upon completion of the milling operation and when the drop-off is greater than 2.5 in. (64mm). Ramps shall be 2 in. (51mm) in height by 24 in. (600mm) in width along the full width of the driveway. Work shall be to the satisfaction of the Engineer.

The contractor shall use HMA according to Section 406 of the Standard Specifications, and other applicable HMA special provisions as contained herein. The HMA mixtures to be used shall be specified in the plans.

The temporary ramps shall be removed just prior to placing the proposed binder course.

Method of Measurement. Temporary Ramp (Special) will be measured for payment in place and the area computed in square yards (square meters).

Basis of Payment. Temporary Ramp (Special) will be paid for at the contract unit price per square yard (square meter) for TEMPORARY RAMP (SPECIAL)

Revised 4/13/2023