



COMPLETE COMMODITY CODE NO. 05-6610-5310M

CODE NO.	MATERIALS	SIZE	QUAN.
(1) 05-6610-5310	PRE-CAST HANDHOLE	30"X36"	1
(2) 05-9075-5470	STONE 3/4" CRUSHED	BAG	5
(2) 05-5082-5330	SONO TUBE	30"	1
(2) 05-5082-5342	SONO TUBE	42"	1
(2) 05-3267-2940	CONC. REDI-MIX	CU. YD.	1/2
(2) 57-0770-0000	6" X 6" MESH	36"X10'	1
05-1452-9720	BRICK		24
02-4299-5524	FRAME MANHOLE	24"	1
02-4574-5040	COVER, MANHOLE	24"	1
09-7796-9312	GROUND ROD	3/4"X12'	1
09-2630-3240	GROUND CLAMP		1

- (1) PRE-CAST HANDHOLE SHALL INCLUDE CABLE HOOKS AND CONDUIT KNOCKOUTS.
- (2) THESE ITEMS ARE FOR POURED-IN-PLACE HANDHOLES ONLY.

**CONSTRUCTION NOTES:**

- 1. 8" BED OF STONE FOR DRAINAGE.
- 2. ALL METALLIC CONDUITS ENTERING HANDHOLE SHALL EXTEND MINIMUM 1" & MAXIMUM 3" INSIDE INNER WALL AND BE EQUIPPED WITH AN APPROVED TYPE OF THREADED GROUNDING BUSHING.

B	81-23-88	ADDED LABEL HOOKS PER COMMISSIONER MURPHY	ERC/ROD
A	12-8-95	REDRAW (CAD)	MP.
	DATE	REVISION	
30" DIA. CONCRETE HANDHOLE			
CITY OF CHICAGO DIVISION OF STREET AND SANITARIUM DIVISION OF ELECTRICITY DIVISION OF TRANSPORTATION			
DRAWN BY: M. PATTON	ENGINEER: D. CARTER	INVENTOR: D. DEBARTOLO	TRUCKER: D. DEBARTOLO
SUPERVISING ENGINEER:			DATE:
PROJECT NO.:			UNQ. NO.:
DRAWING NO.:			867
SCALE:	11"	1"	DATE: 12-8-95

REVISIONS	
NAME	DATE

\\p040465-p040465\elec\14-unit\90\94\2\2005\27.dwg