

62855

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
336,333	2004-110RS	MCHENRY	18	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

SUMMARY OF QUANTITIES			URBAN 1000 TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000				
CODE NO.	ITEM	UNIT		LOC. 1 IL 31	LOC. 2 IL 120			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	12	5			
40600300	AGGREGATE (PRIME COAT)	TON	17	12	5			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	17	12	5			
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	103.5	43.5	60			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	6	6				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"	SQ YD	5970	5970				
44000112	BITUMINOUS REMOVAL OVER PATCHES 3"	SQ YD	34	34				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	30	30				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	2	1	1			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	6	6				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	5	4	1			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	1	1			
67100100	MOBILIZATION	L SUM	1	0.5	0.5			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1		1			
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2802	2276	526			
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328	255	73			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	4510	3814	696			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	860	670	190			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	170	160	10			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	120	48	72			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	328	255	73			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	4510	3814	696			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	860	670	190			

SUMMARY OF QUANTITIES			URBAN 1000 TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000				
CODE NO.	ITEM	UNIT		LOC. 1 IL 31	LOC. 2 IL 120			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	170	160	10			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	120	48	72			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	151	101	50			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	151	101	50			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	426		426			
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	96	48	48			
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1201	699	502			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	140		140			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	2350		2350			

*SPECIALTY ITEMS

Rev.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 2/16/2005

08:30:58 02/16/2005

2/16/2005 12:30:58 PM 230400012