

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 341	2004-114BR	COOK	17	3

SUMMARY OF QUANTITIES

CONTRACT 62870

CODE NUMBER	DESCRIPTION	UNIT	TOTAL	URBAN SFTY-2A						
				SN 016-2436 LOC 1	SN 016-2437 LOC 2	SN 016-2438 LOC 3	SN 016-2439 LOC 4	SN 016-2441 LOC 5	SN 016-2442 LOC 6	
50102400	CONCRETE REMOVAL	CU YD	29.7		29.7					
50300225	CONCRETE STRUCTURES	CU YD	31.5		31.5					
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	8		8					
50301245	FORMED CONCRETE REPAIR (DEPTH EQUAL TO OR LESS THAN 5")	SQ FT	659	207	355	20	53	20	4	
50301250	FORMED CONCRETE REPAIR (DEPTH GREATER THAN 5")	SQ FT	36		36					
50500405 50800205	<i>Furnishing & Erecting Structural</i> REINFORCEMENT BARS, EPOXY Steel COATED	POUND	610		610					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	0.333	0.335	0.333	0.333	0.333	0.333	
67100100	MOBILIZATION	L SUM	1	0.166	0.170	0.166	0.166	0.166	0.166	
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1				0.5		0.5	
X0321316	ACCESS DOOR	EACH	1			1				
X0322467	TEMPORARY INFORMATION SIGNING FOR LANE CLOSURE	SQ FT	288	48			96	96	48	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1		0.8		0.2			
Z0031300	JACKING AND CRIBBING	L SUM	1		1					
Z0073300	TEMPORARY SHORING AND CRIBBING	L SUM	1					1		
58700200	BRIDGE SEAT SEALER	SQ. FT.	132.7		132.7					

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

Rev.