

RESURFACING SCHEDULE

LOCATION	BITUMINOUS SURFACE REMOVAL-BUTT JOINT (SQ YD)	TEMPORARY RAMP (SQ YD)	BITUMINOUS SURFACE REMOVAL, 1 1/2" (SQ YD)	BITUMINOUS SURFACE REMOVAL, (VAR DEPTH) (SQ YD)	BITUMINOUS BASE COURSE REMOVAL (SQ YD)	SUB-BASE GRANULAR MATERIAL, TYPE A 4" (SQ YD)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)	AGGREGATE (PRIME COAT) (TON)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70 (TON)	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70 (TON)	BITUMINOUS BASE COURSE SUPERPAVE 9" (SQ YD)	AGGREGATE SHOULDERS, TYPE B 6" (SQ YD)	BITUMINOUS SHOULDERS SUPERPAVE 8" (SQ YD)	MIXTURE FOR CRACKS, JOINTS, & FLANGEWAYS (TON)
229+55.00 TO 235+14.00	200.03	16.67		1707.5			152.6	3.8	162	68		544		
235+14.00 TO 236+51.50	293.45	24.69		378.6			53.8	1.3	59	10				
239+09.91 TO 239+75.00	293.68	24.98		24.9			25.5	0.6	28					
239+75.00 TO 245+63.17						234	148.4	3.7	160	115	208	699	315	0.34
245+63.17 TO 249+16.08						1058	150.6	3.8	158	132	942			0.28
249+16.08 TO 249+87.88					96	324	30.6	0.8	32	27	288			
249+87.88 TO 253+41.96						1062	151.1	3.8	159	132	944			0.29
253+41.96 TO 254+99.18						236	50.3	1.3	53	44	210	97	77	0.13
254+99.18 TO 355+48.00							2143.7	53.6	2251	1876				8.02
355+48.00 TO 358+20.00			506.7	400.0			78.7	2.0	83	47	14341	7059		
358+20.00 TO 359+15.13			117.1	293.3			37.2	0.9	45	7	290			
359+15.13 TO 359+36.80			105.9				8.3	0.2	9					
359+36.80 TO 360+91.00			314.0	293.3			57.5	1.4	66	18				
360+91.00 TO 366+04.00			1710.0				136.8	3.4	144	72				
366+04.00 TO 379+97.00			4643.3				371.5	9.3	390	195			165	
379+97.00 TO 384+97.00			1666.7				133.3	3.3	140	70				
384+97.00 TO 399+08.31			4704.4				376.3	9.4	395	198				
400+36.75 TO 401+10.00			244.2				19.5	0.5	21	10				
401+10.00 TO 403+82.00			706.7	200.0			72.5	1.8	80	30				
403+82.00 TO 404+18.00			120.0				9.6	0.2	10					
404+18.00 TO 469+69.77			20635.7	400.0			1682.8	42.1	1775	867			154	
469+69.77 TO 472+94.34		14.94	937.6				75.0	1.9	79					
474+79.72 TO 485+60.02		31.28	3120.9				249.7	6.2	262					
490+03.00 TO 502+00.00		30.05	3458.0				276.6	6.9	290					
TOTAL	787.16	142.61	42991.2	3697.6	96	2914	6491.9	162.2	6851	3918	2592	15971	7770	9.06
PAY TOTAL	787	143	42991*	3698	96	2914	6492*	162*	6851	3918	2592	15971	7770	9

* NOT A TOTAL QUANTITY

AGGREGATE SHOULDER SCHEDULE

LOCATION	AGGREGATE SHOULDERS, TYPE B (TON)	GRADING AND SHAPING SHOULDERS (UNIT)
STATION	SIDE	
234+57.98 TO 235+14.00	LT	1.2
235+14.00 TO 236+51.50	RT	2.9
235+14.00 TO 235+34.34	LT	0.4
235+72.39 TO 239+51.50	LT	1.7
239+09.91 TO 239+75.00	RT	1.4
239+09.91 TO 239+75.00	LT	1.4
239+75.00 TO 240+50.80	LT	1.6
358+00.68 TO 358+20.00	LT	0.3
358+20.00 TO 359+15.13	RT	1.4
358+20.00 TO 359+15.13	LT	1.4
359+36.80 TO 360+42.17	RT	1.5
359+36.80 TO 360+91.00	LT	2.2
360+42.17 TO 360+91.00	RT	0.7
360+91.00 TO 366+04.00	RT	7.4
360+91.00 TO 366+04.00	LT	7.4
366+04.00 TO 373+38.20	RT	10.6
366+04.00 TO 373+63.60	LT	11.0
375+41.12 TO 379+97.00	RT	6.6
375+70.30 TO 379+97.00	LT	6.2
379+97.00 TO 384+97.00	RT	7.2
379+97.00 TO 384+97.00	LT	7.2
384+97.00 TO 399+08.31	RT	20.4
384+97.00 TO 399+08.31	LT	20.4
400+36.75 TO 401+10.00	RT	1.1
400+36.75 TO 401+10.00	LT	1.1
401+10.00 TO 403+82.00	RT	3.9
401+10.00 TO 403+82.00	LT	3.9
404+18.00 TO 431+17.47	RT	38.9
404+18.00 TO 431+17.47	LT	38.9
435+55.06 TO 467+42.87	RT	46.0
435+55.09 TO 469+69.77	LT	49.3
468+46.07 TO 469+69.77	RT	1.8
TOTAL		307.4
PAY TOTAL		200.7

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION SCHEDULE OF QUANTITIES
NAME	DATE	
		FAP 317 (US ROUTE 24) SECTION 25 RS-2 & 26 RS-4 LIVINGSTON COUNTY SCALE: _____ DRAWN BY BANDY DATE _____ CHECKED BY STEUART