

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	SIDE	TEMPORARY PAVEMENT MARKING - LINE 4"		TEMPORARY PAVEMENT MARKING - LINE 6"	SHORT-TERM PAVEMENT MARKING		WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
		SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SKIP DASH YELLOW (FOOT)	(3 APPLICATIONS) (FOOT)	(4 APPLICATIONS) (FOOT)	
229+55.00 TO 236+51.50	LT		696.5				
229+55.00 TO 236+51.50	RT		696.5				574.59
229+55.00 TO 236+51.50	CENTER			175.0	209.0		
239+09.91 TO 355+48.00	LT		11638.1				
239+09.91 TO 355+48.00	RT		11638.1				9593.55
239+09.91 TO 355+48.00	CENTER			2910.0	3491.4		
355+48.00 TO 472+92.87	LT		11352.8				
355+48.00 TO 472+92.87	RT		11352.8				11074.14
355+48.00 TO 472+92.87	CENTER	6344.0		2045.0	4541.1		
474+79.72 TO 485+60.02	LT		1080.3				
474+79.72 TO 485+60.02	RT		1080.3				890.47
474+79.72 TO 485+60.02	CENTER			270.0	432.1		
490+03.00 TO 502+00.00	LT		1197.0				
490+03.00 TO 502+00.00	RT		1197.0				987.06
490+03.00 TO 502+00.00	CENTER			300.0	478.8		
TOTAL		6344.0	51929.4	5700.0	3700.4	5452.0	23119.81
PAY TOTAL		58273		5700	9152		23120

PAVEMENT MARKING SCHEDULE

LOCATION	SIDE	THERMOPLASTIC PAVEMENT MARKING - LINE 4"		THERMOPLASTIC PAVEMENT MARKING - LINE 6"	RAISED REFLECTIVE PAVEMENT MARKERS (EACH)	PAVEMENT MARKING REMOVAL (SQ FT)
		SOLID DOUBLE YELLOW (FOOT)	SOLID WHITE (FOOT)	SKIP DASH YELLOW (FOOT)		
229+55.00 TO 236+51.50	LT		696.5			
229+55.00 TO 236+51.50	RT		696.5			
229+55.00 TO 236+51.50	CENTER			175.0	3	
239+09.91 TO 355+48.00	LT		11638.1			
239+09.91 TO 355+48.00	RT		11638.1			
239+09.91 TO 355+48.00	CENTER			2910.0	37	
245+52.66 TO 249+14.48	LT					120.5
245+52.66 TO 249+14.48	RT					120.5
249+89.48 TO 253+51.30	LT					120.5
249+89.48 TO 253+51.30	RT					120.5
355+48.00 TO 472+92.87	LT		11352.8			
355+48.00 TO 472+92.87	RT		11352.8			
355+48.00 TO 472+92.87	CENTER	6344.0		2045.0	107	
474+79.72 TO 485+60.02	LT		1080.3			
474+79.72 TO 485+60.02	RT		1080.3			
474+79.72 TO 485+60.02	CENTER			270.0	4	
490+03.00 TO 502+00.00	LT		1197.0			
490+03.00 TO 502+00.00	RT		1197.0			
490+03.00 TO 502+00.00	CENTER			300.0	5	
TOTAL		6344.0	51929.4	5700.0	156	482
PAY TOTAL		58273		5700	156	482

SEEDING SCHEDULE

LOCATION	SIDE	SEEDING, CLASS 2 (ACRE)	NITROGEN FERTILIZER NUTRIENT (POUND)	PHOSPHORUS FERTILIZER NUTRIENT (POUND)	POTASSIUM FERTILIZER NUTRIENT (POUND)	MULCH, METHOD 2 (ACRE)	TEMPORARY EROSION CONTROL SEEDING (2 APPLICATIONS) (POUND)
229+55.00 TO 236+51.50	LT	0.128	11.52	11.52	11.52	0.128	25.6
229+55.00 TO 236+51.50	RT	0.235	21.15	21.15	21.15	0.235	47.0
239+09.91 TO 357+59.81	LT	2.970	267.30	267.30	267.30	2.970	594.0
239+09.91 TO 357+59.81	RT	2.753	247.77	247.77	247.77	2.753	550.6
TOTAL		6.086	547.74	547.74	547.74	6.086	1217.2
PAY TOTAL		6	540	540	540	6	1200

EROSION CONTROL SCHEDULE

LOCATION	SIDE	PERIMETER EROSION BARRIER (FOOT)	AGGREGATE (EROSION CONTROL) (TON)	EARTH EXCAVATION FOR EROSION CONTROL (CU YD)	INLET AND PIPE PROTECTION (EACH)	TEMPORARY DITCH CHECKS (EACH)
233+57.99	RT					1
242+00.00 TO 254+00.00	LT	1200				
249+51.77	RT				1	
272+22.67	LT					1
277+39.62	LT					1
278+17.61	RT					1
282+83.53	LT					1
288+62.53	LT		0.76	14.81		
289+05.44	RT				1	
295+65.59	RT					1
315+11.54	RT					1
317+97.31	LT		0.76	14.81		
317+97.31	RT				1	
339+78.04	RT					1
344+21.48	RT					1
TOTAL		1200	1.52	29.62	3	9
PAY TOTAL		1200	2	30	3	9

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES
 FAP 317 (US ROUTE 24)
 SECTION 25 RS-2 & 26 RS-4
 LIVINGSTON COUNTY
 SCALE: _____ DRAWN BY BANDY
 DATE _____ CHECKED BY STEUART