


F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-71R-3)	PEORIA	1360	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		



SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE													
				ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
M2810109	STONE RIPRAP, CLASS A5	SQ M	1,139						696	1,139	443						
M2810111	STONE RIPRAP, CLASS A6	SQ M	59		59												
M2810125	STONE RIPRAP, CLASS B3	SQ M	309		309												
M2820100	FILTER FABRIC FOR USE WITH RIPRAP	SQ M	3,623	1,448	2,402	309			696	1,139	443						
M2850100	ARTICULATED BLOCK PAVEMENT MAT	SQ M	2,402		2,402												
M3110010	SUB-BASE GRANULAR MATERIAL, TYPE A	M TON	4,894	4,892	2												
M3111010	SUB-BASE GRANULAR MATERIAL, TYPE B	M TON	252	252													
M3530240	PORTLAND CEMENT CONCRETE BASE COURSE 240MM	SQ M	8,206	8,206													
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	M TON	337.2	90.3	246.9												
M4060300	AGGREGATE (PRIME COAT)	M TON	89	89													
M4060980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ M	1,754	1,754													
M4060990	TEMPORARY RAMP	SQ M	47	47													
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	30,984	1,134	29,850												
M4205200	PROTECTIVE COAT	SQ M	134,667	7,358	127,309												
M4205050	BRIDGE APPROACH PAVEMENT(SPECIAL)	SQ M	827		827												
M4210290	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 290MM	SQ M	46,265		46,265												
M4214290	PAVEMENT REINFORCEMENT 290MM	SQ M	46,265		46,265												
M4400040	BITUMINOUS SURFACE REMOVAL 40MM	SQ M	13,970	13,970													
M4401015	BITUMINOUS SURFACE REMOVAL (COLD MILLING)	SQ M	38,282	38,282													
M4402000	PAVEMENT REMOVAL	SQ M	97,777	141	97,636												
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	3994	3,902	92												
M4402050	SIDEWALK REMOVAL	SQ M	90	90													
M4402420	MEDIAN REMOVAL	SQ M	1,329	1,329													
M4402530	PAVED SHOULDER REMOVAL	SQ M	23,819	5,376	18,443												
M4405000	PAVED DITCH REMOVAL	METER	1,293	365	928												
M4426225	CLASS B PATCHES, TYPE II, 250 MM	SQ M	767	767													
M4426245	CLASS B PATCHES TYPE II 350MM	SQ M	601	601													
M4429400	SAW CUTS	METER	2,987	2,987													
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	2,168	2,168													
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	10,180	516	9,664												
M4820000	BITUMINOUS SHOULDERS	M TON	2,683	2,683													
M4830200	PORTLAND CEMENT CONCRETE SHOULDERS - 200MM	SQ M	5		5												
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250MM	SQ M	17,597		17,597												
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290MM	SQ M	25,069		25,069												

- * SPECIALTY ITEMS
- + FUND CODE SFTY-3N
- ++ FUND CODE Y080
- +++ FUND CODE SFTY-3C
- Δ NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMP B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190 PROPOSED (EXISTING 072-0026)
- (3) RAMP B-1 & B-4 OVER RAMP A-3, B-3 & I-74, SN 072-0183 PROPOSED (EXISTING 072-0027)
- (4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005), SN 072-2030, SN 072-2032
- (5) WALL 8, SN 072-8556, WALL 8A, SN 072-8557, WALL 9, SN 072-8558, WALL 10, SN 072-8559, WALL 11, SN 072-8560, WALL 12, SN 072-8561, SN 072-2504, WALL 12B, DIFFERENTIAL HEIGHT BARRIER, BOX CULVERT, WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
- (6) WAR MEMORIAL DRIVE / STERLING / GLEN
- (7) WAR MEMORIAL DRIVE / SCENIC DRIVE
- (8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS	
NAME	DATE



ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
 FAI ROUTE 74 (I-74)
 DRAWN BY ROY
 CHECKED BY LSA
 DATE 11/23/04

11/23/04 07:15:28 AM