F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	17
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

Q01 — 95% FED 15% STATE → Q10 — 80% FED 20% STATE → Q01 →

SUMMARY OF QUANTITIES

				URBAN													
				90% FED 10% STATE											90% FED 5% STATE 5% CITY		90% FED 10% CITY
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
X0323970	UNDERPASS LUMINAIRE, (INSTALL ONLY)	EACH	29									29					
X0323971	HIGH MAST LUMINAIRE, (INSTALL ONLY)	EACH	183									183					
X0323989	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY	EACH	19	7	12												
X0323997	SIGN SUPPORT, PARAPET MOUNTED, TYPE 1	EACH	2	2													
X0324134	BATTERY BACKUP SYSTEM WITH CABINET	EACH	3												1	1	1
X4207500	CONCRETE PAVEMENT WARRANTY	L SUM	1		1												
X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	22		22												
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	22		22												
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAY)	L SUM	1		1												
X7015000	CHANGEABLE MESSAGE SIGN	CAL MO	72		72												
X8350100	LIGHT TOWER, INSTALL ONLY	EACH	34									34					
X8800020	SIGNAL HEAD, LED, 1 - FACE, 3 - SECTION, MAST ARM MOUNTED	EACH	16													10	6
X8800035	SIGNAL HEAD, LED, 1 - FACE, 3 - SECTION, BRACKET MOUNTED	EACH	9													5	4
X8800038	SIGNAL HEAD, L.E.D., 1 - FACE, 4 - SECTION, MAST ARM MOUNTED	EACH	1													1	
X8800040	SIGNAL HEAD, LED, 1 - FACE, 5 - SECTION, BRACKET MOUNTED	EACH	4													3	1
X8810610	PEDESTRIAN SIGNAL HEAD, LED, 1 - FACE, BRACKET MOUNTED	EACH	6														6
XX004187	INSTALL CONTROLLER	EACH	2									2					
Z0002600	BAR SPLICERS	EACH	250			78	84	88									
Z0013798	CONSTRUCTION LAYOUT	L SUM	1		1												
Z0018300	DRAINAGE STRUCTURE REPAIR	EACH	24		24												
+ Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1		1												
+ Z0030130	IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	1		1												
+ Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON - REDIRECTIVE) TEST LEVEL 3	EACH	3		3												
++ Z0076600	TRAINEES	HOUR	3,000		3,000												
*4001603	BITUMINOUS SURFACE REMOVAL - BUTT JOINT (SPECIAL)	SQ M	611	611													
*4001612	PIPE CULVERTS, CLASS A ,2750 MM DIAMETER (JACKED)	METER	191.0							191.0							
*4001622	DRAINAGE STRUCTURES, TYPE 1A, SPECIAL WITH ONE TYPE 20 FRAME AND GRATE	EACH	1		1												
*4001623	COMPRESSIBLE FILL MATERIAL	CU M	58							58							
*5000554	PARTIAL DEPTH PATCHING (SPECIAL)	SQ M	211	211													

* SPECIALTY ITEMS
\+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
△ NON PARTICIPATING

(1) RAMP A-3 OVER RAMP B-5, SN 072-0172
(2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190 PROPOSED (EXISTING 072-0026)
(3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183 PROPOSED (EXISTING 072-0027)
(4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005), SN 072-2030, SN 072-2032
(5) WALL 8, SN 072-8556, WALL 8A, SN 072-8557, WALL 9, SN 072-8558, WALL 10, SN 072-8559, WALL 11, SN 072-8550, WALL 12, SN 072-8561, SN 072-2504, WALL 12B, DIFFERENTIAL HEIGHT BARRIER, BOX CULVERT, WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
(6) WAR MEMORIAL DRIVE / STERLING / GLEN
(7) WAR MEMORIAL DRIVE / SCENIC DRIVE
(8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS	
NAME	DATE

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

FAI ROUTE 74 (I-74)

DATE 11/23/04

DRAWN BY RDY
CHECKED BY LSA