


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7R-3)	PEORIA	1360	25
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SET * - BILL OF MATERIALS FOR INFORMATION ONLY					URBAN IM										90 % FED 10 % STATE			90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE
					ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F	TRAFFIC SIGNALS Y031-1F		
					(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert >20	Culvert <20, R Wall					War Memorial Dr/Sterling/Olen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance		
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY																	
M281011	STONE RIPRAP, CLASS A6	SQ M	59		59															
M281025	STONE RIPRAP, CLASS B3	SQ M	309		309															
M282010	FILTER FABRIC FOR USE WITH RIPRAP	SQ M	1,448		309						1,139									
M285030	ARTICULATED BLOCK MAT	SQ M	312.8		312.8															
M311010	SUB-BASE GRANULAR MATERIAL, TYPE A	M TON	4,892	4,892																
M311010	SUB-BASE GRANULAR MATERIAL, TYPE B	M TON	252	252																
M3530240	PORTLAND CEMENT CONCRETE BASE COURSE 240MM	SQ M	8,206	8,206																
M4060200	BITUMINOUS MATERIAL (PRIME COAT)	M TON	260.4	81.6	178.8															
M4060300	AGGREGATE (PRIME COAT)	M TON	42.4	42.4																
M4060980	BITUMINOUS SURFACE REMOVAL-BUTT JOINT	SQ M	1,337	1,337																
M4202255	PORTLAND CEMENT CONCRETE PAVEMENT 250MM (JOINTED)	SQ M	27,932	1,134	26,798															
M4205200	PROTECTIVE COAT	SQ M	100,313	7,358	92,955															
M4205050	BRIDGE APPROACH PAVEMENT (SPECIAL)	SQ M	827	827																
M4210290	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 290 MM	SQ M	26,691	26,691																
M4214290	PAVEMENT REINFORCEMENT 290MM	SQ M	26,691	26,691																
M4401015	BITUMINOUS SURFACE REMOVAL (COLD MILLING)	SQ M	38,282	38,282																
M4402000	PAVEMENT REMOVAL	SQ M	69,633	141	69,492															
M4402040	COMBINATION CURB AND GUTTER REMOVAL	METER	3,902	3,902																
M4402050	SIDEWALK REMOVAL	SQ M	90	90																
M4402420	MEDIAN REMOVAL	SQ M	1,329	1,329																
M4402530	PAVED SHOULDER REMOVAL	SQ M	22,672	5,376	17,296															
M4405000	PAVED DITCH REMOVAL	METER	1,036	365	671															
M4426225	CLASS B PATCHES, TYPE II, 250 MM	SQ M	767	767																
M4429400	SAW CUTS	METER	1,704	1,704																
M4430020	STRIP REFLECTIVE CRACK CONTROL TREATMENT	METER	2,168	2,168																
M4812000	AGGREGATE SHOULDERS, TYPE B	M TON	9,156		9,156															
M4820000	BITUMINOUS SHOULDERS	M TON	1,471	1,471																
M4830250	PORTLAND CEMENT CONCRETE SHOULDERS - 250 MM	SQ M	16,143		16,143															
M4830290	PORTLAND CEMENT CONCRETE SHOULDERS - 290 MM	SQ M	15,026		15,026															
M5010430	CONCRETE HEADWALL REMOVAL	CU M	154.8	44.2	15.6							95.0								
M5010521	REMOVE EXISTING CULVERTS	METER	47	23									24							
M5010522	PIPE CULVERT REMOVAL	METER	87										87							
M5020100	STRUCTURE EXCAVATION	CU M	6,281.0			1,283	2,782						2,216							
M5030105	NEOPRENE EXPANSION JOINT 50 MM	METER	74.6			24.4	25.5	24.7												

REVISIONS	
NAME	DATE
	01/31/05

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**BILL OF MATERIALS**  
 WAR MEMORIAL DRIVE  
 FAI ROUTE 74 (I-74) (WB)  
 PLAN SET #1  
 DRAWN BY CADD  
 CHECKED BY RSC  
 DATE 11/12/04

**FOR INFORMATION ONLY**



**PARSONS**  
**TRANSPORTATION GROUP**  
 Engineers and Planners