


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7R-3)	PEORIA	1360	28
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

SET * - BILL OF MATERIALS FOR INFORMATION ONLY					URBAN IM										90 % FED 10 % STATE			90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A (WMD)	ROADWAY J000-2A (I-74)	BRIDGE (1) X271-2A A3	BRIDGE (2) X281-2A B3/B5	BRIDGE (3) X781-2A B1/B4	BRIDGE (4) X028-2A Culvert>20	MINOR STRUCTURES (5) Y007 Culvert<20, R Wall	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-IF	TRAFFIC SIGNALS Y031-IF War Memorial Dr/Sterling/Gen	TRAFFIC SIGNALS Y031-IF War Memorial Dr/Scenic Dr	TRAFFIC SIGNALS Y031-IF Scenic Dr/Mall Entrance			
M6061400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 22.30	METER	339.0	339.0																
M6061600	COMBINATION CONCRETE CURB AND GUTTER, TYPE B 22.60	METER	447.0	447.0																
M6063090	COMBINATION CONCRETE CURB AND GUTTER, TYPE M SPECIAL	METER	121.9		121.9															
M6063300	PAVED DITCH, TYPE A-15	METER	65.0		65															
M6063600	CONCRETE MEDIAN SURFACE, 100 MM	SQ M	452.1	452.1																
M6064100	CONCRETE MEDIAN, TYPE SB-15.30	SQ M	301.7	301.7																
M6064600	CONCRETE MEDIAN, TYPE SB-22.30	SQ M	335.0	335.0																
M6300100	STEEL PLATE BEAM GUARDRAIL, TYPE A	METER	804.50	75.00	729.50															
M6320030	GUARDRAIL REMOVAL	METER	1,051		1,051															
M6370140	CONCRETE BARRIER, SINGLE FACE (MODIFIED)	METER	437.8		437.8															
M6370120	CONCRETE BARRIER, DOUBLE FACE (MODIFIED)	METER	129.0		129.0															
M6380600	MODULAR GLARE SCREEN SYSTEM	METER	1,840.0		1,840.0															
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	121.0		121															
M6640480	CHAIN LINK GATES, 1.2 M X 3.3 M SINGLE	EACH	2		2															
M7030520	PAVEMENT MARKING TAPE, TYPE III 300MM	METER	43,474	21,101	22,373															
M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	835		835															
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	4,786	2,045	2,741															
M7040300	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	436.00		436.00															
M7040400	TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	3,306.00		3,306.00															
M7210105	SIGN PANEL OVERLAY, SPECIAL	SQ M	45.82	40.84	4.98															
M7800105	THERMOPLASTIC PAVEMENT MARKING - LINE 100 MM	METER	5,015	5,391	24															
M7800115	THERMOPLASTIC PAVEMENT MARKING - LINE 150 MM	METER	1,334	1,334																
M7800120	THERMOPLASTIC PAVEMENT MARKING - LINE 200 MM	METER	2,949	2,909	40															
M7800125	THERMOPLASTIC PAVEMENT MARKING - LINE 300 MM	METER	523	523																
M7800140	THERMOPLASTIC PAVEMENT MARKING - LINE 600 MM	METER	151	151																
M7800600	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ M	13	6	7															
M7802010	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 100 MM	METER	22,816	145	22,671															
M7802015	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 150 MM	METER	1,823	26	1,797															
M7802020	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 200 MM	METER	3,450	103	3,347															
M7802030	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 300 MM	METER	311	46	265															
M7802060	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 600 MM	METER	40	29	11															
M8100260	CONDUIT IN TRENCH, 50 MM DIA, PVC	METER	1,473											1,265		118	90			
M8100270	CONDUIT IN TRENCH, 65 MM DIA, PVC	METER	22													10	12			
M8100290	CONDUIT IN TRENCH, 90 MM DIA, PVC	METER	130													85	45			

P:\643996\CIVIL\SHWB\S00001-IAWB.DGN



PARSONS TRANSPORTATION GROUP
Engineers and Planners

REVISIONS	
NAME	DATE
	01/31/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
BILL OF MATERIALS
 WAR MEMORIAL DRIVE
 FAI ROUTE 74 (I-74) (WB)
 PLAN SET #1
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04