

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7R-3)	PEORIA	1360	29
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS		FED. AID PROJECT	

SET * - BILL OF MATERIALS FOR INFORMATION ONLY					URBAN IM											
					90 % FED 10 % STATE					90 % FED 5 % STATE 5% CITY		90 % FED 10 % STATE				
					ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTER-CONNECT Y031-1F	TRAFFIC SIGNALS Y031-1F
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	(WMD)	(I-74)	A3	B3/B5	B1/B4	Culvert >20	Culvert <20, R Wall			War Memorial Dr/Sterling/Glen	War Memorial Dr/Scenic Dr	Scenic Dr/Mall Entrance	
M8100300	CONDUIT IN TRENCH 100 MM DIA, PVC	METER	61													36
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	1,474									1,265		120		89
M8731220	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	METER	150													150
M8731240	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	METER	1,535												985	550
M8731250	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	METER	280												170	110
M8750490	TRAFFIC SIGNAL POST GALVANIZED STEEL 4.25 METER	EACH	1												1	
M8770025	STEEL MAST ARM ASSEMBLY AND POLE 6.70 METER	EACH	1													1
M8770730	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 7.92 METER	EACH	1												1	
M8770740	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 9.14 METER	EACH	1													1
M8770755	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 10.97 METER	EACH	1													1
M8770765	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 12.19 METER	EACH	1													1
M8770777	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 14.02 METER	EACH	1												1	
M8780100	CONCRETE FOUNDATION, TYPE A	METER	1.2												1.2	
M8780200	CONCRETE FOUNDATION, TYPE D	METER	2.4												1.2	1.2
M8780400	CONCRETE FOUNDATION, TYPE E 750 MM DIAMETER	METER	6.0												3	3
MX030199	TEMPORARY PAVEMENT	SQ M	207						207							
MX030471	FORM LINER LIMESTONE SURFACE	SQ M	993					182	150			661				
MX030472	FORM LINER GRID AND FIN SURFACE	SQ M	1,382					216	194			972				
MX030473	FORM LINER PARAPET SURFACE	SQ M	140						140							
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	M TON	371		34										337	
MX033109	DRILLING AND SETTING SOLDIER PILES	CU M	81.4									81.4				
MX033181	WATER DUST CONTROL	UNIT	395												395	
MX033182	APPLY DUST SUPPRESSION AGENTS	UNIT	998												998	
MX033183	SOIL STABILIZERS	KG	96,143												96,143	
MX033192	AGGREGATE SUB-BASE	M TON	68,812												68,812	
MX033194	WHITENASH	SQ M	88,069												88,069	
MX033206	TEMPORARY SIGN PANEL OVERLAY	SQ M	13.32						13.32							
MX033450	CONCRETE BARRIER, DOUBLE FACE (SPECIAL)	CU M	1,317.9									223.9			1,094.0	
MX033460	WET TEMPORARY PAVEMENT MARKING TAPE TYPE III 100 MM	METER	835.0												835.0	
MX032657	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER	METER	4,484.00												4,484.00	
MX402045	AGGREGATE SURFACE COURSE, TYPE B, 200 MM	SQ M	680												680	
MX406064	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "E", N70	M TON	3,717						3,717							
MX406246	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	M TON	5,575						5,575							
MX406295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL 19.0 L (LOW ESAL)	M TON	26,904						26,904							

FOR INFORMATION ONLY



REVISIONS	
NAME	DATE
	01/31/05

ILLINOIS DEPARTMENT OF TRANSPORTATION
 BILL OF MATERIALS
 WAR MEMORIAL DRIVE
 FAI ROUTE 74 (I-74) (WB)
 PLAN SET #1
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04