

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-71R-3)	PEORIA	1360	66
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BITUMINOUS PAVEMENT SCHEDULE															
LOCATION	STA	TO	STA	LENGTH M	WIDTH M	AREA (CADD CALCS) SQ M	AGGREGATE SUB-BASE M TON	BIT CONC BINDER COURSE SUPERPAVE, IL 19.0L, (LOW ESAL),150 MM M TON	BIT CONC BINDER COURSE SUPERPAVE, IL 19.0L, (LOW ESAL),100 MM M TON	POLYMERIZED BIT. CONC SURFACE COURSE, SUPERPAVE, MIX E, N70 M TON	POLYMERIZED BIT. CONC BINDER COURSE, SUPERPAVE, IL 19.0, N70 M TON	BITUMINOUS SHOULDERS 200 MM M TON	STRIP REFLECTIVE CRACK CONTROL TREATMENT METER	AGGREGATE (PRIME COAT) M TON 2kg/m2	BITUMINOUS MATERIAL PRIME COAT M TON 2l/m2 .00095 mt/l
STAGE 3															
I-74 MAINLINE, WB	141+900.000	TO	141+950.000	50.00	13.61	680.50	496.08	235.00							1.29
I-74 MAINLINE, WB	141+950.000	TO	142 + 300.000	350.00	13.61	4,763.50	3,472.59	1,644.98							9.05
I-74 MAINLINE, WB	142 + 300.000	TO	142 + 650.000	350.00	13.61	4,763.50	3,472.59	1,644.98							9.05
	142 + 300.000	TO	142 + 425.000	125.00											
	142 + 425.000	TO	142 + 610.000	185.00											
	142 + 610.000	TO	142 + 650.000	40.00											
I-74 MAINLINE, WB	142 + 650.000	TO	143 + 000.000	350.00	13.61	4,763.50	3,472.59	1,644.98							9.05
I-74 MAINLINE, WB	143 + 000.000	TO	143 + 300.000	300.00	14.21	4,263.00	3,107.73	1,474.51							8.10
Access Rd RT			10+610.000(A3)			221.65									
I-74 MAINLINE, WB	143 + 300.000	TO	143 + 650.000	350.00	14.21	4,973.50	3,625.68	1,720.26							9.45
I-74 MAINLINE, WB	143 + 650.000	TO	143 + 950.000	300.00	14.21	4,263.00	3,107.73	1,474.51							8.10
I-74 MAINLINE, WB	143 + 950.000	TO	144 + 250.000	300.00	14.21	4,263.00	3,107.73	1,474.51							8.10
	144 + 150.000		144+260.000			458.19									
I-74 MAINLINE, WB	144 + 250.000	TO	144 + 325.000	75.00	Var	1,200.75	875.35	443.91							2.28
I-74 MAINLINE, WB	144 + 325.000	TO	144 + 600.000	275.00	17.81	4,897.75	3,570.46	1,706.55							9.31
I-74 MAINLINE, WB	144 + 600.000		144 + 718.000	118.00	17.81	2,101.58	1,532.05	732.26							3.99
STAGE 3-A SUBTOTAL:								29,841	14,196	0	0	0	0	0	78
RAMPS															
Ramp A-3	10+000.000	TO	10+090.049	90.05	Var	234.13	170.68	55.96							0.44
	10+090.049	TO	10+225.000	134.95	8.1	1,093.10	796.87	261.25							2.08
	10+225.000	TO	10+390.000	165.00	9.60	1,584.00	1,154.74	378.58							3.01
Approach	10+390.000	TO	10+399.000	9.00											
Approach	10+399.000	TO	10+444.000	9.00											
	10+444.000	TO	10+453.000	9.00											
	10+453.000	TO	10+575.000	122.00	10.20	1,244.40	907.17	297.41							2.36
	10+575.000	TO	10+700.000	125.00	10.20	1,275.00	929.48	304.73							2.42
Ramp A-4	10+345.280	TO	10+371.000	25.72	2.65	68.16	49.69	16.29							0.13
	10+371.000	TO	10+490.000	119.00	2.65	315.35	229.89	75.37							0.60
	10+490.010	TO	10+635.290	145.30	2.65	385.05	280.70	92.03							0.73
Ramp B-1	10+137.966	TO	10+250.000	112.03	9.6	1,075.53	784.06	257.05							2.04
	10+250.000	TO	10+420.000	170.00	9.6	1,632.00	1,189.73	390.05							3.10
	10+420.000	TO	10+500.000	80.00	10.2	816.00	594.86	195.02							1.55
	10+500.000	TO	10+650.000	150.00	10.2	1,530.00	1,115.37	365.67							2.91
	10+650.000	TO	10+698.000	48.00	10.2	489.60	356.92	117.01							0.93
Bridge Approach	10+698.000	TO	10+707.000	9.00											
Bridge Approach	10+707.000	TO	10+850.000	9.00											
	10+850.000	TO	10+859.000	9.00											
	10+859.000	TO	10+904.000	45.00	10.2	459.00	334.61	109.70							0.87
	10+904.000	TO	10+963.000	59.00	7.55	445.45	324.73	106.46							0.85
	10+963.000	TO	11+052.000	89.00	7.55	671.95	489.85	160.60							1.28
	11+052.000	TO	11+168.669	116.67	6.95	810.85	591.11	193.79							1.54
Ramp B-2	10+074.334	TO	10+195.000	120.67	9.85	1,188.56	866.46	284.07							2.26
	10+195.000	TO	10+351.450	156.45	Var	1,835.16	1,337.83	438.60							3.49
	10+351.450	TO	10+430.000	78.55	Var	1,193.96	870.40	285.36							2.27
	10+430.000	TO	10+550.000	120.00	7.55	906.00	660.47	216.53							1.72
Gore Left B-2	10+430.000	TO	10+550.000	120.00	Var	318.00	231.82	76.00							0.60
	10+550.000	TO	10+730.000	180.00	9.6	1,728.00	1,259.71	412.99							3.28
	10+730.000	TO	10+778.000	48.00	7.55	362.40	264.19	86.61							0.69
Gore Left B-2	10+730.000	TO	10+778.000	48.00	Var	127.00	92.58	30.35							0.24
	10+778.000	TO	10+950.000	172.00	Var	928.80	677.10	221.98							1.76

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		FAI ROUTE 74 (I-74) (WB) BITUMINOUS PAVEMENT SCHEDULE DRAWN BY CADD CHECKED BY RSC DATE 11/12/04

