


F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	74
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

PERMANENT PAVEMENT MARKINGS SCHEDULE														
FAI ROUTE 74					POLYUREA PAVEMENT MARKINGS TYPE I						EPOXY PAVEMENT			
					LINE 100mm		LINE 150mm	LINE 200mm			LINE 300mm	LINE 600mm	LETTERS & SYMBOLS	
					SOLID	SOLID	DASH	SOLID	DASH	DOT	SOLID	SOLID		
					WHITE	YELLOW	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	WHITE	
LOCATIONS	STA	TO	STA	L	M	M	M	M	M	M	M	SM		

I-74 & RAMPS CONTINUED												
	143+300.00	TO	143+650.00									
I-74 EB	143+300.000		143+325.000	25		25.00	6.25	25.00				
I-74 EB	143+325.000		143+375.000	50		50.00	25.00					
I-74 EB	143+375.000		143+650.000	275	275.00	275.00	137.50					
I-74 WB	143+300.000		143+325.000	25		25.00	6.25	25.00				
I-74 WB	143+325.000		143+621.000	296	296.00	296.00	74.00					
I-74 WB	143+621.000		143+650.000	29		29.00	7.25	29.00				
RAMP A-2	10+440.000		10+465.000	25				25.00				
RAMP A-2	10+465.000		10+517.000	52	52.00							
RAMP A-3	10+172.000		10+221.000	49	49.00			49.00				
RAMP A-3	10+221.000		10+530.000	309	309.00	309.00						
A-3 GORE CHEVRONS										22.40		
RAMP B-1	10+700.000		10+905.000	205	205.00	205.00						
RAMP B-1	10+905.000		10+929.000	24		24.00		24.00				
RAMP B-1	10+929.000		10+950.000	21	21.00	21.00		42.00				
RAMP B-2	10+583.000		10+732.000	149	149.00	149.00						
RAMP B-2	10+732.000		10+754.000	22	22.00			22.00				
RAMP B-3	10+151.000		10+373.000	222	222.00	222.00						
RAMP B-4	10+192.000		10+326.000	134		134.00	33.50					
RAMP B-4	10+326.000		10+442.000	116	116.00	116.00						
RAMP B-5	10+725.000		10+905.000	180	180.00	180.00						
RAMP B-5	10+905.000		10+930.000	25	25.00			25.00				
RAMP B-6	10+271.000		10+405.000	134	134.00							
	143+650.00	TO	143+950.00									
I74EB	143+650.000		143+670.000	20	20.00	20.00	10.00					
I74EB	143+670.000		143+690.000	20		20.00	10.00					
I74EB	143+690.000		143+811.000	121		121.00	30.25	121.00				
I74EB	143+811.000		143+950.000	139	139.00	139.00	34.75					
I74WB	143+650.000		143+730.000	80		80.00		80.00				
I74WB	143+730.000		143+820.000	90		90.00			22.50			
I74WB	143+820.000		143+950.000	130	130.00	130.00						
RAMP A-3	10+000.000		10+090.000	90	90.00			90.00				
RAMP A-3	10+090.000		10+172.000	82	82.00							
A-3 GORE CHEVRONS										26.60		
RAMP B-1	10+000.000		10+020.000	20	20.00							
RAMP B-1	10+020.000		10+138.000	118	118.00			118.00				
RAMP B-1	10+138.000		10+175.000	37	37.00	37.00						
B-1 GORE CHEVRONS										81.40		
RAMP B-2	10+274.000		10+325.000	51	51.00	51.00	12.75					
RAMP B-2	10+325.000		10+430.000	105	105.00	105.00	26.25					
RAMP B-2	10+430.000		10+550.000	120	120.00			120.00				
RAMP B-2	10+550.000		10+583.000	33	33.00	33.00						
RAMP B-3	10+000.000		10+122.000	122		122.00		122.00				
RAMP B-3	10+122.000		10+151.000	29	29.00	29.00						
B-3/B-1 GORE CHEVRONS										35.10		
	10+175.000	TO	10+700.000									
RAMP B-1	10+175.000		10+490.000	315	315.00	315.00						
RAMP B-1	10+490.000		10+700.000	210	210.00	210.00						
RAMP B-4	10+442.000		10+850.000	408	408.00	408.00						

SUBTOTAL, I-74 & RAMPS (SHEET)	3,962.00	3,970.00	413.75	917.00	0.00	22.50	165.50	0.00	0.00
SUBTOTAL, I-74 & RAMPS (SHEETS 1 & 2)	7,576.00	7,528.00	1,150.50	2,229.00	0.00	191.75	208.90	10.80	6.84



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 PERMANENT PAVEMENT MARKING
 FAI ROUTE 74 (I-74) (WB)
 SCHEDULES
 DRAWN BY CADD
 CHECKED BY RSC
 DATE 11/12/04