F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	884
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET #2 BILL OF MATERIALS
FOR INFORMATION ONLY

				URBAN / IM													
				90% FED 10% STATE											90% FED 5% STATE 5% CITY		90% FED 10% CITY
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
M5500830	STORM SEWERS, CLASS A, TYPE 3 300MM	METER	23.5		23.5												
M5500900	STORM SEWERS, CLASS A, TYPE 3 1200MM	METER	15.5		15.5												
M5501265	STORM SEWERS, CLASS A, TYPE 4 600MM	METER	33.5		33.5												
M5501665	STORM SEWERS, CLASS A, TYPE 5 600MM	METER	3.5		3.5												
M5510060	STORM SEWER REMOVAL 600MM	METER	36.0		36.0												
M5510095	STORM SEWER REMOVAL 1200MM	METER	10.0		10.0												
M6010080	FRENCH DRAINS	CU M	42							42							
M6010605	PIPE UNDERDRAINS 100MM	METER	2,721.0		2,721.0												
M6010705	PIPE UNDERDRAINS 100MM (SPECIAL)	METER	142.5		142.5												
M6021405	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	1		1												
M6021410	MANHOLES, TYPE A, 1.2M DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1		1												
M6021511	MANHOLES, TYPE A, 1.2M DIAMETER, WITH MEDIAN INLET (604101)	EACH	2		2												
M6060010	CLASS SI CONCRETE (OUTLET)	CU M	14.8		14.8												
M6060270	CONCRETE GUTTER, TYPE A (MODIFIED)	METER	129.2		129.2												
M6300100	STEEL PLATE BEAM GUARD RAIL, TYPE A	METER	1,084.70		1,084.70												
M6320030	GUARDRAIL REMOVAL	METER	366		366												
M6370140	CONCRETE BARRIER, SINGLE FACE (MODIFIED)	METER	14		14												
M6420015	SHOULDER RUMBLE STRIP	METER	31,575.7		31,575.7												
M6640100	CHAIN LINK FENCE, 1.2 METER	METER	363.0		363.0												
M7030520	PAVEMENT MARKING TAPE, TYPE III 100MM	METER	14,667		14,667												
M7030540	PAVEMENT MARKING TAPE, TYPE III 150MM	METER	2,541		2,541												
M7030550	PAVEMENT MARKING TAPE, TYPE III 200MM	METER	253		253												
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ M	2,370		2,370												
M7040300	RELOCATE TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	1,698.85		1,698.85												
M7210105	SIGN PANEL OVERLAY, SPECIAL	SQ M	5.24		5.24												
M7802010	POLYUREA PAVEMENT MARKING TYPE I - LINE 100MM	METER	7,601		7,601												
M7802015	POLYUREA PAVEMENT MARKING TYPE I - LINE 150MM	METER	1,691		1,691												
M7802020	POLYUREA PAVEMENT MARKING TYPE I - LINE 200MM	METER	1,241		1,241												
M7802030	POLYUREA PAVEMENT MARKING TYPE I - LINE 300MM	METER	114		114												
MX030472	FORM LINER GRID AND FIN SURFACE	SQ M	606.5							606.5							
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	M TON	951		951												
MX032894	SLOTTED VANE DRAIN	METER	81.5		81.5												
MX032929	ENGINEERED FILL, CLASS 4	CU M	332		332												

* SPECIALTY ITEMS
\+ FUND CODE SFTY-3N
++ FUND CODE Y080
+++ FUND CODE SFTY-3C
△ NON PARTICIPATING

(1) RAMP A-3 OVER RAMP B-5, SN 072-0172
(2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
(3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN C72-0183
(4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005)
(5) WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
(6) WAR MEMORIAL DRIVE / STERLING / GLEN
(7) WAR MEMORIAL DRIVE / SCENIC DRIVE
(8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS	
NAME	DATE

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

TOTAL BILL OF MATERIALS
PLAN SET #2

FAI ROUTE 74 (I-74)

DATE 11/23/04

DRAWN BY RDY
CHECKED BY LSA