

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	085
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

SET #2 BILL OF MATERIALS FOR INFORMATION ONLY				URBAN / IM													
				90% FED 10% STATE						90% FED 5% STATE 5% CITY			90% FED 10% CITY				
				CONSTRUCTION TYPE CODE													
CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y007	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
MX033089	ENGINEERED FILL, CLASS 2	CU M	1,899		1,899												
MX033181	WATER (DUST CONTROL)	UNIT	1,254		1,254												
MX033182	APPLY DUST SUPPRESSION AGENTS	UNIT	627		627												
MX033183	SOIL STABILIZERS	KG	14,850		14,850												
MX033192	AGGREGATE SUBBASE	M TON	27,319		27,319												
MX033194	WHITEWASH	SQ M	34,120		34,120												
MX034462	REMOVAL AND DISPOSAL OF TEMPORARY CONCRETE BARRIER (STATE OWNED)	METER	2,626.05		2,626.05												
MX406295	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0L (LOW ESAL)	M TON	11,907		11,907												
MX720100	TEMPORARY SIGN PANEL ASSEMBLY	SQ M	3.25		3.25												
MX721010	COMPOSITE TEMPORARY SIGN OVERLAY	SQ M	4.45		4.45												
MZ021500	EXPANSION JOINT 75MM	METER	17.5		17.5												
MZ022800	FENCE REMOVAL	METER	594.0		594.0												
MZ031105	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ M	435.2							435.2							
MZ031107	MECHANICALLY STABILIZED EARTH RETAINING WALL WITH CAST-IN-PLACE FACING	SQ M	727.4							727.4							
X0322906	WEEP HOLES CORED	EACH	84							84							
Δ X0323677	STREET SWEEPING	HOUR	231		231												
X0323678	DUST CONTROL PADS	EACH	2		2												
X0323989	REINSTALL TEMPORARY SIGN PANEL ASSEMBLY	EACH	3		3												
Z0018300	DRAINAGE STRUCTURE REPAIR	EACH	24		24												
Z0029999	IMPACT ATTENUATOR REMOVAL	EACH	1		1												
*4001622	DRAINAGE STRUCTURES, TYPE 1A, SPECIAL WITH ONE TYPE 20 FRAME AND GRATE	EACH	1		1												
*4001623	COMPRESSIBLE FILL MATERIAL	CU M	58							58							

- * SPECIALTY ITEMS
- + FUND CODE SFTY-3N
- ++ FUND CODE Y080
- +++ FUND CODE SFTY-3C
- Δ NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
- (3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183
- (4) NORTH AND SOUTH CULVERT EXTENSION, SN 072-2005 (072-2005)
- (5) WALL 18B, SN 072-8618 (072-2005); WALL 18C, SN 072-8619 (072-2005)
- (6) WAR MEMORIAL DRIVE / STERLING / GLEN
- (7) WAR MEMORIAL DRIVE / SCENIC DRIVE
- (8) SCENIC DRIVE / MALL ENTRANCE



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
TOTAL BILL OF MATERIALS
PLAN SET #2
 FAI ROUTE 74 (I-74)
 DRAWN BY RDY
 CHECKED BY LSA
 DATE 11/23/04