

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-70R-3	PEORIA	1360	911
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

WORK ZONE PAVEMENT MARKING REMOVAL SCHEDULE						
LOCATION	TYPE	LENGTH (L)	WIDTH (W)	% REDUCTION (R) FOR SKIP DASH OR DOTTED	WORK ZONE PAVEMENT MARKING REMOVAL	
		M	MM	%	SO M	
STAGE 3-1						
FAI ROUTE 74 WESTBOUND						
STA. 144+718.000 TO STA. 144+768.208	RT EX. EDGE LINE	49.82	100	N/A	4.98	
STA. 144+718.000 TO STA. 145+050.000	RT EX. SKIP DASH	327.93	150	25	12.30	
STA. 144+718.000 TO STA. 145+050.000	RT EX. SKIP DASH	327.29	150	25	12.27	
STA. 144+718.000 TO STA. 145+050.000	RT EX. EDGE LINE	328.56	100	N/A	32.86	
STA. 144+729.909 TO STA. 144+820.430	RT EX. DOTTED	89.02	200	25	4.45	
STA. 144+820.430 TO STA. 145+050.000	RT EX. EDGE LINE	225.72	100	N/A	22.57	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	340.97	100	N/A	34.10	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	343.91	100	N/A	34.39	
STA. 145+050.000 TO STA. 145+390.000	RT EX. SKIP DASH	341.95	150	25	12.82	
STA. 145+050.000 TO STA. 145+390.000	RT EX. SKIP DASH	342.93	150	25	12.86	
STA. 145+390.000 TO STA. 145+730.000	RT EX. EDGE LINE	336.97	100	N/A	33.70	
STA. 145+390.000 TO STA. 145+730.000	RT EX. SKIP DASH	337.03	150	25	12.64	
STA. 145+390.000 TO STA. 145+730.000	RT EX. SKIP DASH	337.10	150	25	12.64	
STA. 145+390.000 TO STA. 145+650.063	RT EX. EDGE LINE	257.33	100	N/A	25.73	
STA. 145+650.063 TO STA. 145+730.000	RT EX. DOTTED	79.19	200	25	3.96	
STA. 145+730.000 TO STA. 145+907.767	RT EX. DOTTED	177.77	200	25	8.89	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	340.00	100	N/A	34.00	
STA. 145+730.000 TO STA. 146+070.000	RT EX. SKIP DASH	340.00	150	25	12.75	
STA. 145+730.000 TO STA. 146+070.000	RT EX. SKIP DASH	340.00	150	25	12.75	
STA. 145+907.767 TO STA. 146+070.000	RT EX. EDGE LINE	161.58	100	N/A	16.16	
STA. 146+070.000 TO STA. 146+410.000	RT EX. SKIP DASH	344.22	150	25	12.91	
STA. 146+070.000 TO STA. 146+410.000	RT EX. SKIP DASH	345.91	150	25	12.97	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	342.63	100	N/A	34.26	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	347.56	100	N/A	34.76	
RAMP C-1						
STA. 10+089.637 TO STA. 10+127.952	LT EX. EDGE LINE	38.48	100	N/A	3.85	
RAMP C-2						
STA. 10+379.376 TO STA. 10+469.405	LT EX. EDGE LINE	90.02	100	N/A	9.00	
STAGE 3-4						
FAI ROUTE 74 WESTBOUND						
STA. 144+718.000 TO STA. 144+768.614	RT EX. EDGE LINE	49.34	100	N/A	4.93	
STA. 144+718.000 TO STA. 146+050.000	RT EX. EDGE LINE	331.12	100	N/A	33.11	
STA. 144+718.000 TO STA. 146+050.000	RT EX. EDGE LINE	329.90	100	N/A	32.99	
STA. 144+718.000 TO STA. 146+050.000	RT EX. EDGE LINE	329.60	100	N/A	32.96	
STA. 144+718.000 TO STA. 145+050.000	RT EX. SKIP DASH	330.51	150	25	12.39	
STA. 144+718.000 TO STA. 145+050.000	RT EX. SKIP DASH	328.97	150	25	12.34	
STA. 144+768.614 TO STA. 144+859.458	RT EX. DOTTED	89.67	200	25	4.48	
STA. 144+859.458 TO STA. 145+050.000	RT EX. EDGE LINE	189.32	100	N/A	18.93	
STA. 144+859.458 TO STA. 144+932.141	RT EX. EDGE LINE	71.38	100	N/A	7.14	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	341.29	100	N/A	34.12	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	343.15	100	N/A	34.32	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	343.65	100	N/A	34.37	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	345.53	100	N/A	34.55	
STA. 145+050.000 TO STA. 145+390.000	RT EX. SKIP DASH	342.21	150	25	12.83	
STA. 145+050.000 TO STA. 145+390.000	RT EX. SKIP DASH	344.59	150	25	12.92	
STA. 145+390.000 TO STA. 145+730.000	RT EX. EDGE LINE	338.00	100	N/A	33.80	
STA. 145+390.000 TO STA. 145+730.000	RT EX. EDGE LINE	338.13	100	N/A	33.81	
STA. 145+390.000 TO STA. 145+730.000	RT EX. EDGE LINE	338.16	100	N/A	33.82	
STA. 145+390.000 TO STA. 145+730.000	RT EX. SKIP DASH	338.06	150	25	12.68	
STA. 145+390.000 TO STA. 145+730.000	RT EX. SKIP DASH	338.23	150	25	12.68	
STA. 145+390.000 TO STA. 145+650.063	RT EX. EDGE LINE	168.34	100	N/A	16.83	
STA. 145+650.063 TO STA. 145+730.000	RT EX. DOTTED	169.95	200	25	8.50	
STA. 145+730.000 TO STA. 145+805.098	RT EX. DOTTED	75.10	200	25	3.76	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	340.00	100	N/A	34.00	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	340.00	100	N/A	34.00	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	340.00	100	N/A	34.00	
STA. 145+730.000 TO STA. 146+070.000	RT EX. SKIP DASH	340.00	150	25	12.75	
STA. 145+730.000 TO STA. 146+070.000	RT EX. SKIP DASH	340.00	150	25	12.75	
STA. 145+805.098 TO STA. 146+070.000	RT EX. EDGE LINE	264.90	100	N/A	26.49	
STA. 146+070.000 TO STA. 146+410.000	RT EX. SKIP DASH	341.04	150	25	12.79	
STA. 146+070.000 TO STA. 146+410.000	RT EX. SKIP DASH	343.16	150	25	12.87	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	342.52	100	N/A	34.25	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	345.68	100	N/A	34.57	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	346.51	100	N/A	34.65	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	349.66	100	N/A	34.97	

WORK ZONE PAVEMENT MARKING REMOVAL SCHEDULE CONTINUED						
LOCATION	TYPE	LENGTH (L)	WIDTH (W)	% REDUCTION (R) FOR SKIP DASH OR DOTTED	WORK ZONE PAVEMENT MARKING REMOVAL	
		M	MM	%	SO M	
PRIOR TO PERMANENT PAVEMENT MARKINGS						
FAI ROUTE 74 WESTBOUND						
STA. 144+718.000 TO STA. 145+050.000	LT EX. EDGE LINE	334.11	100	N/A	33.41	
STA. 144+718.000 TO STA. 145+050.000	LT EX. SKIP DASH	83.30	150	N/A	12.50	
STA. 144+718.000 TO STA. 145+050.000	LT EX. SKIP DASH	83.14	150	N/A	12.47	
STA. 144+718.000 TO STA. 145+050.000	LT EX. EDGE LINE	331.90	100	N/A	33.19	
STA. 144+718.000 TO STA. 145+050.000	RT EX. EDGE LINE	330.77	100	N/A	33.08	
STA. 144+718.000 TO STA. 145+050.000	RT EX. SKIP DASH	82.53	150	N/A	12.38	
STA. 144+718.000 TO STA. 145+050.000	RT EX. SKIP DASH	82.37	150	N/A	12.36	
STA. 144+718.000 TO STA. 144+768.614	RT EX. EDGE LINE	49.82	100	N/A	4.98	
STA. 144+729.909 TO STA. 144+814.836	RT EX. DOTTED	21.12	200	N/A	4.22	
STA. 144+814.836 TO STA. 145+008.626	LT EX. DOTTED	57.50	200	N/A	11.50	
STA. 144+814.836 TO STA. 145+050.000	RT EX. EDGE LINE	233.43	100	N/A	23.34	
STA. 144+814.836 TO STA. 144+932.141	RT EX. EDGE LINE	115.38	100	N/A	11.54	
STA. 145+008.626 TO STA. 145+050.000	LT EX. EDGE LINE	82.48	100	N/A	8.25	
STA. 145+050.000 TO STA. 145+390.000	LT EX. EDGE LINE	337.09	100	N/A	33.71	
STA. 145+050.000 TO STA. 145+390.000	LT EX. SKIP DASH	84.52	150	N/A	12.68	
STA. 145+050.000 TO STA. 145+390.000	LT EX. SKIP DASH	84.77	150	N/A	12.72	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	344.90	100	N/A	34.49	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	341.96	100	N/A	34.20	
STA. 145+050.000 TO STA. 145+390.000	RT EX. SKIP DASH	85.74	150	N/A	12.86	
STA. 145+050.000 TO STA. 145+390.000	RT EX. SKIP DASH	85.98	150	N/A	12.90	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	340.05	100	N/A	34.01	
STA. 145+050.000 TO STA. 145+390.000	RT EX. EDGE LINE	132.09	100	N/A	13.21	
STA. 145+050.000 TO STA. 145+184.623	LT EX. EDGE LINE	133.65	100	N/A	13.37	
STA. 145+390.000 TO STA. 145+730.000	LT EX. EDGE LINE	337.71	100	N/A	33.77	
STA. 145+390.000 TO STA. 145+730.000	LT EX. SKIP DASH	84.45	150	N/A	12.67	
STA. 145+390.000 TO STA. 145+730.000	LT EX. SKIP DASH	84.46	150	N/A	12.67	
STA. 145+390.000 TO STA. 145+730.000	RT EX. EDGE LINE	338.04	100	N/A	33.80	
STA. 145+390.000 TO STA. 145+730.000	RT EX. SKIP DASH	84.53	150	N/A	12.68	
STA. 145+390.000 TO STA. 145+730.000	RT EX. SKIP DASH	84.55	150	N/A	12.68	
STA. 145+390.000 TO STA. 145+730.000	RT EX. EDGE LINE	337.91	100	N/A	33.79	
STA. 145+390.000 TO STA. 145+680.130	RT EX. EDGE LINE	288.37	100	N/A	28.84	
STA. 145+680.130 TO STA. 145+680.130	RT EX. EDGE LINE	120.13	100	N/A	12.01	
STA. 145+680.130 TO STA. 145+730.000	RT EX. DOTTED	12.47	200	N/A	2.49	
STA. 145+730.000 TO STA. 146+070.000	LT EX. SKIP DASH	85.00	150	N/A	12.75	
STA. 145+730.000 TO STA. 146+070.000	LT EX. SKIP DASH	85.00	150	N/A	12.75	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	340.00	100	N/A	34.00	
STA. 145+730.000 TO STA. 146+070.000	RT EX. SKIP DASH	85.00	150	N/A	12.75	
STA. 145+730.000 TO STA. 146+070.000	RT EX. SKIP DASH	85.00	150	N/A	12.75	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	340.00	100	N/A	34.00	
STA. 145+730.000 TO STA. 146+070.000	RT EX. EDGE LINE	288.27	100	N/A	28.83	
STA. 145+730.000 TO STA. 145+910.082	RT EX. DOTTED	45.02	200	N/A	9.00	
STA. 145+805.097 TO STA. 146+070.000	RT EX. EDGE LINE	264.93	100	N/A	26.49	
STA. 146+018.268 TO STA. 146+070.000	LT EX. DOTTED	12.93	200	N/A	2.59	
STA. 146+070.000 TO STA. 146+410.000	LT EX. EDGE LINE	335.05	100	N/A	33.51	
STA. 146+070.000 TO STA. 146+410.000	LT EX. SKIP DASH	84.17	150	N/A	12.63	
STA. 146+070.000 TO STA. 146+410.000	LT EX. SKIP DASH	84.58	150	N/A	12.69	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	348.56	100	N/A	34.86	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	343.62	100	N/A	34.36	
STA. 146+070.000 TO STA. 146+410.000	RT EX. SKIP DASH	86.32	150	N/A	12.95	
STA. 146+070.000 TO STA. 146+410.000	RT EX. SKIP DASH	86.73	150	N/A	13.01	
STA. 146+070.000 TO STA. 146+410.000	RT EX. EDGE LINE	339.95	100	N/A	34.00	
STA. 146+070.000 TO STA. 146+410.985	LT EX. DOTTED	8.20	200	N/A	1.64	
RAMP C-3						
STA. 10+032.813 TO STA. 10+370.000	EX. EDGE LINE	337.20	100	N/A	33.72	
STA. 10+084.354 TO STA. 10+200.099	LT EX. EDGE LINE	115.74	100	N/A	11.57	
STA. 10+200.099 TO STA. 10+370.000	LT EX. EDGE LINE	170.40	100	N/A	17.04	
STA. 10+370.000 TO STA. 10+598.650	EX. EDGE LINE	228.77	100	N/A	22.88	
STA. 10+370.000 TO STA. 10+598.650	LT EX. EDGE LINE	229.08	100	N/A	22.91	
STA. 10+553.775 TO STA. 10+598.650	LT EX. DOTTED	11.22	200	N/A	2.24	