F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	PEORIA	1360	1010
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

* DS2-03, DS2-05, DS2-09, DS2-12, DS2-17

SIGN NUMBER	*	
WIDTH x HGHT.	2070mm x 300mm	
BORDER WIDTH		
CORNER RADIUS		
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Orange
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	Black

SYMBOL	X	Y	WID	HT

Dimensions are in mm

Letter spacings are to start of next letter

LETTER POSITIONS (X)

	R	A	M	P		C	L	O	S	E	D		LENGTH	SERIES-SIZE
72	175	208	205	137	200	175	162	181	185	162	136	72	1926	D200



SIGN NUMBER	DS2-04, DS2-13	
WIDTH x HGHT.	600mm x 480mm	
BORDER WIDTH	15mm	
CORNER RADIUS	50mm	
MOUNTING	Ground	
BACKGROUND	TYPE:	Reflective
	COLOR:	Orange
LEGEND/BORDER	TYPE:	Reflective
	COLOR:	Black

SYMBOL	X	Y	WID	HT

Dimensions are in mm

Letter spacings are to start of next letter

LETTER POSITIONS (X)

	R	A	M	P																LENGTH	SERIES-SIZE
116	90	102	108	70	116															370	C125
	C	L	O	S	E	D															
40	90	86	94	96	84	71	39													521	C125

DS2-03
COMPOSITE TEMPORARY SIGN OVERLAY, 0.62 SQ M.
GALE AVENUE RT. STA. 99+575.00.

DS2-05
COMPOSITE TEMPORARY SIGN OVERLAY, 0.62 SQ M.
GALE AVENUE RT. STA. 99+861.000.

DS2-09
COMPOSITE TEMPORARY SIGN OVERLAY, 0.62 SQ M.
GALE AVENUE LT. STA. 100+156.000.

DS2-12
COMPOSITE TEMPORARY SIGN OVERLAY, 0.62 SQ M.
GALE AVENUE LT. STA. 100+144.000.

DS2-17
COMPOSITE TEMPORARY SIGN OVERLAY, 0.62 SQ M.
GALE AVENUE LT. STA. 100+470.000.

DS2-04
TEMPORARY SIGN PANEL ASSEMBLY, 0.29 SQ M.
GALE AVENUE RT. STA. 99+800.000.

DS2-13
TEMPORARY SIGN PANEL ASSEMBLY, 0.29 SQ M.
GALE AVENUE LT. STA. 100+237.000.

REVISIONS	
NAME	DATE

CLARK ENGINEERS, INC.

ILLINOIS DEPARTMENT OF TRANSPORTATION

SIGN PANEL DETAILS

DRAWN BY RDY

DATE 11/23/04

CHECKED BY LSA