

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	172-7DR-3	PEORIA	1360	1334
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
68200				

ITS BILL OF MATERIALS

DESCRIPTION	UNIT	TOTAL QUANTITY	SCHEDULE OF QUANTITIES	
			MDS-174-02	FO LINK
SERVICE INSTALLATION, TYPE B	EACH	1	1	
HEAVY-DUTY HANDHOLE	EACH	3	2	1
CONDUIT IN TRENCH, 50MM DIA., PVC	METER	204.0	56.0	148.0
CONDUIT PUSHED, 50MM DIA., PVC	METER	178.0	100.0	78.0
TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	120.5	46.5	74.0
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	METER	109.0	109.0	
CONCRETE FOUNDATION, TYPE E 600MM DIAMETER	METER	2.5	2.5	
NONINTRUSIVE DETECTOR POLE 9.1 METER	EACH	1	1	
ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C	METER	109.0	109.0	
POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1	1	

FOR INFORMATION ONLY

ITS SHEET 3 OF 13

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
ITS PLAN

BILL OF MATERIALS

SCALE
DATE 11/02/04

DRAWN BY MJL
CHECKED BY GFR

