

68200 3

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(72-7)R-3	PEORIA	1360	1347
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

BILL OF MATERIALS FOR PLAN SET #4
FOR INFORMATION ONLY

URBAN / IM

90% FED
10% STATE

90% FED
5% STATE 5% CITY

90% FED
10% CITY

CONSTRUCTION TYPE CODE

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	ROADWAY J000-2A	BRIDGE (1) X271-2A	BRIDGE (2) X281-2A	BRIDGE (3) X781-2A	BRIDGE (4) X028-2A	MINOR STRUCTURES (5) Y00T	OVERHEAD SIGNS Y002-1C	LIGHTING Y030-1E	ITS Y035	TRAFFIC SIGNAL INTERCONNECT (6) Y031-1F	TRAFFIC SIGNALS (6) Y031-1F	TRAFFIC SIGNAL INTERCONNECT (7) Y031-1F	TRAFFIC SIGNALS (7) Y031-1F	TRAFFIC SIGNAL INTERCONNECT (8) Y031-1F	TRAFFIC SIGNALS (8) Y031-1F
63100167	TRAFFIC BARRIER TERMINAL, TYPE I SPECIAL (TANGENT)	EACH	2	2															
78100100	RAISED REFLECTIVE PAVEMENT MARKERS	EACH	82	82															
78201000	TERMINAL MARKER DIRECT APPLIED	EACH	2	2															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	82	82															
86301000	TERMINAL FACILITY	EACH	1	1															
M4060200	BITUMINOUS MATERIALS (PRIME COAT)	MTON	8.7	8.7															
M4060300	AGGREGATE (PRIME COAT)	MTON	47	47															
M4060980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ.M	417	417															
M4060990	TEMPORARY RAMP	SQ.M	47	47															
M4400040	BITUMINOUS SURFACE REMOVAL 40 MM	SQ.M	13,970	13,970															
M4426245	CLASS B PATCHES TYPE II 350 MM	SQ.M	601	601															
M4429400	SAW CUTS	METER	1283	1283															
M4812000	AGGREGATE SHOULDERS, TYPE B	MTON	516	516															
M4820000	BITUMINOUS SHOULDERS	MTON	1212	1212															
M6320030	GUARDRAIL REMOVAL	METER	23	23															
M6330610	REMOVE AND RE-ERECT STEEL PLATE BEAM GUARDRAIL	METER	556	556															
M7030100	SHORT TERM PAVEMENT MARKING	METER	987	987															
M7030220	TEMPORARY PAVEMENT MARKING - LINE 100 MM	METER	3995	3995															
M7030240	TEMPORARY PAVEMENT MARKING - LINE 150 MM	METER	500	500															
M7031000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ.M	30	30															
M7802010	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 100 MM	METER	3995	3995															
M7802015	POLYUREA PAVEMENT MARKING TYPE 1 - LINE 150 MM	METER	500	500															
M8100240	CONDUIT IN TRENCH, 30 MM DIA., PVC	METER	39	39															
M8150205	TRENCH AND BACKFILL FOR ELECTRICAL WORK (SPECIAL)	METER	10	10															
M8731510	ELECTRIC CABLE IN CONDUIT, LEAD IN, NO. 18 3 PAIR	METER	45	45															
M8150200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	METER	33	33															
M8860400	DETECTOR LOOP, SPECIAL	METER	46	46															
MX032083	GUARDRAIL AGGREGATE EROSION CONTROL	MTON	111	111															
MX406066	POLYMERIZED BIT CONC SURFACE COURSE, SUPERPAVE, MIX E, N90, 38MM	MTON	1328	1328															
MX406248	POLYMERIZED BIT CONC BINDER COURSE, SUPERPAVE, IL 19.0, N90, 57MM	MTON	1992	1992															
MZ017205	DOWEL BARS 38 MM	EACH	1740	1740															
*4001603	BITUMINOUS SURFACE REMOVAL - BUTT JOINT (SPECIAL)	SQ.M	611	611															
*5000554	PARTIAL DEPTH PATCHING (SPECIAL)	SQ.M	211	211															

- * SPECIALTY ITEMS
- + FUND CODE SFTY-3N
- ++ FUND CODE Y080
- +++ FUND CODE SFTY-3C
- Δ NON PARTICIPATING

- (1) RAMP A-3 OVER RAMP B-5, SN 072-0172
- (2) RAMPS B-3 & B-5 OVER US 150 & RAMP B-6, SN 072-0190
- (3) RAMPS B-1 & B-4 OVER RAMPS A-3, B-3 & I-74, SN 072-0183
- (4) SN 072-2005, 072-2030 & 072-2032
- (5) SN 072-8618 & SN 072-8619
- (6) WAR MEMORIAL DRIVE / STERLING / GLEN
- (7) WAR MEMORIAL DRIVE / SCENIC DRIVE
- (8) SCENIC DRIVE / MALL ENTRANCE

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

BILL OF MATERIALS
FAI ROUTE 74 (I-74)

DATE 9/29/04

DRAWN BY CEM
CHECKED BY CEM

c:\p\projects\174mb-cl0-800.dgn