COUNTY TOTAL SHEET NO.
TAZEWELL 1366 156 RTE. SECTION TO STA. FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT \*(90-11)R-2;90(13,14,14-1)R-1 13.300 m -1.200m \_\_ 1.200m 3.300 m 3.300 m 3.300 m 3.300 m SOUTHBOUND NORTHBOUND THRU THRU 3.600 m 3.600 m -BITUMINOUS REMOVAL (25 MM) BINDER COURSE (50 MM) - SEE NOTE 1 BARRICADES OR DRUMS WITH MONO DIRECTIONAL, STEADY BURN LIGHTS TEMPORARY PAVEMENT MARKING LINE - 100 mm, WHITE TEMPORARY PAVEMENT PLACED DURING STAGE 3A-1 TEMPORARY PAVEMENT MARKING LINE - 100 mm, DOUBLE YELLOW FLEXIBLE DELINEATORS NORTH MAIN ST MOT TYPICAL SECTION NO. 9A (9A) STA. 2+800,000 TO STA. 3+023.295 BEGIN RESURFACE AND WIDENING VAR 13.300 m TO 11.450 m 1.200m 3.300 m 3.300 m 3.300 m 3.300 m 3.300 m SOUTHBOUND SOUTHBOUND NORTHBOUND THRU VAR 4.800 m 3.600 m BITUMINOUS REMOVAL (25 MM) BINDER COURSE (50 MM) SEE NOTE 1 BARRICADES OR DRUMS WITH MONO DIRECTIONAL STEADY BURN LIGHTS TEMPORARY PAVEMENT MARKING LINE - 100 mm, WHITE TEMPORARY PAVEMENT PLACED DURING STAGE 3A-1 TEMPORARY PAVEMENT MARKING LINE - 100 mm, DOUBLE YELLOW FLEXIBLE DELINEATORS NOTES: 1. USE DISTRICT 4 STANDARD 602401-D4, TEMPORARY INLET DRAINAGE TREATMENT 2. BINDER COURSE IS TO BE PLACED IN WORKZONE AREAS AS SHOWN NORTH MAIN ST MOT TYPICAL SECTION NO. 10A STA. 3+023.295 TO STA. 3+103.295 DATE ILLINOIS DEPARTMENT OF TRANSPORTATION FAI ROUTE 74 (I-74) MAINTENANCE OF TRAFFIC STAGE 3A-2 **URS** ILL. 116-U.S. 150-NORTH MAIN ST. TYPICAL SECTIONS 9A & 10A

DRAWN BY MRF CHECKED BY RTG

DATE 12/20/2004