F.A.I. RTE.	SECTION	COUNTY	TOTAL	SHEET NO.
74	(90-11)R-2;90 (13,14,14-1)R-1	TAZEWELL	1366	1328
STA.		TO STA.		
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT				ECT
68201				

ITS BILL OF MATERIALS

DESCRIPTION		TOTAL QUANTITY	SCHEDULE OF QUANTITIES	
			MDS-I74-01B	HRI-MN(EP)-03
SERVICE INSTALLATION, TYPE B	EACH	1		1
HEAVY-DUTY HANDHOLE	EACH	1	1	
CONCRETE HANDHOLE	EACH	1		1
CONDUIT IN TRENCH, 50MM DIA., PVC	METER	21.0	13.0	8.0
CONDUIT PUSHED, 50MM DIA., PVC		208.0	153.0	55.0
TRENCH AND BACKFILL FOR ELECTRICAL WORK		14.5	6.5	8.0
ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C		177.0	105.0	72.0
CONCRETE FOUNDATION, TYPE E 600MM DIAMETER		2.5	2.5	
NONINTRUSIVE DETECTOR POLE 9.1 METER		1.0	1	
ELECTRIC CABLE IN CONDUIT, GROUNDING, NO. 6 1C		177.0	105.0	72.0
POLE MOUNTED EQUIPMENT CABINET, TYPE B		1	1	
POLE MOUNTED EQUIPMENT CABINET, TYPE C		1		1
HIGHWAY-RAIL INFORMATION SIGN	EACH	1		1

FOR INFORMATION ONLY

ITS SHEET 3 OF 13

REVISIONS
NAME DATE

BILL OF MATERIALS

FORWARDS

SCALE DRAWN BY MJL
DATE 12/20/04 CHECKED BY CJH