815 Commerce Drive Suite 200 Oak Brook, Illinois 60523 Telephone: 630.990.3800 Fax: 630.990.3801



CITY OF DIXON, ILLINOIS

Post Office Box 386 Dixon, Illinois 61021 Telephone: 815.288.1485

DIXON MUNICIPAL AIRPORT CHARLES R. WALGREEN FIELD

OVERLAY TAXIWAYS B, D AND E: REHABILITATE FRONTAGE APRON PAVEMENT

AIP PROJECT NO. 3-17-0036-B7 IDA PROJECT NO. C73-3436

| i | | |
|----|------|----------------|
| + | | † |
| -+ | | ╁ |
| | | + |
| | | _ |
| | | |

Date

11 MARCH 2005

Sheet Title

COMBINED SUMMARY OF QUANTITIES

| 843-04B8007 | | | | | | |
|---------------------|------|----------|--|--|--|--|
| Project Numbe | er | | | | | |
| KLK | 02, | 02/03/05 | | | | |
| Layout By | Date | | | | | |
| KLK,TMM | 02 | /03/05 | | | | |
| Designed By Date | | | | | | |
| RMH <u>03/11/05</u> | | | | | | |
| Reviewed By | Date | | | | | |
| KLK - | | | | | | |

2

lo.

COMBINED SUMMARY OF QUANTITIES

OVERLAY TAXIWAYS B, D AND E; REHABILITATE FRONTAGE APRON PAVEMENT

| | , Ilem | Quantity | | |
|----------|----------------------------------|-------------|---------|--|
| Number | Description | Unit | As Bid | Record Paid |
| AR125100 | Elevated Retroflective Marker | Each | 82.0 | |
| \R150510 | Engineer's Field Office | Lump Sum | 1.0 | 77 25 27 38 APR |
| \R150540 | Haul Route | Lump Sum | 1.0 | |
| AR152410 | Unclassified Excavation | Cubic Yard | 2,090.0 | |
| AR156510 | Silt Fence | Linear Foot | 464.0 | |
| AR156513 | Separation Fabric | Square Yard | 1,756.0 | |
| H201610 | Bituminous Base Course | Ton | 168.0 | |
| AR201620 | Bituminous Base Course, Leveling | Ton | 890.0 | |
| AR209608 | Crushed Agg. Base Course - 8" | Square Yard | 1,756.0 | |
| \R401610 | Bituminous Surface Course | Ton | 954.0 | |
| \R401650 | Bituminous Pavement Milling | Square Yard | 1,754.0 | |
| \R401665 | Bituminous Pavement Sawing | Linear Foot | 1,227.0 | |
| AR401900 | Remove Bituminous Pavement | Square Yard | 1,855.0 | in the state of the |
| AR602510 | Bituminous Prime Coat | Gallon | | |
| NR603510 | Bituminous Tack Coat | Gallon | 2,967.0 | - 10 m |
| \R620525 | Pavement Marking - Black Border | Square Foot | 1,209.0 | |
| AR620530 | Pavement Marking - Epoxy | Square Foot | 3,745.0 | |
| AR701418 | 18" RCP, Class III | Linear Foot | 101.0 | |
| AR701430 | 30' RCP, Class III | Linear Foot | 92,5 | |
| NP701512 | 12" RCP, Class IV | Linear Foot | 112.0 | |
| AR701515 | 15' RCP, Class IV | Linear Foot | 275.0 | |
| AR705412 | Porous Backfill No. 2 | Cubic Yard | 26.0 | |
| \R705504 | 4" Perforated Underdrain | Linear Foot | 491.5 | FF STERNAL |
| \R705640 | Underdrain Cleanout | Each | 1.0 | |
| \R751540 | Manhole 4' | Each | 10 | |
| AR751550 | Manhole 5' | Each | 2.0 | |
| NR751560 | Manhole 6' | Each | 10 | |
| AR800961 | Granular Drainage Subbase - 12" | Square Yard | 1,756.0 | |
| AR800962 | RAP Subbase - From On-site | Cubic Yard | 14.0 | |
| \R800963 | RAP Subbase - From Off-site | Cubic Yard | 818.0 | |
| 4R800972 | Bituminous Sand Mix - 2" | Square Yard | 741.0 | |
| AR800973 | Crack Control Material | Linear Foot | 1,539,0 | |
| AR901510 | Seeding | Acre | 1.8 | |
| 4R905520 | Topsoiling (From Off Site) | Cubic Yard | 490.0 | Section and an artist of the section |
| AR908510 | Mulching | Acre | 1.8 | |

NOTE

QUANTITIES ON THIS SHEET REPRESENT THE **COMBINED SUMMARY OF QUANTITIES** FOR THE **DVERLAY**TAXIWAYS B, D AND E AND REHABILITATE FRONTAGE APRON PAVEMENT. FOR INDIVIDUAL QUANTITIES,

SEE THE RESPECTIVE SUMMARY OF QUANTITY SHEETS INCLUDED IN EACH SECTION.