815 Commerce Drive Suite 200 Oak Brook, Illinois 60523 Telephone: 630.990.3800 Fax: 630.990.3801



CITY OF DIXON, ILLINOIS

Post Office Box 386 Dixon, Illinois 61021 Telephone: 815.288.1485

DIXON MUNICIPAL AIRPORT CHARLES R. WALGREEN FIELD

OVERLAY TAXIWAYS B, D AND E: REHABILITATE FRONTAGE APRON PAVEMENT

AIP PROJECT NO. 3-17-0036-B7 IDA PROJECT NO. C73-3436

			∔
\vdash			1
			⊥
			L
			L
			Ι
			Ι
			Ι
			Ι
No.	Drawing Issue Description	Date	Τe

Dat

11 MARCH 2005

Sheet Title

SUMMARY OF QUANTITIES -SECTION 2

843-04B	8007
Project Number	
KLK	02/03/05
Layout By	Date
KLK,TMM	02/03/05
Designed By	Date
RMH	03/11/05
Reviewed By	Date

46

st No.

SUMMARY OF QUANTITIES - SECTION 2

REHABILITATE FRONTAGE APRON PAVEMENT

	ltem .		Quantity	
Number	Description	Unit	As Bid	Record Paid
AR152410	Unclassified Excavation	Cubic Yard	2,090.0	
AP(156510	Silt Fence	Linear Foot	64.0	
AR156513	Separation Fabric	Square Yard	1,756.0	1-act 72 d
AR201610	Bituminous Base Course	Ton	168.0	
AR209608	Crushed Agg, Base Course - 8"	Square Yard	1,756.0	
AR401610	Bituminous Surface Course	Ton	190.0	
AR401650	Bituminous Pavement Milling	Square Yard	329.0	
AR401665	Bituminous Pavement Sawing	Linear Foot	869.0	
AR401900	Remove Bituminous Pavement	Square Yard	1,855.0	
AR602510	Bituminous Prime Coat	Gallon	583.0	
AR603510	Bituminous Tack Coat	Gallon	328.0	
AR701418	18" RCP, Class III	Linear Foot	101.0	A Andrew Accord
AR701430	30" RCP, Class III	Linear Foot	92.5	
AR701512	12* RCP, Class IV	Linear Foot	112.0	
AR701515	15' RCP, Class IV	Linear Foot	275.0	gal Si Si Silangan
AR705412	Porous Backfill No. 2	Cubic Yard	26.0	
AR705504	4' Perforated Underdrain	Linear Foot	491.5	
AR705640	Underdrain Cleanout	Each	1.0	
AP751540	Manhole 4'	Each	1.0	4.5
AR751550	Manhole 5'	Each	2.0	and the second
AR751560	Manhole 6'	Each	1.0	
AR800961	Granular Drainage Subbase - 12'	Square Yard	1,756.0	142 ALAS ASSAULT
AR800962	RAP Subbase - From On-site	Cubic Yard	14.0	
AR800963	RAP Subbase - From Off-site	Cubic Yard	818.0	
AR901510	Seeding	Acre	0.3	
AR905520	Topsolling (From Off Site)	Cubic Yard	75.0	a construction of the second
AR908510	Mulching	Acre	0.3	

NOTE

QUANTITIES ON THIS SHEET REPRESENT THE REHABILITATE FRONTAGE APRON PAVEMENT QUANTITIES ONLY.